

AFNOR/FE ELECTRONIC INVOICING COMMISSION

French standardization

Document reference

PR XP Z12-012

**Formats and profiles for invoice messages and life cycle statuses,
constituting the minimum requirements applicable to the Electronic
Invoice Reform in France**

Version 1.4 of June 30th, 2026

Only the verb forms **must** and **shall** are used to express one or more requirements that must be met in order to comply with this document. For test methods, the use of the infinitive corresponds to a requirement.

Published and distributed by the Association Française de Normalisation (AFNOR) - 11, rue Francis de Pressensé - 93571

La Plaine Saint-Denis Cedex Tel.: + 33 (0)1 41 62 80 00 - Fax: + 33 (0)1 49 17 90 00 - www.afnor.org

© AFNOR — All rights reserved

Table of contents

Introduction.....	10
1 Scope	11
2 Normative references	11
3 Terms and definitions	12
4 Minimum electronic invoice formats and profiles	15
4.1 European Semantic Standard EN16931	15
4.2 Implementations of the two profiles EN16931 and EXTENDED-CTC-FR	19
4.2.1 The need to offer several semantic profiles in the minimum base	19
4.2.2 Implementation in UBL and UN/CEFACT CII syntaxes requires a specific description.....	20
4.3 Summary description of the semantic data structure of the two profiles	20
4.3.1 The EN16931 profile	20
4.3.2 The EXTENDED-CTC-FR profile	24
4.3.3 Evolution of the EN16931 standard.....	28
4.3.4 Factur-X EXTENDED profile and evolution of the EXTENDED-CTC-FR profile	29
4.4 Special points to note	29
4.4.1 Data types	29
4.4.2 Profile data management and invoicing framework	30
4.4.3 Management of Notes	31
4.4.4 Credit note management	31
4.4.5 Calculation rules.....	32
4.4.6 Rounding rules in calculations	33
4.4.7 VAT management	34
4.4.8 Management of taxes other than VAT, case of the WEEE eco-contribution	34
4.4.9 Management of allowances and charges.....	35
4.4.10 Code Management.....	36
4.4.11 Management of sub-lines in the EXTENDED-CTC-FR profile (and EXTENDED in Factur-X).....	36
4.4.12 Multi-seller invoices.....	39
4.4.13 Bidirectional self-billing invoices (self-billing)	45
4.5 Additional specific management rules under the French reform.....	47
4.5.1 Additional control rules for compliance with regulation in France	48
4.5.2 Mapping rules for creating flows 1 and 10.1	55
4.5.3 CPRO control rules for B2G invoices to the public sector	59
4.5.4 Specific management rules for multi-seller invoices and bidirectional self-billing	65
4.6 Rule for creating a readable representation of an electronic invoice under this Standard.	70
4.6.1 Building a readable representation model	70
4.6.2 How to represent data in the form of codes.....	71
4.6.3 Factur-X and structured invoices with an attached readable presentation	71
4.6.4 Examples	72
4.7 Conversions between base formats.....	74
4.8 Presentation of the annex file describing the minimum invoice formats.....	74
4.8.1 Sheet "FE EN16931 + EXTENDED"	76
4.8.2 Sheet "BR-France CTC"	76
4.8.3 Sheet "BR-France-CTC-CPRO"	77
4.8.4 Sheet "BR EN16931 + EXT FR and FX"	77
4.8.5 Sheet "Codelists for XML Fx - 15 05 26"	78
4.8.6 Sheets "Flux 2 UBL EN16931 FR" and "Flux 2 UBL EXT-CTC-FR"	79
4.8.7 Leaves "FACTUR-X BASIC WL FR," "CII D22B & FX EN16931 FR," and "CII D22B & FX EXT-CTC-FR)	80
4.8.8 Sheets "FE - Flow 1," "Flow 1 UBL," and "Flow 1 CII"	84
4.8.9 Sheet "E-REPORTING - Flow 10"	85
4.8.10 Sheet "Flux F11 – Annuaire"	85
4.8.11 Sheet "Management Rules 3.2"	85
5 The Life cycle Message – CDAR	86

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

5.1	Description of the CDAR message structure to be used.....	86
5.2	Applicable management rules.....	94
5.3	Reasons for life cycle statuses.	98
5.4	Presentation of the annex file for CDAR sheets	98
5.4.1	Sheet "CDV FE – CDAR"	98
5.4.2	Sheet "BR-FR-CDV for invoices"	99
5.4.3	Sheet "CDV actors"	99
5.4.4	Sheet "Action codes"	99
5.4.5	Sheet "STATUS reasons table"	99
	Annexe A (normative) Excel description of formats and profiles.....	101
	Annexe B (normative) Examples of invoices (flow 2) and CDAR life cycle messages.....	102
	Bibliography.....	103

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

Preliminary notes

As part of the reform, the term “Partner Dematerialization Platform (PDP)” has been replaced by “Plateforme Agréée (PA, Accredited Platform)” and the term “Dematerialization Operator (OD)” has been replaced by “Solution Compatible (SC)”.

Foreword

This document is intended for all organizations that wish to exchange electronic invoices in the context of French regulations (Electronic Invoice Reform as described in Articles 289, 289BIS, 290 and 290A of the General Tax Code), but also more broadly in compliance with the provisions of Directive 2006-112-EC, amended by EU Directive 2025/516 known as ViDA (VAT in the Digital Age).

This document deals with the formats and profiles of Invoice and Life Cycle Status messages, which constitute the minimum basis applicable to the Electronic Invoice Reform in France.

This document is not intended to detail use cases, which will be published separately.

This document describes the formats and profiles applicable in the context of the electronic invoicing reform in France:

- On the one hand, with regard to invoice messages, in accordance with the European Semantic Standard for electronic invoicing EN16931
- On the other hand, for the life cycle status message implemented from the UN/CEFACT Cross Domain Acknowledgement and Response (CDAR) message

Knowledge of the EN16931 standards, as well as the UBL, UN/CEFACT CII and UN/CEFACT CDAR implementation syntaxes, is an essential prerequisite for reading this document.

Attached to this document is an Excel file containing a detailed description of the formats and profiles, as well as their implementations in the UBL, UN/CEFACT CII and UN/CEFACT CDAR syntaxes, the associated management rules and the applicable code lists.

This document is intended to evolve, particularly in the description of the EXTENDED-CTC-FR profile for the Invoice message and in that of the life cycle status message, in line with the work of the AFNOR Commission and in support of the operational roll-out of the Electronic Invoice Reform in France and the implementation of the widespread use of electronic invoicing in the European Union and beyond.

VERSION MANAGEMENT

Version No.	Version Date	Description of changes
V1.0	2025 05 07	Initial version
V1.1	2025 07 31	Some editorial corrections in the foreword, introduction, and definition 3.6 of "e-reporting." Chapter 4.2: paragraphs added to better explain formats and profiles and clarify the use of Factur-x profiles. Chapter 4.3: addition of reminders to the regulatory texts for "Delivered to" and "Purchase order"/Clarifications on the use of BT-8. Chapter 4.4.3: addition of the DCL code (BT-21) as a note for the reference "invoice issued by A on behalf of and for B" (in the case of an invoicing mandate). Chapter 4.4.8: addition of a paragraph on the management of parafiscal

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

Version No.	Version Date	Description of changes
		taxes based on a GS1 (GTIN) nomenclature. Rule BR-FR-02: deletion of "space as an accepted character " in an invoice identifier (BT-1). Rules BR-FR-12 and BR-FR-13: clarification and addition of rules BR-FR-21 and BR-FR-22 to describe additional rules for checking the format of electronic addresses based on the presence of a note with a BAR subject code used to qualify the type of processing expected (e-invoicing, e-reporting, non-reform, etc.). Rule BR-FR-17: addition of an attachment type value (RECAPITULATIF_COTRAITANCE). Addition of rules BR-FR-23 to BR-FR-26 to check the size of electronic addresses and Code_Routage, as well as the characters allowed for Code_Routage and electronic addresses in schemeID 0225. BR-FR-DEC-02 rules: editorial correction (for a quantity, not an amount). Rule BR-FR-MAP-01: addition of an example. Rule BR-FR-MAP-02: editorial correction ("contract reference" instead of "contract number"). Rule BR-FR-MAP-06: editorial correction "... in BT-22 of flow 1." Rule BR-FR-MAP-08: rewording. Rule BR-FR-MAP-13: addition of the list of fields concerned. Rules BR-FR-MAP-17 to BR-FR-MAP-22: rewording for greater precision. Addition of Rule BR-FR-MAP-23 on the date format in flow 10.1 (mapping rule for UBL invoices). Chapter 4.6.1: columns updated following the modification of AnnexA on the "FE EN16931 + EXTENDED" sheet (one column per profile to identify the data belonging to each profile). Chapter 5.2: Rule BR-FR-CDV-CL-08: MDT-158 (not MDT-132) Correction to AnnexA: see "VERSIONS" sheet: update of management rules, correction of some Xpaths in the UBL implementation of the EXTENDED-CTC-FR profile, review of the "CDV actors" sheet, addition of reasons for the "IRRECEIVABLE" status
<u>V1.2</u>	<u>2025 10 31</u>	<u>Reflects change in terminology: Approved Platform and Compatible Solution.</u> <u>A few corrections and clarifications, particularly regarding the INVOICEE.</u> <u>Addition of data to the EXTENDED-CTC-FR profile:</u> • <u>Delivery terms (Incoterms).</u> • <u>Code qualifying the type of attribute and value with measurement (e.g., to indicate g of CO2).</u> • <u>Reason for VAT exemption (or VAT information) in line, in text</u>

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

Version No.	Version Date	Description of changes
		<u>and code.</u> • <u>Data for managing sub-lines.</u> • <u>Data required to manage multi-seller invoices.</u> <u>Change in cardinality of the invoice object identifier to 0..n (BT-18, BT-128).</u> <u>The addition of additional management rules for B2G invoices sent to CHORUS PRO.</u> <u>Management of sub-lines.</u> <u>Management of multi-seller invoices.</u> <u>Updating management and mapping rules.</u> <u>Management of READABLE.</u> <u>Management of conversions between formats and profiles in this Standard.</u> <u>Correction of certain life cycle status message management rules (in particular to manage unacceptable invoices).</u> <u>Addition of the reason "NON TRASMISE"(NOT TRANSMITTED) to the status "Submitted" (in cases where the recipient does not have an Approved Platform for receiving invoices).</u>
V1.3	2026 02 26	<u>Addition of flow definition 11, supplement to flow definition 10.</u> <u>EXTENDED-CTC-FR profile:</u> • <u>Addition of exemption reasons in text and code for document-level discounts and charges (EXT-FR-FE-187, EXT-FR-FE-188, EXT-FR-FE-189, EXT-FR-FE-190).</u> • <u>Addition of quantity in ONE unit to the Parent line (in the case of sub-lines). Update of illustrations.</u> <u>Chapter 4.3.3: revision of Standard EN16931</u> <u>Chapter 4.3.4: EXTENDED-CTC-FR profile</u> <u>Chapter 4.4.4: credit note management: no negative credit notes.</u> <u>Chapter 4.4.7: VATEX code management, details for EU or non-EU service sales.</u> <u>Chapter 4.4.9: allowance and charge management, details on rebates and gross prices.</u> <u>Chapter 4.4.11: Subline management, updated the shemes adding the quantity of ONE unit from the Parent line.</u> <u>Chapter 4.4.12: Multi-seller invoices: example</u> <u>Chapter 4.8: Addition of the "Flow 11 - Annuaire" sheet in Appendix A</u> <u>Chapter 5.2: BR-FR-CDV-07: correction (no MDT-59 = DFH)</u> <u>Appendix A: see the Versions sheet, and in particular</u>

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

Version No.	Version Date	Description of changes
		- The management rules for the EXTENDED profile BR-FREXT-S-08 and other BR-FREXT-XX-08 (taking into account the reasons for VAT exemption for VAT Breakdown of the EXTENDED-CTC-FR profile. - Flow 10: reintegration of blocks TG-2, TT-5, and TT-6 allowing additional and corrective flow 10 submissions (CO/MO) between the taxpayer and its "Plateforme Agréée" only. "Flow 11 – Annuaire" sheet.
V1.4	2026 06 30	<u>Chapter 4.1: Updated EXTENDED-CTC-FR profile schema</u> <u>Chapter 4.3.2: EXTENDED-CTC-FR profile (Factur-X EXTENDED):</u> <u>Addition of data from the EN16931 standard revision:</u> ✓ <u>Exchange rate and date (BT-167, 167-1, 167-2 and EXT-FR-FE-192)</u> ✓ <u>Addition of handling for non-VAT taxes associated with charges (BT-177, 177-1 and BT-193, 193-1; and business rules BR-FREXT-BR-38, BR-FREXT-CO-06, BR-FREXT-CO-22).</u> ✓ <u>Addition of schemeIDs BY and SE for private identifiers BT-29 and BT-46.</u> ✓ <u>Addition of rules BR-FREXT-S-01, BR-FREXT-Z-01, BR-FREXT-E-01, etc., replacing rules BR-S-01, BR-Z-01, BR-E-01, etc.</u> ✓ <u>Addition of rules BR-FREXT-BR-28, 38, 44, 54, replacing rules BR-28, 38, 44, 54.</u> ✓ <u>Addition of rules BR-FREXT-CO-06, 08, 16, 22, 24, replacing rules BR-CO-6, 8, 16, 22, 24.</u> ✓ <u>Removal of rules BR-FREXT-BR-27 and BR-28.</u> <u>Addition of INCOTERMS and delivery location fields (EXT-FR-FE-BG-15).</u> <u>Change in cardinality for the discount on Unit Price (BT-147) and for the text and code reasons for these discounts (EXT-FR-FE-195 and EXT-FR-FE-196).</u> - Addition of the dates for the purchase order (EXT-FR-FE-197), the contract (EXT-FR-FE-199), and the shipping document (EXT-FR-FE-198). - Addition of the dates for the purchase order (EXT-FR-FE-200) and the shipping notice (EXT-FR-FE-201) to the line level. <u>Addition of two-way self-billing.</u> <u>Chapter 4.3.3:</u> <u>Minor text corrections (clarifications).</u>

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

Version No.	Version Date	Description of changes
		- Paragraph on Rules BR-X-01 (X = S, Z, E, AE; IC, O, G, AF, AG). <u>Chapter 4.3.4: Accommodation of the two calculation methods for VAT breakdown until at least December 31, 2026.</u> <u>Chapter 4.4.10: Addition of a note regarding the linking of code lists with XSDs (no linking).</u> <u>Chapter 4.4.12.1: Addition of the option to include multiple sub-invoices from the main seller within a multi-seller invoice (particularly for the public sector).</u> <u>Addition of Chapter 4.4.13: Bidirectional self-billing.</u> <u>Chapter 4.5.1:</u> <u>Rule BR-FR-08: Modification to make the Invoicing Framework (BT-23) mandatory and to add values B9, S9, and M9.</u> <u>BR-FR-31: Addition of value BCINT.</u> <u>Addition of BR-FR-32 (verification that SIREN numbers have 9 digits).</u> <u>BR-FR-DEC-03: Acceptance of negative unit prices and discounts on bidirectional invoices.</u> - Amendment to rule BR-FR-CO-05 to exclude the GROUP and INFORMATION lines from the requirement to include a prior invoice. <u>Chapter 4.5.2:</u> <u>BR-FR MAP-11: Correction (swapping of BT codes for Postal Code and City).</u> <u>Addition of BR-FR-MAP-30 to aggregate the various BT-147 values into a single value in Flow 1 or 10.1 (for the EXTENDED-CTC-FR profile).</u> <u>Addition of BR-FR-MAP-31 to force the VAT rate from BT-119 / TT-57 to 0 in flows 1 / 10.1 if missing from the invoice.</u> <u>Chapter 4.5.3:</u> <u>Modification of rule BR-FR-CPRO-01 to use values from list 1153 (GC and CT instead of the proprietary values MARCHE and CONTRAT).</u> <u>Correction of rules BR-FR-CPRO-09, 19, 22, and 39 following the publication of the CHORUS PRO 1.1 specifications.</u> <u>Addition of rules BR-FR-CPRO-45 and BR-FR-CPRO-46 following the publication of the CHORUS PRO 1.1 specifications.</u> - Addition of rules BR-FR-CPRO-47, 48, 49, and 50 for the implementation of B2G/G2B. <u>Chapter 4.5.4:</u> <u>Modifications to Multi-Vendor rules to also incorporate the bi-directional invoice scenario: BR-FR-MV-01, 03, 04, 05, 06, 07, 08, 09, 10, 11.</u> <u>Modification of rule BR-FR-MV-12 for multi-vendor and bi-directional scenarios, and to ensure sub-invoice numbers comply with rules BR-FR-01 and BR-FR-02.</u> <u>Addition of rules BR-FR-BD-02 and BR-FR-BD-13, specific to bi-</u>

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

Version No.	Version Date	Description of changes
		<u>directional invoices.</u> • <u>Addition of rules BR-FR-MV-14 and BR-FR-BD-14 to specify a prior invoice line within multi-vendor or bi-directional sub-invoices.</u> • <u>Addition of rule BR-FR-BDMAP-01 for the extraction of flow 1 (10.1) in the case of bi-directional self-billing.</u> <u>Chapter 4.8:</u> • <u>Code list update (May 25, 2026).</u> • <u>Update to Business Rules 3.2.</u> • <u>Update to sheet descriptions in Annex A.</u> <u>Chapter 5.2:</u> • <u>Modification of rule BR-FR-CDV-14 for "Collected" statuses (Amount AND VAT Rate).</u> • <u>Addition of BR-FR-CDV-16: MDT-124-2 (incremental status detail number MDG-37) – Mandatory.</u> • <u>Modification of BR-FR-CDV-CL-01: addition of BCINT + explanation of code usage.</u> • <u>Correction of BR-FR-CDV-CL-05: addition of code 5.</u> • <u>Modification of BR-FR-CDV-CL-09: inclusion of B2G-specific reasons.</u> <u>Chapter 5.3: addition of B2G rejection reasons.</u> <u>Annexes A and B: update to references V1.4 (instead of V1.3).</u>

Introduction

As part of the Electronic Invoicing Reform in France, governed by Articles 289bis, 290, 290 A of the General Tax Code, applicable from September 2026, the AFNOR Electronic Invoicing Commission has been set up to take charge of describing the invoice formats and profiles and life cycle statuses that constitute the minimum base that «Plateformes Agréées» (PA) shall support, enabling any entity subject to the reform (VAT-registered in France) using these same formats to exchange them with their counterparties in accordance with the requirements of the reform.

This work is part of European standardization in the field of electronic invoicing, which led to the publication by AFNOR of the EN16931 Semantic Standard for Structured Electronic Invoices and its implementation in the UBL and UN/CEFACT CII syntaxes. This work is also based on the publication of Factur-X, a Franco-German standard for mixed (or hybrid) invoices consisting of a representation readable under the PDF/A-3 (ISO 19005-3) and a structured representation of the invoice data in UN/CEFACT CII syntax from the EN16931 standard.

To meet all business needs, and as provided for in EN16931, an "Extended" profile, called "EXTENDED-CTC-FR," has also been defined, incorporating additional invoicing data and modifying some management rules or cardinality of certain data in the EN16931 model.

To this have been added the Management Rules necessary to comply with the requirements of the Electronic Invoicing Reform.

Finally, with regard to life cycle statuses, the AFNOR Commission's work was based on the UN/CEFACT Cross Domain Acknowledgement and Response (CDAR) standard message and the description of its use in the context of the reform between «Plateformes Agréées» (PA) and the PPF Data Concentrator (Public Invoicing Portal). However, it was still necessary to define and describe in this document and its annex the use of this CDAR message for exchanges between entities subject to the reform through their respective "Plateformes Agréées" (PA), and with the latter.

The purpose of this document is to recall the main principles of the EN16931 standard and its application, and then to introduce the detailed technical and functional description of the invoice and life cycle status formats and profiles attached in the annex, which includes several components:

- a **semantic specification of the two profiles EN16931 and EXTENDED-CTC-FR**, with the Management Rules specific to the application of the Electronic Invoice Reform in France and applicable to all invoices within the scope of the reform.
- A reminder of the management rules of the EN16931 standard, to which a few additional management rules applicable to the EXTENDED-CTC-FR profile have been added.
- A **syntactic** description of the implementation of the two semantic profiles **EN16931 and EXTENDED-CTC-FR** in the **XML UBL 2.1** and **UN/CEFACT CII D22B** syntaxes, to which the description of the BASIC WL profile of Factur-X (mixed invoice without line data in structured form) has been added.
- A description of the use of the **UN/CEFACT CDAR life cycle status message for electronic invoice exchanges** between parties subject to the reform through their respective «Plateformes Agréées» (PA).

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

1 Scope

This document aims to describe the formats and profiles of Invoice and Life Cycle Status messages used in electronic invoice exchanges, which constitute the minimum basis for the Electronic Invoicing reform in France.

It therefore describes what entities subject to the reform shall comply with in terms of electronic invoices and life cycle statuses, as well as the checks and transformations that «Plateformes Agréées» (PA) shall apply in order to comply with their regulatory obligations.

2 Normative references

The following reference documents are essential for the application of this document. For dated references, only the edition cited applies. For undated references, the latest edition of the reference document applies (including any amendments).

- NF EN 16931-1+A1, Electronic invoicing — Part 1: Semantic data model for the essential elements of an electronic invoice, published in November 2019.
- CEN/TS 16931-2:2017, Electronic invoicing — Part 2: List of syntaxes compliant with EN 16931-1
- CEN/TS 16931-3-1:2017, Electronic invoicing — Part 3-1: Methodology for syntax mapping of the essential elements of an electronic invoice
- CEN/TS 16931-3-2:2017, Electronic invoicing — Part 3-2: Syntax mapping for ISO/IEC 19845 (UBL 2.1) — UBL 2.1 Invoice and Credit Note schema, published in June 2020.
- CEN/TS 16931-3-3:2017, Electronic invoicing — Part 3-3: Syntax mapping for the Cross Industry Invoice syntax — UN/CEFACT XML schema D16B, published in June 2020.
- CEN/TR 16931-4:2017, Electronic invoicing — Part 4: Guidelines for the interoperability of electronic invoices at the transmission level
- CEN/TR 16931-5:2017, Electronic invoicing — Part 5: Guidelines for the use of sectoral or national extensions to EN 16931-1, based on a methodology to be applied in the real environment
- CEN/TR 16931-6, Electronic invoicing — Part 6: Results of tests of EN 16931-1 with regard to its practical application for an end user — Test methodology
- The Factur-X documentation, which is free of copyright and available from FNFE-MPE and FeRD, the French and German national e-invoicing forums, respectively, latest version 1.07.3 published on May 7, 2025, on the website www.fnfe-mpe.org.

3 Terms and definitions

For the purposes of this document, the terms and definitions given in this document and the following terms and definitions apply.

3.1

PPF Directory

Directory of parties subject to the Electronic Invoicing Reform and recipients of electronic invoices within the scope defined by the latter. The directory of recipients is implemented by the PPF for the purposes of the reform.

3.2

CIUS

"Core Invoice Usage Specification": Specification for the use of electronic invoice messages.

3.3

Data Concentrator

PPF service responsible for concentrating e-invoicing data (domestic B2B invoices and the life cycle of these invoices) and e-reporting (invoice, transaction, and payment data excluding e-invoicing) for the tax authorities.

3.4

"e-invoicing"

Refers to the scope of the Electronic Invoicing Reform relating to the exchange of electronic invoices between VAT-registered entities in France, for the exchange of Flow 1, Flow 2 and Flow 6.

3.5

EN16931

European semantic standard for essential data in electronic invoices.

3.6

"e-reporting"

Refers to the scope of the Electronic Invoicing Reform relating to sales, acquisitions and transactions that do not fall within the scope of "e-invoicing" and are listed in Articles 290 and 290A of the General Tax Code (international B2B sales, international B2B acquisitions, B2C sales, payment for sales for which VAT is payable upon receipt). This section gives rise to the transmission of a Flow 10 and a Flow 6 for the collection status of invoices for which VAT is payable upon receipt.

3.7

EXTENSION

Extension of the EN16931 profile due to the addition of data or data groups, an increase in the cardinality of certain data or groups in the EN16931 model, or the addition of new code values applicable to certain fields.

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

3.8

Flow 1, Flow 2, Flow 3, Flow 6, Flow 8, Flow 9, Flow 10, Flow 11

Flows refer to the different types of messages exchanged as part of the reform:

- Flow 1: corresponds to the Invoice message containing only the data required by the tax authorities for invoices falling within the scope of "e-invoicing" (electronic invoices between VAT-registered entities)
- Flow 2: corresponds to the invoice message exchanged between entities subject to the reform and to be transmitted via «Plateformes Agréées» (PA), in accordance with the provisions of this document.
- Flow 3: corresponds to the invoice message exchanged between entities subject to the reform and to be transmitted via «Plateformes Agréées» (PA), BUT which is in a third-party format agreed between the issuer and the recipient and contains all the information required by the tax authorities in a structured form and allows for the compliant extraction of data for the creation of Flow 1 or Flow 10.
- Flow 6: corresponds to the life cycle status message relating to electronic invoice exchanges, implemented in UN/CEFACT CII.
- Flow 8: corresponds to the invoice message exchanged between an entity subject to the reform and an international entity complying with the provisions of this document.
- Flow 9: corresponds to the invoice message exchanged between an entity subject to the reform and a non-taxable entity established in France (mainly an individual), in accordance with the provisions of this document.
- Flow 10: corresponds to the "e-reporting" message that entities subject to the Electronic Invoice Reform shall transmit to the Data Concentrator via their «Plateformes Agréées» (PA). A completed version of flow 10 is described, allowing companies subject to the reform to transmit e-reporting data to their "Plateforme Agréée" in several stages, with the latter responsible for compiling (optional service) the final flow 10 to be transmitted to the Data Concentrator.
- Flow 11: corresponds to the message enabling Accredited Platforms ("Plateformes Agréées") to transmit publishable data from the PPF "Annuaire" to end-users.

Flows 2, 8, 9, and 6 constitute the minimum base formats and profiles covered by this document.

3.9

Minimum base formats and profiles

The base formats and profiles are the structured or mixed data formats that shall be supported within the framework of the Electronic Invoice Reform, which implements the EN16931 standard.

On the one hand, three formats constitute this core for the Invoice message, each implementing two data profiles:

- EN16931 profile, which is a CIUS for France implementing the EN16931 standard
- EXTENDED-CTC-FR profile, which is an EXTENSION for France of the implementation of the EN16931 standard

These two profiles are implemented in two syntaxes (UBL and UN/CEFACT CII) and in the mixed Factur-X format, more specifically:

- XML syntax ISO/IEC 19845 (UBL 2.1): the UBL (Universal Business Language) format complies with the OASIS U.B.L. 2.1 standard.
- UN/CEFACT CII syntax. The CII (Cross Industry Invoice) format complies with the UN/CEFACT SCRDM CII (Supply Chain Reference Data Model – Cross Industry Invoice) standard. The language version selected for the reform is UN/CEFACT CII D22B.

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

- Factur-X. Factur-X is a hybrid (or mixed) electronic invoice format combining a PDF file compliant with ISO-19005-3 PDF/A-3, which constitutes the READABLE representation of the invoice, with a structured representation of the data in factur-x.xml in UN/CEFACT CII syntax attached to it. Factur-X has additional profiles (MINIMUM, BASIC WL, BASIC, and EXTENDED).

In addition, the life cycle status format is implemented in the UN/CEFACT CDAR (Cross Domain Acknowledgement and Response) syntax and is also part of the minimum base formats and profiles.

3.10

Electronic Invoice Reform

Electronic invoicing reform applicable in France as of September¹, 2026, as described in Articles 289, 289bis, 290, and 290A of the General Tax Code.

3.11

“Plateformes Agréées” (PA)

“Plateformes Agréées” (PA, Accredited Platforms): Electronic invoicing platform through which electronic invoices between VAT-registered entities falling within the scope of the Electronic Invoicing Reform's "e-invoicing" shall be exchanged, along with "e-reporting" data for international B2B invoices excluding imports of goods, transactions, and payments.

3.12

PPF

Public Invoicing Portal, an administrative platform offering recipient directory and data concentrator services.

3.13

“Solutions Compatibles” or SC

Compatible Solutions are management solutions used by companies upFlow or downFlow of the invoice exchange that claim to be compatible with the requirements of the electronic invoice reform in France, namely their ability to create, integrate, and check the compliance of electronic invoices in one of the minimum base formats described in this Standard, as well as in the creation, checking and processing of life cycle status messages as described in this Standard.

This corresponds to the concept of a Dematerialization Operator (OD), initially described in the external specifications of the PPF, with a notion of compatibility with the regulatory and normative requirements in which they partially participate. Compatible Solutions are connected to one or more “Plateformes Agréées” (PA, Accredited Platforms) to issue or receive electronic invoices and life cycle status messages.

4 Minimum electronic invoice formats and profiles

4.1 European Semantic Standard EN16931

The European Semantic Standard was developed as a standard for essential invoice data. The aim was to make it mandatory for all public sector entities in the European Union to receive structured electronic invoices implementing this standard in the UBL and UN/CEFACT CII syntaxes.

This EN16931 Semantic Standard therefore consists of (version published in November 2019) of:

- a set of business data (164), identified by a code in the form BT-XXX (from BT-1 to BT-165, BT-4 does not exist), organized by type (Text, Code, Identifier, Amount, Unit Price, Quantity, etc.), organized into business groups, named BG-XX from BG-1 to BG-31, associated with a cardinality, i.e., an optional or mandatory presence rule and the possibility of multiple occurrences.
- a set of management rules:
 - ✓ 96 management rules related to VAT,
 - ✓ 126 management rules related to the specific presence of business data or related to calculations or conditional rules (if a piece of business data is equal to xxx, then another piece of business data shall be present), or expressing the number of decimal places for certain types of data, lists of authorized values (codes) for certain fields.
- lists of codes to be used for certain data, enabling the values of certain fields to be standardized. All these codes are inherited from EDI practices that have been in use for over 30 years. For example, the type of invoice is defined by a code: 380 means "Commercial Invoice," 381 means "Credit Note," 384 means "Corrected Invoice," etc. Similarly, currencies are coded using trigrams (3 letters), etc.

This standard was not designed to address all business needs, but the vast majority of them. Thus, the EN16931 standard was designed on the assumption that an invoice addresses **a single order and a single delivery**. In order to address local constraints and additional needs, the EN16931 standard provides for two additional provisions:

- The ability to create "Core Invoice Usage Specifications" (**CIUS**), which allow the constraints of the standard to be tightened, for example by removing optional data, renaming certain data, reducing cardinality, and restricting code lists. These CIUS remain fully compliant with the EN16931 standard as they comply with all its management rules and data structure.
- The ability to create **EXTENSIONS** by adding data or data groups, increasing cardinality, relaxing certain management rules, and adding code list values.

The regulatory requirements of the reform and the obligation to cover all business use cases therefore require the definition of two profiles:

- A profile incorporating additional management rules to the EN16931 standard, making it a CIUS. This is the EN16931 profile.
- A profile incorporating additional data, identified by codes in the format EXT-FR-FE-XXX, also organized into groups identified as EXT-FR-FE-BG-ZZZ, and a few modifications to certain management rules. This is the EXTENDED-CTC-FR profile.

These semantic profiles therefore each describe a data tree, traversing it branch by branch, sub-branch by sub-branch until reaching the leaves, which are the data. The path is guided by an indication of a level in the structure (1 or N1: first branches, 2 or N2: second branches, etc.).

Each branch and leaf is associated with a cardinality that indicates whether its presence is optional or mandatory, and whether it is repeatable. The coding takes the form of two digits separated by "..", the first indicating the minimum occurrence and the second the maximum occurrence, with "n" meaning "as many occurrences as desired." Thus:

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France


- 0..1 means "optional and non-repeatable"; 0..n means optional and repeatable
- 1..1 means "mandatory and only once"; 1..n means mandatory and repeatable

Following the adoption of the ViDA Directive, work is underway to revise the EN16931 standard, mainly to add data and correct certain management rules to address a greater number of use cases. Some of these changes are already present in the EXTENDED-CTC-FR profile, which is designed to anticipate as many of these changes as possible so that users can use them before the revision takes effect and is rolled out between 2027 and 2030. The ViDA Directive makes structured electronic invoicing mandatory for all intra-Community B2B transactions as of July 1st, 2030.

The following two diagrams show the semantic structure of the two profiles:


- EN16931 Semantic Standard Profile: only postal address blocks are not detailed. Each piece of data has its own identifier (red background and green background for line data) and cardinality (navy blue background). The red arrow describes the body of the structure with all level 1 elements (gray background).
- EXTENDED-CTC-FR profile: the brown/purple lines correspond to the added data or blocks. The cardinality changes are shown in yellow. BG-26, BG-27, and BG-28 are as in the EN16931 profile (not detailed here). The new Parts (EXT-FR-FE-BG-01, to 05) and BG-10 each have the same data structure.

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France



EN16931 Semantic Standard, profile EN16931 - 2019

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France



4.2 Implementations of the two profiles EN16931 and EXTENDED-CTC-FR

4.2.1 The need to offer several semantic profiles in the minimum base

The EN16931 standard is a semantic description. It allows different profiles to be created:

- On the one hand, usage specifications (called CIUS for Core Invoice Usage Specification), which allow restrictions (optional data removed, reduced cardinalities), but which shall pass all the management rules of the EN16931 standard.
- On the other hand, EXTENSIONS, which integrate additional data, can extend the cardinality of certain data, or even relax certain management rules, remove some, or add others, in a limited way.

These profiles shall then be implemented in a computer format that can be processed automatically. The syntaxes chosen are the two XML syntaxes selected for the implementation of the EN16931 standard for the public sector in the European Union: XML UBL and XML UN/CEFACT CII.

For information, an implementation specification in EDIFACT syntax has also been produced in the "Syntax Binding" publications of Standard EN16931, but can only be used on a voluntary basis and with the bilateral agreement of both parties (Seller and Buyer).

Another implementation has been documented with the mixed Factur-X format, which takes the form of a readable PDF/A-3 representation to which an invoice data file in structured XML UN/CEFACT CII format named "factur-x.xml" is attached. All of this data shall be present in the readable representation. However, this format allows certain information to be present only in the readable representation, which provides greater flexibility, particularly for invoice information that is not mandatory as required by the tax authorities or to which no management and control rules apply, and which is therefore not useful for automating invoice processing and does not affect its compliance with the data model used. This format is available in five profiles, including three main ones (in bold):

- **An EN16931 profile:** which strictly complies with the EN16931 standard. All data in the structured file shall comply with the EN16931 standard (and therefore all management rules).
- A BASIC profile: which is a subset of the EN16931 profile, containing all the mandatory information and all the management rules of the standard. This profile was created to indicate to companies which data they need to manage as a priority. Any invoice that complies with the BASIC profile also complies with the EN16931 profile. Consequently, any invoice based on the BASIC profile can be declared compliant with the EN16931 profile, and it is strongly recommended that it be declared as EN16931. **This profile is therefore not included in the electronic invoicing reform in France.**
- **A BASIC WL profile:** this is the BASIC profile, but without the line data and Document level allowances and charges. This profile will be authorized at the start of the reform (until September 2027, to be confirmed in the update of the texts). It does not strictly comply with the EN16931 standard as it lacks the mandatory lines. All management rules that apply to line data or involve it (calculations of line totals and document allowances) are therefore excluded for this profile.
- A MINIMUM profile containing a minimum amount of data (the bare minimum required to be accepted on CHORUSPRO). **This profile cannot be used in the context of the reform** as it does not contain enough data in structured form.
- **An EXTENDED profile:** this contains a large amount of additional data, such as third parties to the commercial transaction (an invoicing party, a buyer's agent, a third-party payer, a seller's agent, etc.), and a lot of additional data, particularly at line level. This profile allows multi-order and multi-delivery invoices, with more than 700 data fields, which are identified by a specific nomenclature (in the form BT-X-XXX, where BT-X is fixed to express "extension data"). A few management rules have also been added to replace those in the EN16931 Standard, in particular to introduce a tolerance in the calculation rules to deal with certain rounding difficulties or to manage invoices based on unit prices including tax, but also to remain compatible with certain software tools that calculate VAT per line rather than at the bottom of the invoice.

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

That being said, the minimum data profiles are as follows:

- EN16931 profile that complies with the EN16931 standard, to which additional management rules have been added to ensure compliance with the regulatory requirements of the electronic invoicing reform in France
- EXTENDED-CTC-FR profile, which is an extension of the EN16931 semantic model, with the addition of data labeled under the EXT-FR-FE-ZZZ nomenclature, as well as the addition of certain management rules, some of which replace rules in the EN16931 standard (to allow for tolerances in the calculations required for certain use cases).

For Factur-X, the profiles used in the minimum set are as follows:

- BASIC WL: only until September 1, 2027.
- EN16931: to which the additional French management rules described in chapter 4.5 shall be added.
- EXTENDED: which contains the EXTENDED-CTC-FR profile and to which the additional management rules for France described in chapter 4.5 shall be added.

In practice, the **EXTENDED-CTC-FR** profile is a subset of the **Factur-X EXTENDED** profile, which also serves as a repository of extension components to enrich the EXTENDED-CTC-FR profile when necessary to address certain use cases. The Factur-X documentation includes the correspondence between its own extension data and the nomenclature of the EXTENDED-CTC-FR (EXT-FR-FE-ZZZ) profile described in this document and the Excel appendix.

As all data in the structured Factur-X file (factur-x.xml) EXTENDED is present in the readable PDF representation that serves as the envelope for the invoice, the recipient may or may not use the additional data beyond the EXTENDED-CTC-FR profile, as it is available in readable form if necessary.

4.2.2 Implementation in UBL and UN/CEFACT CII syntaxes requires a specific description

The UBL and UN/CEFACT CII syntaxes have their own semantics. They are a set of data, much richer than the EN16931 standard, also organized into groups and subgroups of data, with their own cardinalities.

As a result, the implementation of the two profiles EN16931 and EXTENDED-CTC-FR in UBL and UN/CEFACT CII is the result of a mapping that has to deal with certain semantic differences. This is why the correspondence of an XPATH to each piece of data in the semantic model is not sufficient to describe the implementation in XML.

It is therefore also necessary to describe the implementation of the two profiles in each of the two syntaxes, and moreover by profile, since the data structure may differ in terms of cardinalities from one profile to another.

These semantic differences led to the choice of version D22B for UN/CEFACT CII instead of version D16B, which was initially used when EN16931 was published in 2017, because version D16B did not allow cardinality 0..n of BG-3 (reference block to a previous invoice), which is necessary in the case of credit notes referring to several invoices.

4.3 Summary description of the semantic data structure of the two profiles

4.3.1 The EN16931 profile

The EN16931 profile is initially constructed on the assumption of a **single order and single delivery invoice**.

There are only five parties that may be involved:

- A SELLER (BG-4), mandatory presence once (cardinality 1..1), who is the issuer of the invoice (or the person on whose behalf the invoice is issued, including self-billing). This is mainly the Party that

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

records the transaction as Products in its accounts and generally collects the VAT shown on the invoice.

- A BUYER (BG-7), mandatory once (cardinality 1..1), who is generally the recipient of the invoice, but above all the person who bears the expense in their accounts and can deduct the VAT shown on the invoice.
- A "Delivered to" (BG-13), delivery address, optional, present once at most (cardinality 0..1), which allows you to designate where the goods are delivered or where the services are performed. If not provided, the delivery address is the address of the BUYER. As a reminder, in France, the delivery address for goods is mandatory if it is different from the address of the BUYER (Article 242 nonies A 7bis of Annex II of the CGI).
- A PAYEE (BG-10), optional and present once at most (cardinality 0..1), who is the person to whom the invoice is supposed to be paid. This PAYEE is entered ONLY if they are different from the SELLER (which can be identified by their respective legal identifiers). Furthermore, this PAYEE is only identified by their name, legal identifier, and a private identifier.
- A TAX REPRESENTATIVE OF THE SELLER (BG-11), optional and present once at most (cardinality 0..1), which is mandatory if the SELLER is represented for tax purposes. PLEASE NOTE that if the SELLER is part of a SINGLE TAXABLE ENTITY group, the Single Taxable Entity, which is the head of the group, shall be identified in this data block (and therefore its company name, intra-Community VAT number, and postal address). In addition, its SIREN number shall be entered using the Seller's private identifier (BT-29), with the qualifier 0231.

The BUYER and the SELLER have a lot of information to define them, namely:

- Company name and trade name
- Legal identifier, intra-community VAT number
- Private identifier, qualified because it refers to a reference system. For example, a GLN is a qualified identifier with the code 0188. For those who wish to add a SIRET number, the qualifier is 0009. For a Code_Routage, the qualifier is 0224. For the SIREN number of the sole taxpayer, the code is 0231.
- A postal address
- A block of contact data
- **A STANDARDIZED ELECTRONIC ADDRESS**, which for the recipient (usually the BUYER) is the electronic address where they wish to receive their invoice (address in the form SIREN_XXX referenced in the PPF Directory). For the issuer (usually the SELLER), it is the electronic address at which they wish to receive their life cycle status updates. These electronic addresses are the data required for the exchange of invoices through a network of interoperable "Plateformes Agréée" (PA, Accredited Platforms). They are therefore mandatory in invoices (management rules BR-FR-12 and BR-FR-13) and shall therefore be included in the customer/supplier databases of business management solutions in the same way as the legal identifier, company name, postal address, etc.

There are also numerous document-level references that can be used to deal with a wide range of situations:

- A buyer reference (BT-10): provided by the BUYER, which is normally used to route invoices within their internal organization. It is therefore often a Business Unit number, a service reference, an internal mailbox, etc.
- A Purchase Order reference generated by the BUYER (BT-13): often required for all purchasing processes that involve the generation of a Purchase Order, sent **at the time of the order, and not after delivery or invoicing**. As a reminder, under Article L. 441-9 of the French Commercial Code, the invoice shall mention the purchase order number when it has been previously established by the buyer.
- A contract reference (BT-12): required in particular for recurring services managed without a purchase order number (utilities, telephony, etc.).

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

- A reference to the previous invoice(s) (BG-3, BT-25), mainly for CREDIT NOTES or CORRECTED INVOICES. This information may also be useful in the case of a final invoice following a pre-payment invoice (requiring additional information, see EXTENDED-CTC-FR profile).
- A Shipping Notice reference (BT-16): also known as a Delivery Note.
- A Receipt Reference (BT-15): which can be useful in highly integrated supply chain processes.
- A Sales Order reference (BT-14): sometimes confused with the Purchase Order. This is the order reference generated by the SELLER, which allows them to track the transaction. This information is very often used when purchasing from overhead suppliers or when purchasing online.
- An Invoiced Object Reference (BT-18): this is data where the type of object invoiced is coded in a list that shall be followed. This can be useful for managing references specific to certain activities (a license plate number, a meter number, a telephone number invoiced, an internal customer or file reference etc.).
- A Project reference (BT-11): can be used, for example, to identify a construction site in the construction industry.
- A tender reference or lot number (BT-17).
- A BUYER accounting reference (BT-19), for example to enable allocation in cost accounting. This information shall therefore be provided by the BUYER.
- An invoicing period (BG-14), which is particularly useful for all subscription services or for end-of-year allowances for which it is necessary to specify a reference period.

This profile contains the standard information found on an invoice:

- Number (BT-1), Date (BT-2), Type (BT-3): a code used to identify the type of invoice (commercial invoice, credit note, corrected invoice, pre-payment invoice, self-billed invoice, etc.)
- Currency (BT-5): in principle, the invoice currency applies to all prices and amounts. The only exception is the total amount of VAT, which can also be shown in another currency: the accounting currency (BT-6). This is why there are two entries for the total amount of VAT (the aim being that one of the two is in EUR, as the tax authorities require the VAT amount to be in EUR):
 - ✓ The Total VAT Amount in the Invoice Currency: BT-110 (currency equal to BT-5).
 - ✓ The Total VAT Amount in the Accounting Currency: BT-111 (currency equal to BT-6).
- Due date (BT-9), bearing in mind that it is also possible to provide information on payment terms in BT-20, using free text that can therefore contain, for example, "Payment 30 days net."
- VAT due date (BT-7), which is not used in this way in France, but in the form of an event in BT-8, to indicate whether VAT is due on the invoice date or the delivery date (VAT payable "au débit") or on the payment date (VAT on receipt "à l'encaissement"). BT-8 is mandatory only for service invoices for which the SELLER has opted for debits. Otherwise, it may or may not be present.
- The payment instructions (BG-16) are used to indicate the desired payment method and the expected payment reference, then to provide one or more bank accounts to be paid by transfer, as well as information relating to a direct debit (the invoice serving as notification), and finally credit card information if this method is used, solely for reconciliation purposes (only part of the card number is provided).
- And finally, a repeatable Note (BG-1), consisting of a subject code to describe its use and a free text field. This allows additional data to be added, which is often difficult to use (as it is in the form of text that is only loosely described and not coded). This allows you to include anything that does not fit into the EN16931 standard, but with the risk of much less relevant readability than the usual readable representation on paper or in PDF. This is precisely why the Factur-X format was designed: to combine the usual readability with the minimum regulatory structured data that is required.

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

The profile is then completed with line data and allowance and charge data at the document level (which can be viewed as specific lines).

First, the lines, which are a fairly small set of data:

- Line number (BT-126) and Line note (BT-127)
- Invoiced Object ID (BT-128), header reference that can also be used in line.
- Reference of the line of the Purchase Order to which the invoice line relates (BT-132). Therefore, there is no reference to the receipt or delivery line, for example, which is useful for "3-point" reconciliation.
- BUYER's accounting reference (BT-133), which can therefore be provided at line level.
- Item identification:
 - ✓ Name (BT-153), Description (BT-154)
 - ✓ SELLER's item codes (BT-155), BUYER's item codes (BT-156), or even a standard identifier to be qualified (BT-157), such as a GTIN number.
 - ✓ One or more item classification identifiers (e.g., UNSPSC reference), with a list of available references (see UNTDID 7143 code list).
 - ✓ Country of origin (BT-159)
 - ✓ Attributes (BG-32), repeatable, block of 2 data items, namely a data qualifier followed by its value. For example, COLOR; RED. This is a way of entering almost anything, but in the form of free text "nature of the information/value of the information." This attribute block can be enhanced in the Factur-X EXTENDED profile with a code that qualifies the data in a more standardized way.
- Determination of the unit price without VAT:
 - ✓ Gross Unit Price (BT-148), Rebate (BT-147) on Gross Unit Price
 - ✓ Net Unit Price (BT-146), which is mandatory for the EN16931 standard
 - ✓ Base quantity of the unit price (BT-149), because it is possible to define unit prices for given quantities (e.g., a price for 1,000 screws). This quantity is associated with a unit of measurement (BT-150: part, kg, liter, kW, etc.; the list of units is standardized and very long). This makes it possible to manage rounding issues when unit prices are very low or require many decimal places (a price for 1,000 allows for greater precision: for example, \$2 for 1,000 screws rather than \$0.002 per screw).
- Invoiced quantity (BT-129) and its unit (BT-130).
- Line allowances and charges, which are two separate, repeatable blocks, each consisting of:
 - ✓ The amount of the Allowance / Charge (BT-136/BT-141)
 - ✓ A base and a rate, which is optional
 - ✓ A reason in code or text, one of which is mandatory.
- A total line amount without VAT (BT-131)
- A VAT code and rate. VAT is encoded with a category code (Standard, Exemption, Reverse Charge, etc., see dedicated section below) and a percentage rate.

In addition, there are document-level allowances and charges, which are defined in a similar way:

- Allowances or Charges amounts (BT-92 / BT-99)
- A base and a rate (optional data)
- A reason in code and/or text (at least one of the two is mandatory).
- A category and a VAT rate

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

These document-level allowances or charges can be viewed as special lines (especially charges). Their total is tracked separately at the bottom of the invoice.

The profile is completed by the footer and VAT footer data, the calculation rules for which are described later in this document:

- The VAT footer contains, by category and VAT rate
 - ✓ the pre-tax base to which the rate will apply (BT-116),
 - ✓ the applicable VAT rate (0 if no VAT), (BT-119),
 - ✓ the amount of VAT (BT-117) in the invoice currency (BT-5),
 - ✓ In the event of exemption, the reason for exemption in the form of text or code (VATEX codes managed by the European Commission).
- The totals of the invoice:
 - ✓ Starting with subtotals: Total without VAT for lines (BT-106), Total without VAT for document allowances (BT-107), Total without VAT for document charges (BT-108)
 - ✓ Then the totals used to arrive at the total including tax: Total excluding tax for the invoice (BT-109), Total VAT amount (BT-110, in the invoice currency BT-5 and BT-111 in the accounting currency BT-6), Invoice Total Amount with VAT (BT-112).
 - ✓ Next, add the data used to determine the amount payable: Paid Amount (BT-113), for example for advance payments, Rounding Amount (BT-114) because amounts are sometimes rounded up to the nearest euro, and finally the Amount due for payment (BT-115).

Finally, the profile allows additional supporting documents (BG-24) to be attached, consisting of an identifier, a description, and a file, either by providing an access link (URL) or by attaching the file, generally encoded in base64.

4.3.2 The EXTENDED-CTC-FR profile

The study of use cases shows that the EN16931 standard does not cover all existing information appearing on invoices, as it was designed to address essential needs.

It therefore appeared necessary to define an extended profile, called EXTENDED-CTC-FR. This profile is intended to be long-lived and maintained, with strong upward compatibility constraints so that changes to the profile do not require those who do not need the changes to modify their processing chains.

«Plateformes Agréées» (PA) and Solutions Compatibles (SC) SHALL use the latest version of the validation tools published for each profile.

This EXTENDED-CTC-FR profile has added a few new parties who play a role in the commercial transaction and invoice processing, which sometimes makes it necessary to designate them in invoices. These are:

- The BUYER's AGENT (EXT-FR-FE-BG-01), who may act on behalf of the BUYER, often in the ordering phase, and therefore in the validation or pre-validation ("Approval") of invoices.
- The PAYER (EXT-FR-FE-BG-02), who may be a third party other than the BUYER. This may be a subsidiary or parent company of a group, but also an end customer in the case of subcontracting with direct payment.
- The SELLER's AGENT (EXT-FR-FE-BG-03), who may act on behalf of the seller (a distributor, for example) and may play a role in the process of creating and validating invoices to be issued, or even in monitoring their life cycle status.
- The "INVOICEE" (EXT-FR-FE-BG-04), which is more accurately referred to in the standards as the "Invoiced to," is the Party to whom the invoice is sent because it is responsible for processing it on

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

behalf of the BUYER. However, the use of multiple electronic invoicing addresses for receiving invoices makes it possible to avoid using this ability to send invoices to a third party, but simply to allow that third party to process invoices addressed to the BUYER at an electronic invoicing address (an invoice reception mailbox) whose management is entrusted to that third party by the BUYER. However, when the INVOICEE is named on the invoice, this allows the PA-R (receiving party) to manage delegation rights in a more targeted manner to allow it to access the invoice and the processing actions for which it has been delegated. This third party may also enable compliance with the requirements of Article 441-9 of the French Commercial Code, which requires that the postal address of the entity that receives and processes the invoice on behalf of the BUYER be provided (invoicing address if different from the customer's (BUYER's) address, which shall be interpreted as the postal invoicing address).

- The INVOICER (EXT-FR-FE-BG-05) is the third party who creates and issues the invoice on behalf of the SELLER, under an invoicing mandate.

For all these new parties, the structure of the description data is the same and similar to that of the SELLER and the BUYER, except that only the company name is mandatory (not the postal address), and a "Role Code" has been added to better qualify the role of the third party. This is particularly necessary for the PAYEE, which has been aligned with these actors in terms of available data. The Role code "DL" thus indicates that the PAYEE is a Factoring Company.

The other addition to this profile was to allow multi-order and multi-delivery invoices. To do this, most of the Document level references have been added to the line:

- Purchase order number (EXT-FR-FE-135)
- Reference to the previous invoice (one per line), with the option of adding the type of previous invoice, which allows advance payments to be recovered at line level and indicates that this is an advance payment recovery to enable accurate automatic accounting.
- Delivery address and date at line level.
- Shipping notice, Receipt slip, Sales Order at line level, with the option of entering the line number of these documents that corresponds to the invoice line.
- A subject code for the line note, associated with a cardinality change (0..1) allowing the use of multiple invoice line notes

Finally, some data has been added, particularly due to its usefulness for the public sector or to comply with the requirements of the reform:

- A contract type (EXT-FR-FE-01), supplementing the contract number (BT-12)
- A change in the cardinality of BT-46 (0..n instead of 0..1): private identifier of the BUYER, allowing the usual private identifier to be entered, as well as a SIRET number and a Code_Routage.
- A type code for the previous invoice (BG-3), (EXT-FR-FE-02).
- Change in cardinality of the invoice line Invoiced Object identifier (BT-128) and at Document level Invoiced Object Identifier (BT-18), allowing for multiple references to be available in certain use cases.

To meet certain operational requirements and use cases, the following data has also been added:

- To enable invoices to be issued with different reasons for exemption, and more generally to allow for a more detailed breakdown of VAT:
 - ✓ A VAT exemption reason in text (EXT-FR-FE-178) and code (EXT-FR-FE-179) form, which can be used to specify a VAT context to be included in the VAT breakdown. This is in anticipation of the revision of the Standard, which is necessary as of today.
 - ✓ Similarly, a reason for VAT exemption in text (EXT-FR-FE-187) and code (EXT-FR-FE-188) for document level Allowances, and document level charges (EXT-FR-FE-189 / EXT-FR-FE-190).
 - ✓ The removal of rules BR-S-10 and BR-Z-10 for this EXTENDED-CTC-FR profile, in order to allow the use of this data in line and the corresponding data in VAT breakdown (BT-120 and BT-121).

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

- ✓ Updating of VAT breakdown calculation rules (VAT rules BR-S-8, BR-Z-8, etc.) removed from the EXTENDED-CTC-FR profile with the addition of modified rules applicable only to the EXTENDED-CTC-FR profile. These rules anticipate a significant change in the revision of EN16931 Standard, which requires VAT details to take into account the reasons for VAT exemption in text (BT-120) and code (BT-121) as they are present in the lines, and in charges and allowances at document level. To support the transition, which also requires the reasons for VAT exemption to be entered in the lines, and in charges and allowances at document level, checks if control with and without reasons for VAT exemption are performed, and if one of them is sufficient for a passing check, the other is marked as a “warning” for information and reminder purposes.
- To provide early access to certain data added in the revision of the EN16931 standard, the following data elements have been included (along with their BT-XX codes as defined in that revision):
 - ✓ Exchange rate (BT-167) between the invoice currency (BT-5, repeated in BT-167-1: source currency) and the accounting currency (BT-6, repeated in BT-167-1: target currency), as well as the exchange rate date (EXT-FR-FE-192), which is not present in the EN16931 standard revision.
 - ✓ Non-VAT tax type code at the document level (BT-177) and its listID (BT-177-1)—which must be set to 5153—used to classify charges that are effectively non-VAT taxes identified via a code list other than the standard charges list (UNTDID 7161). Care must be taken when using this field, as some codes appear in both lists. For example, the code AAA signifies "Telecommunication charge" when used for a charge (absence of BT-177-1) and "Petroleum tax" when used for a non-VAT tax (with BT-177-1 = 5153). This necessitated modifying rule BR-38 to BR-FREXT-BR-38 to account for this dual reference system for charge or tax reason codes.
 - ✓ Non-VAT tax type code at the line level (BT-193) and its listID (BT-193-1): follows the same mechanism as the document-level field described above, but applies to charges and non-VAT taxes at the line level. This led to modifying rule BR-44 to BR-FREXT-BR-44 to account for this dual set of codes for Charge or Tax reasons.
 - ✓ Addition of codes BY and SE as qualifiers (schemeID) for private identifiers (BT-29, BT-46), signifying "generated by the BUYER" / "generated by the SELLER".
 - ✓ Addition of rules BR-FREXT-S-01, BR-FREXT-Z-01, BR-FREXT-E-01, BR-FREXT-AE-01, BR-FREXT-IC-01, BR-FREXT-G-01, BR-FREXT-O-01, BR-FREXT-AG-01, and BR-FREXT-AF-01 to replace rules BR-S-01, BR-Z-01, BR-E-01, etc., allowing for multiple VAT detail lines due to the variety of code- and text-based reasons included in the EN16931 standard revision for VAT breakdown (BG-23).
 - ✓ Addition of rules BR-FREXT-BR-28, BR-FREXT-BR-38, BR-FREXT-BR-44, and BR-FREXT-BR-54 to replace rules BR-28, BR-38, BR-44, and BR-54.
 - ✓ Addition of rules BR-FREXT-CO-06, BR-FREXT-CO-08, BR-FREXT-CO-16, BR-FREXT-CO-22, and BR-FREXT-CO-24 to replace rules BR-CO-6, BR-CO-8, BR-CO-16, BR-CO-22, and BR-CO-24.
 - ✓ Removal of rule BR-FREXT-BR-27.
- For the management of international transactions: the delivery terms at document level (EXT-FR-FE-BG-14) and at line level (EXT-FR-FE-BG-15) that are
 - ✓ INCOTERMS codes (EXT-FR-FE-185) at document level and at line level (EXT-FR-FE-193).
 - ✓ and the name of the place where the transfer of ownership takes place (EXT-FR-FE-186) at document level, and at line level (EXT-FR-FE-194).
- To view the dates of certain reference documents:
 - ✓ Dates of the purchase order (EXT-FR-FE-197), the contract (EXT-FR-FE-199), and the shipping document (EXT-FR-FE-198).
 - ✓ Dates of the line-item purchase order (EXT-FR-FE-200) and the line-item shipping notice (EXT-FR-FE-201).

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

- To enable the management of discounts at the unit price level—as is common practice in certain sectors, replacing line-level discounts—and thereby obtain a Net Unit Price reflecting the actual unit price resulting from the line item:
- The cardinality of the discount (BT-147) has been changed to 0..n (instead of 0..1) in the EN16931 profile.
- A discount reason field—in both text (EXT-FR-FE-195) and code (EXT-FR-FE-196) formats—has been added, utilizing the same list used for line-level and document-level discount codes (a subset of the UNTDID 5189 list).
- To better qualify item attributes, two pieces of data have been added (also present in the revision of Standard EN16931):
 - ✓ A code used to describe the type of attribute instead of or in addition to its name (EXT-FR-FE-159), to be selected from list 6313. This also resulted in rule BR-54 being modified to BR-FREXT-BR-54 to allow either an attribute name or an attribute code, or both (instead of requiring only an attribute name).
 - ✓ An attribute value (EXT-FR-FE-160) associated with a unit of measurement (EXT-FR-FE-161), instead of a text value (BT-161). This also resulted in rule BR-54 being modified to BR-FREXT-BR-54 to allow the use of either a text value (BT-161) or a value with a unit of measurement (EXT-FR-FE-160), but not both.
 - ✓ For example, this allows an attribute of "25 g of CO2" to be coded:
 - Code (EXT-FR-FE-159): BRL (Carbon Dioxide)
 - A measured value (EXT-FR-FE-160): 25
 - A unit of measurement (EXT-FR-FE-161): GRM (gram)
- For managing composite items (e.g., a toy book), kits, subtotals, or line item grouping requirements, there is an option to manage sub-lines:
 - ✓ A parent line identifier (EXT-FR-FE-162) allowing one invoice line to be linked to another to indicate their dependency (concept of sub-line)
 - ✓ A line subtype (EXT-FR-FE-163) used to distinguish information or grouping lines, whose data is not included in invoice total calculations, from "Detail" lines, which, along with lines that do not use this qualifier, the invoicing lines used in calculations and transmitted to the PPF (flow 1 and flow 10.1).
 - ✓ A quantity in a UNIT of the Parent line (EXT-FR-FE-191), used to provide details of the composition of a unit of a "GROUP" line within its "DETAIL" sublines.
 - ✓ The creation of management rules to take into account this possibility of sub-lines in totals.
 - ✓ The use of sub-lines is specified in chapter 4.4.
- For the management of multi-seller invoices, created by or on behalf of transparent intermediaries acting on behalf of several Vendors, intended for a single BUYER but also for bidirectional invoices consisting of a sales self-billing invoice combined with a reverse sales invoice from the buyer to the seller:
 - ✓ A line level Seller (EXT-FR-FE-BG-12), containing the same types of information as the SELLER (BG-4), except for the contact information block.
 - ✓ A VAT amount per line (EXT-FR-FE-181) in the invoice currency (BT-5)
 - ✓ A VAT amount per line (EXT-FR-FE-182) in the accounting currency (BT-6)
 - ✓ A line total with VAT (EXT-FR-FE-184)
 - ✓ A VAT liability code (EXT-FR-FE-185, Debits/Receipts), equivalent to BT-8 at the invoice level.

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

- ✓ The implementation of multi-seller invoices is specified in chapter 4.4.

The other addition to this profile is the modification of certain management rules:

- to allow a tolerance of 0.01 cent per line or Document-level allowance or charge in the calculations of amounts at the bottom of the invoice or at the bottom of the VAT.
- to allow an invoice to have lines outside the scope (VAT category = O) and other lines (which the EN16931 standard currently prohibits), rules BR-O-2, BR-O-3, BR-O-4, BR-O-11, BR-O-12, BR-O-13, and BR-O-14 have been removed for the EXTENDED-CTC-FR profile.

All changes, data additions, replacements, and deletions of management rules in the EXTENDED-CTC-FR profile are also replicated in the same way in the Factur-X EXTENDED profile.

4.3.3 Evolution of the EN16931 standard

As part of the European work of CEN TC434, the EN16931 standard has been updated. The main consequence of this will be to incorporate the changes to the EXTENDED-CTC-FR profile into the standard, except for the addition of the Additional Parts, which will remain in the Extensions.

The semantic model of the revised EN16931 standard was approved in mid-February and is currently being published. Its implementation in UBL and CII (as well as EDIFACT) syntaxes is also underway, with its publication scheduled for the second half of 2026

When it is published and operational, the profiles described in this document will be subject to change. In the meantime, the changes that prove necessary for the operational implementation of the electronic invoicing reform in France are added gradually to each new version of this XP Z12-012 standard, in the EXTENDED-CTC-FR profile (and EXTENDED in Factur-X). The aim is to enable those who need the additional data to use it, but also to prepare for the implementation of the revised EN16931 standard.

One of the impacts of the revision of the EN16931 standard is to allow invoices to include several reasons for VAT exemption which can be entered in the invoice lines as well as in document-level allowances and charges, requiring these to be taken into account in VAT breakdown control checks.

It is also possible to use these exemption reasons for VAT categories “S” and “Z” to provide the information necessary for VAT tracking in the invoice.

This has been integrated into this version for the EXTENDED-CTC-FR profile:

- first, by adding the exemption reasons on line level (done in previous version) and in document-level allowances and charges,
- then, by adapting the VAT breakdown control rules, which currently support the inclusion of exemption reasons (BT-120 / BT-121) or not, indicating the rule that may not be complied with, for information purposes (as a “warning”). This allows users to prepare to enter VAT exemption reasons at line level and at document level charges and allowances, without this being a blocking factor for the time being,
- Finally, by modifying business rules BR-E-01, BR-IC-01, BR-Z-01, BR-G-01, BR-O-01, BR-S-01, BR-AE-01, BR-AG-01, and BR-AF-01 to allow multiple VAT breakdown groups (BG-23) for a given VAT category, given that these rules also account for exemption reasons which may vary within a single invoice. This resulted in the creation of rules BR-FREXT-E-01, BR-FREXT-IC-01, BR-FREXT-G-01, BR-FREXT-O-01, BR-FREXT-S-01, BR-FREXT-AE-01, BR-FREXT-AG-01, and BR-FREXT-AF-01.

This option is also essential for managing multi-seller invoices, as the VAT exemption reason in text is used to identify the various sub-invoices and thus produce a VAT breakdown for each sub-invoice.

The tolerance for not taking into account line level VAT exemption reasons and document-level allowances and charges for the EXTENDED-CTC-FR profile will continue until at least December 31, 2026.

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

4.3.4 Factur-X EXTENDED profile and evolution of the EXTENDED-CTC-FR profile

The EXTENDED profile of Factur-X provides a large amount of additional data. It was designed by the FNFE-MPE in collaboration with the FeRD (German Forum) and is based on business practices in EDI exchange (EDIFACT in particular).

To use it, you need to obtain the Factur-X documentation, which includes the validation components. This profile will enable EXTENDED-CTC-FR profile maintenance teams to find the elements they need to address certain specific requirements identified during the use case inventory.

The EXTENDED-CTC-FR profile now includes VAT exemption reasons at line level and document-level allowances and charges, as well as VAT breakdown checks (BG-23). It is important that all invoices covered by the EXTENDED-CTC-FR profile include line level VAT exemption reasons, and document-level allowances and charges whenever the VAT category is different from "S" and "Z." For categories other than "E," the VATEX code that can be used is normally predetermined as follows:

- O (Out of scope): VATX-EU-O
- G (Export): VATEX-EU-G
- K (Intra-Community delivery): VATEX-EU-IC
- AE (reverse charge): VATEX-EU-AE (for any reverse charge, including sales of services in the EU) or VATEX-FR-AE (possible to indicate domestic reverse charge)

If the VAT category is "E," it shall be filled either the VATEX code from the authorized list (VATEX list), a text reason, or both, but strictly in the same way as entered in the VAT breakdown.

This change is also essential for managing multi-seller invoices, as the VAT exemption reason in text is used to identify the different sub-invoices and thus produce a VAT breakdown for each sub-invoice.

The tolerance for not taking into account line level VAT exemption reasons and document-level allowances and charges for the EXTENDED-CTC-FR profile will continue until at least summer 2026.

4.4 Special points to note

4.4.1 Data types

Each piece of data in the semantic model corresponds to a data type that determines its format, which is based on one of the following four primitive types: Binary, Date, Decimal, String (text).

The data types are as follows (for more details, see chapter 6.5 of the EN 16931-1:2019 (E) Semantic Standard):

- **Amount:** this is a "Decimal" type with a maximum of 2 digits after the decimal point, no thousand separator, and "." as the decimal separator. It can be supplemented with a "Currency" attribute if different from the currency in the header. The UBL always requires the Currency, while the CII only requires it when an amount can be expressed in a currency other than that of the invoice (the amount of VAT BT-111 in the accounting currency (BT-6) if different from the currency of the invoice (BT-5)). Example 10000.34
- **Unit price amount:** this is a "Decimal" type without a thousand separator, and with "." as the decimal separator. It can be supplemented with a "Currency" attribute if different from the currency in the header. Example 1000.3454. There is no rule regarding the number of decimal places, but usage and, above all, the revision of Standard EN16931 limits unit prices to 4 decimal places.
- **Quantity:** this is a "Decimal" type without a thousand separator and with "." as the decimal separator. Example 10000.85476. There is no rule regarding the number of decimal places, but usage and, above all, the revision of Standard EN16931 limit quantities to 4 decimal places.

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

- **Percentage:** this is a "Decimal" type with no thousand separator and a "." as the decimal separator. To apply this percentage to the amount to which it applies, divide the percentage value by 100 in your calculations. For a VAT rate of 20%, the value is therefore 20. Example: 24.1234 for a percentage of 24.1234%. There is no rule regarding the number of decimal places, but usage and, above all, the revision of the EN16931 standard limit percentages to 2 decimal places.
- **Identifier:** this is a type that can consist of up to three text fields (described in the detailed documentation):
 - ✓ The value of the identifier (text). For example, FR13456789321 for an intra-Community VAT number
 - ✓ An identification scheme (Scheme Identifier), mandatory if several identification schemes are possible, allowing the identifier's reference system to be specified. For example, the qualifier "VA" specifies that the identifier is an intra-Community VAT number in CII. In UBL, "VAT" shall be used.
 - ✓ A version of the Scheme Identifier (Scheme version Identifier), optional text data
- **Document Reference:** this is text data
- **Date:** dates are represented in the format YYYYMMDD in UN/CEFACT CII and YYYY-MM-DD in UBL
- **Text:** free text, text type
- **Code:** this is a text-type code, accompanied by an attribute identifying the list from which it originates, and potentially the version of the list and the identifier of the agency publishing the list.
- **Binary Object:** this is a type that can potentially consist of three fields:
 - ✓ The content, mandatory, in binary data,
 - ✓ The file type (Mime Code), in text, to be taken from a predefined list,
 - ✓ The file name (Filename), in text.

4.4.2 Profile data management and invoicing framework

In order to organize invoice processing, invoices shall contain information identifying the profile and the underlying transaction process.

This is achieved through two essential pieces of data:

- **BT-24:** profile type, which identifies the message profile, distinguishing between EN16931, EXTENDED-CTC-FR and Factur-X profiles:
 - ✓ EN16931 profile: urn:cen.eu:en16931:2017
 - ✓ EXTENDED-CTC-FR profile:
urn:cen.eu:en16931:2017#conformant#urn.cpro.gouv.fr:1p0:extended-ctc-fr
 - ✓ For Factur-x:
 - For the BASIC WL profile: urn:factur-x.eu:1p0:basicwl
 - For the BASIC profile: urn:cen.eu:en16931:2017#compliant#urn:factur-x.eu:1p0:basic
 - For the EN 16931 profile: urn:cen.eu:en16931:2017
 - For the EXTENDED profile: urn:cen.eu:en16931:2017#compliant#urn:factur-x.eu:1p0:extended
- **BT-23:** indicates the underlying process and is used in France to code both certain processes and the fact that the invoice is for Goods, Services, or Mixed, i.e., composed of sales lines for Goods and sales lines for Services that are independent of each other and not ancillary to each other. This characteristic is coded by the first letter of the invoicing framework B, S, or M. Rule BR-FR-08 indicates the possible values for this invoicing framework.

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

It is also necessary to determine whether an invoice falls under "e-invoicing" or e-reporting for international B2B sales, or B2C e-reporting or non-reform e-reporting, etc. There is no simple rule for determining with certainty whether an invoice falls under "e-invoicing."

This information can be coded in the invoice transmission channel between the issuer and its "Plateformes Agréées" (PA, Accredited Platforms), but can also be included in the invoice itself. In this case, the rule to follow is BR-FR-20, which uses a note with the subject code "BAR" and coded values to be filled in.

4.4.3 Management of Notes

A number of mandatory or conditionally mandatory entries do not exist in the EN16931 template and are therefore coded using a Note (text in BT-22) with a dedicated subject code (in BT-21). The same applies to line notes (Content: BT-127, subject code: EXT-FR-FE-183). Rules BR-FR-05, BR-FR-06, and BR-FR-07 indicate the expected coding.

Among all the subject codes, the list below details the subject codes to be used for the most common subjects:

- AAB: Discount mention.
- AAI: General information: items generally found at the bottom of the page on paper invoices.
- ABL: Legal information: for example, trade register number, RCS.
- ACC: Factoring subrogation clause.
- ADN: indicates that the invoice is subject to B2G obligations in France (B2G value, see rule BR-FR-CPRO-00).
- BAR: indicates the nature of the expected processing, see rule BR-FR-20.
- BLU: "Eco-participation (L. 541-10 of the Environmental Code)" or "WEEE eco-contribution." May also be used for other taxes, including the eco-tax. CUS: Customs information.
- DCL: Declaration by the creator of the invoice, in the event of an invoicing mandate: "invoice issued by A in the name and on behalf of B."
- PMT: Reference to the fixed compensation of €40 for collection costs.
- PMD: Reference to late payment penalties.
- SUR: Supplier's comments.
- TXD: Reference to Single Taxable Entity ("Membre d'Assujetti Unique").

4.4.4 Credit note management

There are two ways to manage credit notes:

- **"Negative invoice":** This is an invoice with a negative total with VAT,
 - ✓ either because the invoice contains negative lines whose sum is greater in absolute value than the sum of the positive lines (this is particularly the case for final invoices with a refund on a pre-payment or estimate, such as energy bills, for which it may also happen that an invoice only has negative refund lines),
 - ✓ either because it only contains negative lines and therefore generally cancels out an invoice. (except in exceptional cases where there are no positive lines, as indicated above). It is therefore a credit note, which shall refer to the invoice or period to which it relates. At the line level, the unit price is positive and the quantities are negative. The calculation rules remain the same and result in negative lines, then negative totals (including the breakdown of VAT details on the pre-tax bases and the tax amounts). In this case, the amounts of allowances and charges are also reversed (i.e., negative). The document types (BT-3 data) that can be subject to this process are those

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

corresponding to invoices (i.e., it is therefore not permitted to create negative credit notes for invoices).

- **"Credit note":** this corresponds to "credit note" documents (such as 381, 261, etc.). In this case, all the total amounts in the lines or footers have the same sign as the invoice that the credit note cancels, which does not prevent there being lines with a negative total amount, as is possible on an invoice. However, it is not possible (authorized according to the semantic standard) to have negative credit notes, i.e., to use a negative credit to cancel a previous positive credit. In this case, an invoice referencing the credit note shall be created. It is also not permitted to have credits with a negative total including tax when this is the result of positive and negative lines, which could be the case for credit notes which cancel out negative invoices because the negative lines outweigh the positive lines. In this case, it is preferable to issue corrected invoices which cancel and replace the erroneous negative invoices.

In France, the most common practice is to code a credit note that cancels an invoice using the "credit note" type. This means that all the data in the credit note is the same as that in the invoice it cancels. The only changes are the credit note invoice number (which shall follow the chronological sequence, as with invoices), the date of the credit note, and the invoice number that the credit note cancels, which shall be entered, and potentially the due date.

The "negative invoice" representation is used when it results from an invoicing calculation that leads to this result, due to reversals on previous invoices (estimates, pre-payments, consignment notes, pallets, etc.).

However, there are countries in Europe that exclusively use negative invoices (even for credit notes that only cancel an invoice).

4.4.5 Calculation rules

The calculation rules for invoices (excluding B2C invoices, in which the unit price is often indicated inclusive of tax) is as follows:

- For each line item, the net line amount (BT-131) is equal to:
 - ✓ the net unit price (positive, BT-146), divided by the base quantity of the price BT-149, which indicates the quantity of each batch of product sold, multiplied by the invoiced quantity (positive or negative, BT-129), rounded to 2 decimal places.
 - ✓ minus the line allowance amounts (BT-136), which are already rounded to 2 decimal places,
 - ✓ increased by the amounts of line charges or fees (BT-141), which are already rounded to 2 decimal places.
 - ✓ This calculation rule is not governed by a schematron rule because it is not required by EN 16931 standard at this time. It will be added in the revision of the Standard with a tolerance to handle rounding problems.
 - ✓ It should also be noted that the unit of measurement for the base quantity of the Unit price (BT-149) SHALL be equal to the unit of the invoiced quantity (BT-130) for the calculation to be correct. If the unit price is per gram and the quantity is measured in kilograms, the above calculation would be incorrect by a factor of 1,000.
- Next, the totals at the document level are organized as follows and are verified within the framework of the management rules of Standard EN 16931 (BR-XX):
 - ✓ The sum of net line amounts (BT-106), equal to the sum of the net line amounts calculated above,
 - ✓ The sum of allowances at document level (BT-107), equal to the sum of the allowance amounts at document level (BT-92), see BR-CO-11.
 - ✓ Sum of charges or fees at document level (BT-108) equal to the sum of the amounts of charges or fees at document level (BT-99), see BR-CO-12.

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

- ✓ The total pre-tax amount of the invoice (BT-109) is equal to (BR-CO-13):
 - the total net line amounts (BT-106),
 - minus the total allowances at document level (BT-107),
 - plus the total charges or expenses at document level (BT-108),
- ✓ The total VAT amount (BT-110) is equal to the sum of the VAT amounts (BT-117) by VAT rate and type, see BR-CO-14.
- ✓ The VAT type makes it possible to distinguish between different cases, in particular where VAT is not applicable. The VAT amount per rate corresponds to the tax-exclusive base for each VAT rate multiplied by the VAT rate, divided by 100 and rounded to two decimal places. The tax-exclusive base for each VAT rate is equal to the sum of the net line amounts (BT-131) that fall under the same VAT rates and types, plus the sum of the net amounts of document charges or fees (BT-108) that fall under the same VAT rates and types, minus the sum of the net amounts of Document allowances (BT-107) that fall under the same VAT rates and types.
- ✓ For the EXTENDED-CTC-FR profile (and the upcoming revision of the Standard), this calculation is enhanced with additional criteria:
 - Firstly, on the grounds for VAT exemption in text (EXT-FR-FE-178) and code (EXT-FR-FE-179) at line level, as well as at document-level allowances and charges (EXT-FR-FE-187, EXT-FR-FE-188, EXT-FR-FE-189, EXT-FR-FE-190), consistent with the BT-120 / B-121 pair in VAT breakdown, and (BG-23),
 - then for taking into account only lines without a line subtype (line status reason code: EXT-FR-FE-163) or with a line subtype equal to "DETAIL".
- ✓ The total amount with VAT (BT-112) of the invoice is equal to the sum of the total amount without VAT (BT-109) and the total amount of VAT (BT-110), see rule BR-CO-15.
- ✓ The pre-payment amount (BT-113) is equal to the amount already paid before the invoice was issued or paid elsewhere or by a third party, which will be deducted from the amount with VAT to determine the net amount payable by the BUYER to the SELLER or the PAYEE.
- ✓ In some cases, there may be a rounding amount (BT-114) to be added to determine the net amount to be paid (BT-115).
- ✓ The net amount to be paid (BT-115) is equal to the total amount with VAT (BT-112) minus the pre-payment amount (BT-113) and, where applicable, plus the rounding amount (BT-114), see rule BR-CO-16.

As these calculation rules may not be followed when calculating VAT at the line level or for invoices with prices defined including VAT (in particular for B2C invoices), the EXTENDED-CTC-FR profile (and EXTENDED in Factur-X) introduces a tolerance of 0.01€ per line and per allowance or charge at document level in the various calculation amounts involved.

4.4.6 Rounding rules in calculations

The rules for calculating an invoice require rounding at certain stages (whenever there is multiplication or division). The rounding method is to the nearest value, with the following rule for determining the residual fraction to the nearest 0.5:

- For positive numbers: round up to the nearest whole number. For example, 13.455 rounded to 2 digits gives 13.46.
- For negative numbers: round down (so that rounding two strictly opposite numbers gives strictly opposite rounded numbers). For example, -13.455 gives -13.46.

4.4.7 VAT management

For each line of the invoice, the applicable VAT shall be specified. There are several reasons why VAT may not be included or may be reduced to 0 on the invoice. The different VAT categories are coded as follows:

- **S: Standard VAT rate**, which shall then be specified.
- **Z: VAT rate equal to 0**. This does not apply in France at present.
- **E: VAT exempt**. To be used if none of the other cases of VAT exemption apply. In this case, it is mandatory to indicate the reason for the exemption in the VAT details at the bottom of the invoice, referring to the applicable tax provision.
- **AE: Reverse charge VAT**. In this case, VAT is payable by the customer, who shall declare and pay it directly to the tax authorities (in general, the customers simultaneously deduct the same VAT). The reason for the absence of VAT to be indicated in the VAT details at the bottom of the invoice is "Reverse charge". The VATEX code to be used is VATEX-EU-AE or, where applicable, VATEX-FR-AE in the case of reverse charge VAT on domestic invoices, with VATEX-EU-AE also being the preferred option.
- **K: Reverse charge due to intra-Community delivery**. This is the reverse charge mechanism, but it applies due to an intra-Community delivery. Therefore, code "K" shall be used instead of code "AE." The reason for the absence of VAT, which shall be indicated in the VAT details at the bottom, is "Intra-Community delivery." The VATEX code to be used is VATEX-EU-IC.
- **Case of sales of services in the EU**: sales of services in the EU are subject to reverse charge VAT by the recipient and are not intra-Community supplies of goods. Although category code K means "VAT exemption for intra-Community sales of goods or services," the tax rule requires the use of category code AE and code VATEX-EU-AE for these sales of services in the EU. Confirmation of the uniform application of this rule in the EU is currently being investigated.
- **G**: Exempt from VAT for exports outside the European Union, the VATEX code to be used is VATEX-EU-G. Service sales outside the EU also use the same category code G and VATEX-EU-G code, pending a more specific solution at the European level, which is currently under review.
- **O: Outside the scope of VAT**. In this case, there can be no other VAT categories on the invoice (rule BR-O-11 of Standard EN 16931). The VATEX code to be used is VATEX-EU-O. However, the EXTENDED-CTC-FR profile (and EXTENDED from Factur-X) has removed rule BR-O-11, which allows invoices to be issued with lines in category O and other lines in other VAT categories.
- **L (IGIC) and M (IPSI)**: not applicable in France and Germany as these are VAT regimes for the Canary Islands and Ceuta/Melilla respectively.

At the bottom of the invoice, each VAT category appearing in the lines shall be included in the VAT breakdown, with the tax-exclusive base equal to the sum of the tax-exclusive amounts of the lines in the VAT category, the VAT category code, the VAT rate (equal to 0 in the case of exemption and not present in the case of "outside scope: O"), the VAT amount (zero if no VAT), and in all cases except "S," the reason for zero VAT.

4.4.8 Management of taxes other than VAT, case of the WEEE eco-contribution

When goods or services are subject to taxes other than VAT, two situations arise:

- The tax is subject to VAT at the same rate as the product or service to which it applies: in this case, the tax is managed as a charge on the invoice line. A reason (BT-144) or reason code (BT-145) is used to identify that it is a tax.
- As part of the revision of Standard EN16931, a dedicated list of codes to qualify the type of tax will be added. It will be included in the EXTENDED-CTC-FR / EXTENDED profiles in a future version of this Standard.
- The tax is not subject to VAT or is subject to a VAT rate different from that of the goods or services to which it refers: in this case, the tax is coded as an additional service line.

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

As there may be a large number of parafiscal taxes, a fairly widely used practice is to use specific item lines using a coding system proposed by GS1 through GTIN (item identifiers to be placed in BT-157 with SchemeID in BT-157-1 equal to 160) listed at this link: <https://www.gs1.fr/publication/liste-taxes-assimilees>.

Similarly, when a tax applies to the entire invoice (at document level), it can be treated as a charge at document level, for which a reason (BT-104) or a reason code (BT-105) can be indicated, and then the applicable VAT (or non-applicable VAT) can be defined in BT-102 and BT-103.

In particular, information on the WEEE eco-contribution shall be included in invoices. It is generally included in the unit price and is provided as information ("including xx.xx € eco-contribution") in a line note (BT-127) and/or in a document note (BT-21 = "BLU", BT-22). It serves no purpose for the integration of the invoice by the buyer.

The revision of the EN16931 standard provides for the inclusion of non-VAT taxes in line-level and document-level charges. This is achieved through the coding of additional reasons (BT-193 at the line level and BT-177 at the document level) using the UNTDID 5153 list—excluding the value "VAT"—as an alternative to the charge reason code (BT-145 or BT-105), which must be selected from the UNTDID 7161 list.

This has been incorporated into the EXTENDED-CTC-FR profile (and the Factur-X EXTENDED profile).

4.4.9 Management of allowances and charges

Allowances and charges are managed at three levels:

- At the document level, for global allowances or charges on the invoice. These allowances and charges are similar to additional lines. For example, they have their own VAT. They are present on all profiles. They are subject to a dedicated sum in the "Document Totals" block BG-22 (BT-108 and BT-107 respectively).
- At the line level, relating to the invoice line, with the same VAT rate as the line (otherwise they shall be entered independently as a positive line for charges and a negative line for allowances). They are included in the net line amount BT-131 (which is therefore equal to the quantity multiplied by the net price plus the sum of the charges and minus the sum of the allowances for the line).
- At the unit price level, only for a rebate (BT-147) which allows to switch from a gross unit price (BT-148), which therefore includes any charges or taxes (such as the eco-tax), to a net unit price (BT-146).

In the UN/CEFACT CII D22B XML syntax, allowances and charges are coded with the same object "SpecifiedTradeAllowanceCharge" in CII and "cac:AllowanceCharge" in UBL, which shall therefore be qualified by the "ChargeIndicator" indicator, which shall be equal to (udt:Indicator in CII, cbc:ChargeIndicator in UBL) to "false" for a allowance and "true" for a charge. The same applies in UBL.

The allowance and charge amounts are both positive (unless it is necessary to indicate a reversal of an allowance or charge, for example in the case of a credit note expressed as a negative invoice).

In the description, this block is therefore repeated once for allowances and once for charges, for clarity.

These allowances and charges are optional and repeatable blocks (cardinality 0..n).

Finally, the "SpecifiedTradeAllowanceCharge" block in UN/CEFACT CII and "cac:AllowanceCharge" in UBL, solely for the application of a rebate corresponding to a reduction in the gross price to constitute the net price (BT-147), bearing in mind that the gross price is optional, unlike the net price, which is mandatory. However, the gross unit price may be mandatory, as is the case in France, if it differs from the net unit price.

"SpecifiedTradeAllowanceCharge" block in UN/CEFACT CII and "cac: AllowanceCharge" in UBL, is also used solely for the application of a rebate (BT-147) on the gross price (BT-148) to constitute the net price (BT-146), bearing in mind that the gross price is optional in Standard EN16931, unlike the net price, which is mandatory. However, the gross unit price may be mandatory, as is the case in France, if it differs from the net unit price.

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

4.4.10 Code Management

A number of data fields shall be selected from code lists. These are part of the EN16931 standard specifications and are updated every six months, effective May 15 and November 15 of each year. This is generally an enhancement, i.e., new codes are added. In very rare cases, some codes may be removed. This is the only source of upward incompatibility, which remains very anecdotal. It is therefore advisable to monitor changes to these code lists in order to assess any potential impact. They are published more than one month before they come into effect.

IMPORTANT: Code lists are primarily managed by the UNECE (United Nations Economic Commission for Europe), which produces UN/CEFACT standards. Consequently, the UN/CEFACT CII syntax has standardized the code lists applicable to the data using them. The EN16931 standard has sometimes made different choices—primarily regarding the management of codes for reasons for allowances, charges, or taxes (where different lists are used despite employing the same syntax components) and the document type code list (which is a subset of the full list, focusing solely on invoice or credit note documents).

To allow for this flexibility, the UNECE has published two XSD versions for UN/CEFACT:

A "coupled" version—linked to the full code lists defined by the UNECE.

An "uncoupled" version—decoupled from these lists (meaning no list-based validation occurs at the XSD level).

Therefore, the "uncoupled" version of the UN/CEFACT CII XSD must be used. List validation is instead performed via the Schematron rules for EN16931 compliance.

The UBL XSD is not coupled with code lists.

4.4.11 Management of sub-lines in the EXTENDED-CTC-FR profile (and EXTENDED in Factur-X)

For certain use cases, it is necessary to provide:

- subtotals grouping together invoicing lines together,
- or provide information on sub-items that make up a main item sold (for example, a toolbox kit comprising a box and various tools),
- or break down an item into basic items that have their own VAT rates, such as a toy book that is the item purchased and delivered, but which consists of a book with 10% VAT and a toy with 20% VAT,
- or group lines by transaction, such as a transport line, with its sub-lines for supplements and options (fuel surcharge, weekend surcharge, etc.),
- or to have lines with subtotals, for example, by delivery, by order, etc.

And of course, this can be constructed on several levels, for example a GROUP line to detail one delivery among others, with sub-lines of composite items, which themselves have DETAIL sub-lines, and so on.

To manage all these use cases, it is first necessary to allow lines to be grouped hierarchically using the "Parent Line ID" data (EXT-FR-FE-162), which indicates the line number to which a line is attached.

Next, in order to avoid adding the same thing multiple times (for example, by adding line amounts and subtotals), line qualification is necessary in order to first distinguish the invoice lines to be taken into account in the calculation of totals and VAT footers, and then to distinguish grouping and subtotal lines from simple information lines.

To do this, the "line subtype" data (EXT-FR-FE-163) shall then be used with the following values:

- "DETAIL": is a line included in the calculation of totals and VAT, along with "standard" lines without a line subtype qualifier. These are also the lines that SHALL be extracted for the creation of flows 1 and 10.1 (see rule BR-FR-MAP-24).
- "INFORMATION": is a line providing additional information, for which all the data in a line may or may not be used. This means that the mandatory presence of the net unit price (BT-146), the invoiced

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

quantity (BT-129) and its unit of measurement (BT-130), VAT information (BG-30) and the line total without VAT (BT-131) become optional (rules BR-FREXT-09). If the line total amount without VAT (BT-131) is present, it is not taken into account in the calculation of totals and VAT footers (see VAT management rules BR-FREXT-ZZZ).

- “GROUP”, which can be seen as a special “INFORMATION” line with optional data, but for which the presence of the line amount without VAT (BT-131) requires that this amount be equal to the amounts without VAT of the sub-lines directly attached to it and which have a line subtype equal to “DETAIL” or GROUP (see BR-FREXT-08). Consequently, when a “GROUP” line has a line amount without VAT (BT-131), the “GROUP” lines attached to it SHALL also have a line amount without VAT (BT-131).

Example of use 1: Use the "INFORMATION" lines to complete the description of the item: The sale of 2 "Toolbox" kits, each containing 3 pliers, 5 hammers, and 1 screwdriver (for a total of 6 pliers, 10 hammers, and 2 screwdrivers). The price is set at the KIT level, with the "INFORMATION" lines providing the details. The lines in blue are grouped together. Line 1 could also have been classified as "DETAIL." Line 2 is an additional independent information line. Line 3 is a standard line.

Lines										
LineID	Parent LineID	LineStatus ReasonCode	Name	Invoiced Quantity	Per Package Qty	Unit of measure	PU Net	VAT Category code	VAT rate	Invoice line net amount
BT-126	BT-X-304 EXT-FR-FE-162	BT-X-8 EXT-FR-FE-163	BT-153	BT-129	BT-X-561 EXT-FR-FE-191	BT-130	BT-146	BT-151	BT-152	BT-131
1			Toolbox	2		C62 (unit)	199,00	S	19%	398,00
1.1	1	INFORMATION	Pliers	6	3	C62 (unit)				0,00
1.2	1	INFORMATION	Hammer	10	5	C62 (unit)				0,00
1.3	1	INFORMATION	Screwdriver	2	1	C62 (unit)				0,00
2		INFORMATION	Free bag	1		C62 (unit)				0,00
3			Nails	500		C62 (unit)	0,02	S	19%	10,00

VAT Breakdown

Basis Amount	Category Code	VAT rate	VAT Amount
BT-115	BT-118	BT-119	BT-117
408,00	S	19%	77,52

Totals

Total without VAT (BT-109)	408,00
Total VAT (BT-110)	77,52
Total with VAT (BT-112)	485,52

Example of use 2: composite items with multiple VAT rates: Toy book. The totals and VAT are calculated on the DETAIL lines (50 and 75). The GROUP line does not provide VAT information as it would not make sense. It is not transmitted in flow 1 or 10.1.

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

Lines

LineID	Parent LineID	LineStatus ReasonCode	Name	Invoiced Quantity	Per Package Qty	Unit of measure	PU Net	VAT Category code	VAT rate	Invoice line net amount
BT-126	BT-X-304 EXT-FR-FE-162	BT-X-8 EXT-FR-FE-163	BT-153	BT-129	BT-X-561 EXT-FR-FE-191	BT-130	BT-146	BT-151	BT-152	BT-131
1		GROUP	Book-toy	5		C62 (unit)	25,00			125,00
2	1	DETAIL	Book-toy	5	1	C62 (unit)	10,00	S	10%	50,00
3	1	DETAIL	Toy	5	1	C62 (unit)	15,00	S	20%	75,00

VAT Breakdown

Basis Amount	Category Code	VAT rate	VAT Amount
BT-115	BT-118	BT-119	BT-117
75,00	S	20%	15,00
50,00	S	10%	5,00

Totals

Total without VAT (BT-109)	125,00
Total VAT (BT-110)	20,00
Total with VAT (BT-112)	145,00

NOTE: the line number does not need to replicate the structure (1.1, 1.2). The Parent line identifier is sufficient for this purpose.

Example of use 3: sub-lines to link them to a main line: a transport service, with a main line, which can contain several data items and references (here, the item invoiced for a parcel number, but there may also be the pick-up address, the delivery address, customer references, , etc.) that do not need to be repeated in each sub-line of the service supplement (various extras).

Lines

LineID	Parent LineID	LineStatus ReasonCode	Name	Invoiced Object	Invoiced Quantity	Unit of measure	PU Net	VAT Category code	VAT rate	Line Total amount without VAT
BT-126	BT-X-304 EXT-FR-FE-162	BT-X-8 EXT-FR-FE-163	BT-153	BT-128	BT-129	BT-130	BT-146	BT-151	BT-152	BT-131
1			Delivery	Package number	1	C62 (unit)	25,00	S	20%	25,00
2	1	DETAIL	Diesel supplement		1	C62 (unit)	3,00	S	20%	3,00
3	1	DETAIL	Week end supplement		1	C62 (unit)	5,00	S	20%	5,00

VAT Breakdown

Basis Amount	Category Code	VAT rate	VAT Amount
BT-115	BT-118	BT-119	BT-117
33,00	S	20%	6,60

Totals

Total without VAT (BT-109)	33,00
Total VAT (BT-110)	6,60
Total with VAT (BT-112)	39,60

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

Example of use 4: multiple levels of sub-lines: the sale of 2 displays, each consisting of 3 packs of Kenya Roast, 6 packs of Dark Roast, and 3 bundles themselves consisting of 3 packs of Columbia Roast and 3 MUGs, with potentially different applicable VAT rates (for the example). This illustrates the fact that lines can be organized on several levels. Again, only DETAIL lines count in the calculation of totals and VAT breakdowns and are transmitted in flows 1 and 10.1.

Lines

LineID	Parent LineID	LineStatus ReasonCode	Name	Invoiced Quantity	Per Package Qty	Unit of measure	PU Net	VAT Category code	VAT rate	Line Total amount without VAT
BT-126	BT-X-304 EXT-FR-FE-162	BT-X-8 EXT-FR-FE-163	BT-153	BT-129	BT-X-561 EXT-FR-FE-191	BT-130	BT-146	BT-151	BT-152	BT-131
1		GROUP	Coffee display	2		C62 (unit)				216,00
1.1	1	DETAIL	Kenya Roast	6	3	C62 (unit)	5,00	S	7%	30,00
1.2	1	DETAIL	Dark Roast	12	6	C62 (unit)	5,00	S	7%	60,00
1.3	1	GROUP	Colombia Bundle	6	3	C62 (unit)				126,00
1.3.1	1.3	DETAIL	Colombia Roast	18	3	C62 (unit)	5,00	S	7%	90,00
1.3.2	1.3	DETAIL	Mug	18	3	C62 (unit)	2,00	S	19%	36,00

VAT Breakdown

Basis Amount	Category Code	VAT rate	VAT Amount
BT-115	BT-118	BT-119	BT-117
36,00	S	19%	6,84
180,00	S	7%	12,60



Totals

Total without VAT (BT-109)	216,00
Total VAT (BT-110)	19,44
Total with VAT (BT-112)	235,44

4.4.12 Multi-seller invoices

Many use cases involve a transparent intermediary who invoices a single BUYER on behalf of several sellers, but in a single consolidated invoice. For example, water supply invoices also include sanitation services sold by other sellers. Taxi booking companies invoice business customers monthly on behalf of each taxi, etc.

To ensure continuity of practice, a specific extension has been added to the EXTENDED-CTC-FR profile. The aim is to allow several individual invoices from several SELLERS to be grouped together in a single invoice for the BUYER, who treats it as a standard invoice. However, flows 1 and 10.1 SHALL be created on an individual invoice basis.

4.4.12.1 How to create multi-seller invoice

In principle, a multi-seller invoice contains one unit invoice per vendor, but it is possible to have several different invoices from the same vendor, including the primary vendor (a scenario observed particularly with certain G2B invoices due to multiple billing entities being linked to the same public entity SIREN).

However, all unit invoices SHALL have the same Invoice Date (BT-2) and the same invoice type (BT-3).

To identify these specific invoices, the Business process type or "Billing Framework" (BT-23 : "Cadre de Facturation") SHALL be chosen from the following three values: B8 (Goods invoice); S8 (Services invoice); M8 (mixed invoice with Goods lines and Service lines), to be used when this invoice groups together unit invoices that are not all either Goods or Services.

The multi-seller invoice uses sub-line management, creating a line (BG-25) of type "GROUP" for each unit invoice that is not attached to another line (i.e., with a line subtype (EXT-FR-FE-163) equal to "GROUP" and without a Parent Line ID (EXT-FR-FE-162)), in which all the information specific to the unit invoice will be present, namely:

- the line level Seller (EXT-FR-FE-BG-12), corresponding to block BG-4 of the unit invoice, including:
 - ✓ the company name (EXT-FR-FE-164),

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

- ✓ the legal identifier of the line level seller (EXT-FR-FE-167),
- ✓ the intra-community VAT number (EXT-FR-FE-168), corresponding to BT-31 of the unit invoice, and, where applicable, the tax identifier (EXT-FR-FE-169), corresponding to BT-32 (used, for example, by a Franchisee in Base who does not have a VAT number),
- ✓ the country of the line level Seller's address,
- the unit invoice number, coded with the Invoiced Object Identifier at line level (BT-128), with the qualifier (BT-128-1) equal to AFL, corresponding to BT-1 of the unit invoice,
- the “billing framework” (“Cadre de facturation”) coded with the Invoiced Object identifier at line level (BT-128), with the qualifier (BT-128-1) equal to AVV, corresponding to BT-23 of the unit invoice,
- the VAT TaxPoint code (EXT-FR-FE-180), corresponding to BT-8 of the unit invoice (as it is possible that some unit invoices are with VAT due on invoice issuance (“au debit”) and others with VAT due upon receipt of payment (“à l’encaissement”)),
- the VAT amount per line (EXT-FR-FE-181) in the invoice currency (BT-5), which will provide the total VAT amount of the unit invoice in the invoice currency (BT-110),
- the VAT amount per line (EXT-FR-FE-182) in the accounting currency (BT-6), which will provide the total VAT amount for the unit invoice in the accounting currency (BT-111),
- the Total line amount with VAT (EXT-FR-FE-184), which will provide the total invoice amount with VAT per unit invoice (BT-112 of unit invoice).
- It is not necessary to enter VAT category code, rate, and exemption reason information in text or code (they will not be used in the calculations).

Next, the lines of each unit invoice SHALL comply with the following rules:

- Contain the unit invoice number (coded with the Invoiced Object Identifier in the line (BT-128, with the qualifier (BT-128-1) equal to AFL).
- Contain the legal identifier of the line level seller (EXT-FR-FE-167).
- To enable VAT breakdown by unit invoice, the reason for exemption in text at line level (EXT-FR-FE-178) SHALL begin with the invoice number between # followed by the exemption text if applicable.

The VAT breakdown is calculated in accordance with the rules of the EXTENDED-CTC-FR profile, with the VAT Category (BT-118) as the partial sum key, the VAT rate (BT-119), the exemption reason in text (BT-120) and code (BT-121) also usable for categories S and Z, and only "DETAIL" lines or lines without a subtype, as well as document level allowances or charges.

Situation 3 Sellers SELLER : VENDEUR A INVOICER : VENDEUR A														<table> <tr> <td>BT-1</td><td colspan="9">F20250025</td></tr> <tr> <td>BT-2</td><td colspan="9">01/10/2025</td></tr> <tr> <td>BT-3</td><td colspan="9">380</td></tr> <tr> <td>BT-8</td><td colspan="9">5</td></tr> <tr> <td>BT-23</td><td colspan="9" rowspan="3"> Business Process (Cadre de Facturation) S8/B8/M8 stands for "Multi-Vendor Invoice." The business process (Cadre de Facturation) for unit invoices is described in BT-128, SchemeID = AVV. </td></tr> </table>									BT-1	F20250025									BT-2	01/10/2025									BT-3	380									BT-8	5									BT-23	Business Process (Cadre de Facturation) S8/B8/M8 stands for "Multi-Vendor Invoice." The business process (Cadre de Facturation) for unit invoices is described in BT-128, SchemeID = AVV.								
BT-1	F20250025																																																																							
BT-2	01/10/2025																																																																							
BT-3	380																																																																							
BT-8	5																																																																							
BT-23	Business Process (Cadre de Facturation) S8/B8/M8 stands for "Multi-Vendor Invoice." The business process (Cadre de Facturation) for unit invoices is described in BT-128, SchemeID = AVV.																																																																							
Vendeur A issues an invoice containing 3 groups of line items, one for each final seller (including Vendeur A).																																																																								
Multi-Vendor Invoice																																																																								
Line ID	Parent line ID	Subtype of invoice line	Item name	Item Description	Unit Price	Quantity	Line SELLER Name	Line SELLER legal ID	Line SELLET VAT ID	Line SELLER Country code	Unit invoice ID	VAT point date code (~BT-8)	Business process type (Cadre de facturation) for unit invoice	Line total amount	VAT Category code	VAT rate	VATEX code	VATEX (text)	Line total VAT	Line total with VAT																																																				
BT-126	EXT-FR-FE-162 (BT-X-304)	EXT-FR-FE-163 (BT-X-8)	BT-153	BT-154	BT-146	BT-129	EXT-FR-FE-164	EXT-FR-FE-167	EXT-FR-FE-168	EXT-FR-FE-177	BT-128	BT-128-1	EXT-FR-FE-180	BT-128	BT-128-1	BT-131	BT-151	BT-152	EXT-FR-FE-179	EXT-FR-FE-178	EXT-FR-FE-181	EXT-FR-FE-184																																																		
1		GROUP	Unit invoice VENDEUR A				VENDEUR A	123456782	FRxx123456782	FR	F20250025	AFL	5	S1	AVV	2 500,00				350,00	2 850,00																																																			
2	1	DETAIL	Service A	ceci	1 000,00	1,00		123456782			F20250025	AFL				1 000,00	S	20,00%	#F20250025#																																																					
3	1	DETAIL	Service B	cela	500,00	3,00		123456782			F20250025	AFL				1 500,00	S	10,00%	#F20250025#																																																					
4		GROUP	Unit invoice VENDEUR X				VENDEURX	321654879	FRxx321654879	FR	123456782_321654879_F20250025	AFL	72	S1	AVV	5 500,00				1 100,00	6 600,00																																																			
5	4	DETAIL	Service X	ceci	300,00	5,00		321654879			123456782_321654879_F20250025	AFL				1 500,00	S	20,00%	#123456782_321654879_F20250025#																																																					
6	4	DETAIL	Service Z	cela	1 000,00	4,00		321654879			123456782_321654879_F20250025	AFL				4 000,00	S	20,00%	#123456782_321654879_F20250025#																																																					
7		GROUP	Unit invoice VENDEUR 00				VENDEUR00	254136987	FRxx254136987	FR	123456782_254136987_F20250025	AFL	72	S1	AVV	850,00				170,00	1 020,00																																																			
8	7	DETAIL	Service 25	ceci	12,00	50,00		254136987			123456782_254136987_F20250025	AFL				600,00	S	20,00%	#123456782_254136987_F20250025#																																																					
9	7	DETAIL	Service 32	cela	25,00	10,00		254136987			123456782_254136987_F20250025	AFL				250,00	S	20,00%	#123456782_254136987_F20250025#																																																					

Base VAT	VATEX Code	VATEX Text	VAT code	VAT rate	VAT amount
BT-116	BT-121	BT-120	BT-118	BT-119	BT-117
1 000,00		#F20250025#	S	20,00%	200,00
1 500,00		#F20250025#	S	10,00%	150,00
5 500,00		#123456782_32165487			

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

LOGO LE VENDEUR VENDEUR NOM COMMERCIAL LE VENDEUR 35 rue d'ici, ligne 2 vendeur 75018 PARIS, FR CONTACT : DEP ADV, 01 02 03 54 87, contact@vendeur.fr @dresse électronique (0225) : 100000009_STATUTS GLN : 587451236587 SIREN : 100 000 009 N° TVA intra : FR 88 100 000 009	FACTURE N° : F202600022 Date : 05/01/2025 CLIENT : DEP COMPTAFOUR LE CLIENT CLIENT NOM COMMERCIAL 55 avenue de là-bas acheteur ligne 2 06000 MA VILLE, FR @dresse de facturation (0225) : 200000008 Contact: 01 01 25 45 87, contact@acheteur.fr Vos identifiants GLN : 3654789851 SIREN : 200 000 008 N° TVA : FR 37 200 000 008 Livraison: adresse, références NOUS AUSSI 12 impasse plus loin livré à ligne 2 06000 MA VILLE, FR DEVISE : EURO (EUR)																																																																								
Nos références N° DE CLIENT : REF_CLIENT2514 N° BON DE VENTE : SO20255874 Vos références REFERENCE ACHETEUR / SERVICE EXECUTANT : BU_2516 N° BON DE COMMANDE : PO202525478 Références sur la facture CADRE DE FACTURATION : S8 DATE DE DEBUT DE PRESTATION : 01/12/2025 DATE DE FIN DE PRESTATION : 31/12/2025	<table><tr><th># Ligne FACT</th><th># ligne BC CODE ARTICLE, REFERENCE</th><th>NOM & DESIGNATION, Période Objet Classification Attributs Note</th><th>P.U. HT (EUR)</th><th>UNITÉ pour P.U.</th><th>Qté</th><th>Remise (-) Charge (+) (EUR)</th><th>TOTAL HT (EUR) - TVA TTC</th><th>TVA (taux, code) - VATEX code VATEX texte</th></tr><tr><td>1 GROUP</td><td></td><td>DISTRIBUTION DE L'EAU Vendeur: LE VENDEUR - SIREN_VENDEUR: 100000009 - N°TVA: FR88100000009 - Pays: FR - GLN: 587451236587 Cadre de Facturation (AVV): S1 N° Fact Vendeur (AFL): F202600022</td><td></td><td></td><td></td><td></td><td>90,95 - (TVA) 5,00 (TTC) 95,95</td><td>-</td></tr><tr><td>2 DETAIL #Parent: 1</td><td></td><td>ABONNEMENT - (PART DISTRIBUTEUR) Période de 01/01/2026 ou 31/01/2026 SIREN_VENDEUR: 100000009 N° Fact Vendeur (AFL): F202600022</td><td>(Net): 20,0000</td><td>PCE</td><td>1,00</td><td></td><td>20,00</td><td>5,50% (S) - (T) #F202600022#</td></tr><tr><td>3 DETAIL #Parent: 1</td><td></td><td>CONSOMMATION Période de 01/12/2025 ou 12/12/2025 SIREN_VENDEUR: 100000009 N° Fact Vendeur (AFL): F202600022</td><td>(Net): 0,6925</td><td>MTQ</td><td>25,00</td><td></td><td>17,31</td><td>5,50% (S) - (T) #F202600022#</td></tr><tr><td>4 DETAIL #Parent: 1</td><td></td><td>CONSOMMATION Période de 13/12/2025 ou 31/12/2025 SIREN_VENDEUR: 100000009 N° Fact Vendeur (AFL): F202600022</td><td>(Net): 0,7152</td><td>MTQ</td><td>75,00</td><td></td><td>53,64</td><td>5,50% (S) - (T) #F202600022#</td></tr><tr><td>5 GROUP</td><td></td><td>COLLECTE ET TRAITEMENT - EAUX USÉES Vendeur: VENDEUR XXXSIREN_VENDEUR: 111111118 - N°TVA: FR4411111118 - Pays: FR - SIRET: 11111111800019 Cadre de Facturation (AVV): S1 N° Fact Vendeur (AFL): 111111118_F202600022</td><td></td><td></td><td></td><td></td><td>121,95 - (TVA) 12,20 (TTC) 134,15</td><td>-</td></tr><tr><td>6 DETAIL #Parent: 5</td><td></td><td>CONSOMMATION Période de 01/12/2025 ou 12/12/2025 SIREN_VENDEUR: 111111118 N° Fact Vendeur (AFL): 111111118_F202600022</td><td>(Net): 1,1235</td><td>MTQ</td><td>25,00</td><td></td><td>28,09</td><td>10,00% (S) - (T) #111111118_F202600022#</td></tr><tr><td>7 DETAIL #Parent: 5</td><td></td><td>CONSOMMATION Période de 13/12/2025 ou 31/12/2025 SIREN_VENDEUR: 111111118 N° Fact Vendeur (AFL): 111111118_F202600022</td><td>(Net): 1,2514</td><td>MTQ</td><td>75,00</td><td></td><td>93,86</td><td>10,00% (S) - (T) #111111118_F202600022#</td></tr></table>	# Ligne FACT	# ligne BC CODE ARTICLE, REFERENCE	NOM & DESIGNATION, Période Objet Classification Attributs Note	P.U. HT (EUR)	UNITÉ pour P.U.	Qté	Remise (-) Charge (+) (EUR)	TOTAL HT (EUR) - TVA TTC	TVA (taux, code) - VATEX code VATEX texte	1 GROUP		DISTRIBUTION DE L'EAU Vendeur: LE VENDEUR - SIREN_VENDEUR: 100000009 - N°TVA: FR88100000009 - Pays: FR - GLN: 587451236587 Cadre de Facturation (AVV): S1 N° Fact Vendeur (AFL): F202600022					90,95 - (TVA) 5,00 (TTC) 95,95	-	2 DETAIL #Parent: 1		ABONNEMENT - (PART DISTRIBUTEUR) Période de 01/01/2026 ou 31/01/2026 SIREN_VENDEUR: 100000009 N° Fact Vendeur (AFL): F202600022	(Net): 20,0000	PCE	1,00		20,00	5,50% (S) - (T) #F202600022#	3 DETAIL #Parent: 1		CONSOMMATION Période de 01/12/2025 ou 12/12/2025 SIREN_VENDEUR: 100000009 N° Fact Vendeur (AFL): F202600022	(Net): 0,6925	MTQ	25,00		17,31	5,50% (S) - (T) #F202600022#	4 DETAIL #Parent: 1		CONSOMMATION Période de 13/12/2025 ou 31/12/2025 SIREN_VENDEUR: 100000009 N° Fact Vendeur (AFL): F202600022	(Net): 0,7152	MTQ	75,00		53,64	5,50% (S) - (T) #F202600022#	5 GROUP		COLLECTE ET TRAITEMENT - EAUX USÉES Vendeur: VENDEUR XXXSIREN_VENDEUR: 111111118 - N°TVA: FR4411111118 - Pays: FR - SIRET: 11111111800019 Cadre de Facturation (AVV): S1 N° Fact Vendeur (AFL): 111111118_F202600022					121,95 - (TVA) 12,20 (TTC) 134,15	-	6 DETAIL #Parent: 5		CONSOMMATION Période de 01/12/2025 ou 12/12/2025 SIREN_VENDEUR: 111111118 N° Fact Vendeur (AFL): 111111118_F202600022	(Net): 1,1235	MTQ	25,00		28,09	10,00% (S) - (T) #111111118_F202600022#	7 DETAIL #Parent: 5		CONSOMMATION Période de 13/12/2025 ou 31/12/2025 SIREN_VENDEUR: 111111118 N° Fact Vendeur (AFL): 111111118_F202600022	(Net): 1,2514	MTQ	75,00		93,86	10,00% (S) - (T) #111111118_F202600022#
# Ligne FACT	# ligne BC CODE ARTICLE, REFERENCE	NOM & DESIGNATION, Période Objet Classification Attributs Note	P.U. HT (EUR)	UNITÉ pour P.U.	Qté	Remise (-) Charge (+) (EUR)	TOTAL HT (EUR) - TVA TTC	TVA (taux, code) - VATEX code VATEX texte																																																																	
1 GROUP		DISTRIBUTION DE L'EAU Vendeur: LE VENDEUR - SIREN_VENDEUR: 100000009 - N°TVA: FR88100000009 - Pays: FR - GLN: 587451236587 Cadre de Facturation (AVV): S1 N° Fact Vendeur (AFL): F202600022					90,95 - (TVA) 5,00 (TTC) 95,95	-																																																																	
2 DETAIL #Parent: 1		ABONNEMENT - (PART DISTRIBUTEUR) Période de 01/01/2026 ou 31/01/2026 SIREN_VENDEUR: 100000009 N° Fact Vendeur (AFL): F202600022	(Net): 20,0000	PCE	1,00		20,00	5,50% (S) - (T) #F202600022#																																																																	
3 DETAIL #Parent: 1		CONSOMMATION Période de 01/12/2025 ou 12/12/2025 SIREN_VENDEUR: 100000009 N° Fact Vendeur (AFL): F202600022	(Net): 0,6925	MTQ	25,00		17,31	5,50% (S) - (T) #F202600022#																																																																	
4 DETAIL #Parent: 1		CONSOMMATION Période de 13/12/2025 ou 31/12/2025 SIREN_VENDEUR: 100000009 N° Fact Vendeur (AFL): F202600022	(Net): 0,7152	MTQ	75,00		53,64	5,50% (S) - (T) #F202600022#																																																																	
5 GROUP		COLLECTE ET TRAITEMENT - EAUX USÉES Vendeur: VENDEUR XXXSIREN_VENDEUR: 111111118 - N°TVA: FR4411111118 - Pays: FR - SIRET: 11111111800019 Cadre de Facturation (AVV): S1 N° Fact Vendeur (AFL): 111111118_F202600022					121,95 - (TVA) 12,20 (TTC) 134,15	-																																																																	
6 DETAIL #Parent: 5		CONSOMMATION Période de 01/12/2025 ou 12/12/2025 SIREN_VENDEUR: 111111118 N° Fact Vendeur (AFL): 111111118_F202600022	(Net): 1,1235	MTQ	25,00		28,09	10,00% (S) - (T) #111111118_F202600022#																																																																	
7 DETAIL #Parent: 5		CONSOMMATION Période de 13/12/2025 ou 31/12/2025 SIREN_VENDEUR: 111111118 N° Fact Vendeur (AFL): 111111118_F202600022	(Net): 1,2514	MTQ	75,00		93,86	10,00% (S) - (T) #111111118_F202600022#																																																																	
Détail TVA (motif, obligatoire si exonération, code S, E, AE, K, G, O)	Code	Taux	Base TVA	Montant TVA																																																																					
#F202600022#	S	5,50%	90,95	5,00																																																																					
#111111118_F202600022#	S	10,00%	121,95	12,20																																																																					
TVA acquittée sur les encaissements Tout retard de paiement engendre une pénalité exigible à compter de la date d'échéance, calculée sur la base de trois fois le taux d'intérêt légal. Indemnité forfaitaire pour frais de recouvrement en cas de retard de paiement : 40 €. Les règlements reçus avant la date d'échéance ne donneront pas lieu à escompte. CONDITIONS DE PAIEMENT : PAIEMENT 30 JOURS NET																																																																									
TOTAL HT		TOTAL TVA	TOTAL TTC																																																																						
212,90		17,20	230,10																																																																						
Montant déjà payé : (ou à payer par un tiers) 0,00																																																																									
Date d'échéance : 04/02/2025	NET A PAYER 230,10 EUR																																																																								
Bénéficiaire NOM : LE VENDEUR	MOYEN DE PAIEMENT : VIREMENT COMPTE : MON COMPTE BANCAIRE IBAN : FR20 1254 2547 2569 8542 5874 698 - BIC : BIC_MONCOMPTE REFERENCE AVIS DE PAIEMENT : F202600022_200000008																																																																								

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

4.4.12.2 Unit invoice number

In order to guarantee its uniqueness, it should be prefixed or suffixed with an element that guarantees the uniqueness of the number within the various unit invoices and for each Seller. One practice is to prefix it with a Seller identifier (e.g., their legal identifier), supplemented where applicable with an identifier for the main invoicing Seller, thus creating a unique invoicing series per Seller (which will therefore have gaps in the numbering, as not every Seller will be present in every multi-seller invoice generated by the invoicing party (transparent intermediary)).

The best practice is to generate invoice numbers by sub-seller in chronological order and by unit invoice, prefixed by the legal identifier of the Seller and that of the Invoicer Party:

- 123456782_321654879_F20250025 for Seller X in the example above,
- 123456782_254136987_F20250012 for Seller 00 in the example above, who would have been present in fewer multi-seller invoices than SELLER X (12 instead of 25).

4.4.12.3 Charges and Allowances

In general, it is preferable to avoid document-level allowances or charges in a multi-seller invoice.

Document-level Charges and Allowances are assigned only to the main invoice, i.e., to the main Seller identified in block BG-4 of the Multi-seller invoice. In order for the VAT breakdown to be correct, it is therefore necessary to enter the reasons for VAT exemption for document level allowances and charges, such as the reasons for VAT exemption at line level (and in particular, the reason in text beginning with the sub-invoice (unit) number between #).

If necessary for unit invoices, use the lines to add charges. Similarly, global allowances can be processed on lines, with a unit price of zero, a quantity equal to 1, and the use of the line allowance.

4.4.12.4 Management rules

The rules for managing multi-seller invoices are described in section 4.5.4.

4.4.12.5 Creation of flow 1 or 10.1 based on individual invoices

Processing a multi-seller invoice requires the unit invoices to be recomposed, serving as accounting documents for each vendor and as a basis for creating the required flow 1 or 10.1.

To do this, unit invoices are created by extraction and mapping as described in the multi-seller invoice mapping rules (section 4.5.5).

This involves compiling unit invoices that do not have the same invoice number as the multi-seller invoice:

- By keeping only the lines corresponding to each unit invoice (using the BT-128 value with BT-128-1 = AFL), for DETAIL lines only.
- By deleting charges and allowances at the Document level (if they exist in the invoice).
- By keeping only the VAT breakdown lines (BG-23) for which the exemption reason in text (BT-120) begins with the unit invoice number (BT-128, with the qualifier (BT-128-1) equal to AFL from the GROUP line) between #
- For the self-billed invoice:
 - In its "GROUP" type line (with no Parent line), it specifies:
 - The Seller (using the self-billed invoice Seller data (BG-4))
 - The invoice number (BT-1) in field BT-128 with schemeID "AFL"
 - The invoicing framework in field BT-128 with schemeID "AVV"

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

- And, on each attached "DETAIL" type line, it specifies:
- The individual invoice number (encoded using the line-level invoiced object identifier (BT-128), with the qualifier (BT-128-1) set to "AFL").
- The Seller's legal identifier (EXT-FR-FE-167).
- To enable a VAT breakdown specific to the self-billed invoice, the exemption reason in the line text (EXT-FR-FE-178) MUST begin with the invoice number enclosed in # symbols, followed by the exemption text if applicable.
- For the cross-sale invoice:
- In its "GROUP" type line (with no Parent line), it specifies:
- The Seller (using the BUYER's data (BG-7))
- An invoice number different from the self-billed invoice number (BT-1), in field BT-128 with schemeID "AFL"
- The invoicing framework in field BT-128 with schemeID "AVV"
- And, on each attached "DETAIL" type line, it specifies:
- The cross-sale invoice number (encoded using the line-level invoiced object identifier (BT-128), with the qualifier (BT-128-1) set to "AFL").
- The legal identifier ...of the online seller (EXT-FR-FE-167), which therefore serves as the BUYER's legal identifier.
- To enable a VAT breakdown specific to self-billing, the line-level exemption reason text (EXT-FR-FE-178) MUST begin with the cross-reference invoice number enclosed in # signs, followed by the exemption text, if applicable.
- By inverting the unit prices (which led to a relaxation of the rule requiring positive unit prices for this scenario) so that the line amounts are negative.
- Using the data from the "GROUP" line to:
 - ✓ Replace the SELLER information with that of the line level seller (in the "GROUP" line)
 - ✓ Replace the invoice number (BT-1) with the unit invoice number (BT-128, with the qualifier (BT-128-1) equal to AFL)
 - ✓ Replace the invoicing framework (BT-23) with the invoice line "billing framework" ("Cadre de Facturation" BT-128, with the qualifier (BT-128-1) equal to AVV).
 - ✓ Replace the VAT liability code (BT-8) with the line level Tax Point Date code (EXT-FR-FE-180).
 - ✓ Replace the sum of in line amounts (BT-106) and the total amount without VAT (BT-109) with the total amount without VAT for the "GROUP" line (BT-131).
 - ✓ Replace the total VAT amounts BT-110 and BT-111 with those entered in EXT-FR-FE-181 and EXT-FR-FE-182 (if applicable).
 - ✓ Replace the total amount with VAT (BT-112) with the amount entered in EXT-FR-FE-185, if it exists, otherwise calculate it as the amount without VAT (BT-109) plus the amount of VAT in the invoice currency (BT-110).
 - ✓ Enter the paid amount (BT-113) as shown in EXT-FR-FE-185, as the invoice shall be paid to the transparent intermediary, the "invoicer" party and the payee party.
 - ✓ Enter the Net Amount Payable (BT-115) as equal to BT-112 – BT-113, i.e. equal to 0.
- Potentially, if the Payee is not present in the multi-sale invoice, they can be added to the unit invoice with the SELLER data from the multi-seller invoice (BG-4).

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

For the main Seller's unit invoice, the same process applies, except that:

- The Charges and Allowance lines at the Document level are retained (and are therefore only attached to the main Seller)
- The total amount without VAT (BT-109) shall be equal to $BT-106 - BT-107 + BT-108$.
- If the multi-seller invoice does not contain any document-level allowances and charges, the conversion to a single invoice is the same as for all single invoices.

Once the single invoices have been created, the standard checks can be carried out and flows 1 or 10.1 created on this basis. The single invoices are given the status "Submitted" but are not sent to the BUYER. Only the multi-seller invoice is sent.

If one of the unit invoices is rejected, all unit invoices shall be rejected and the multi-seller invoice shall be generated again.

Unit invoices can be sent to each relevant Seller for accounting purposes. There may also be solutions in place that organize these transfer of accounting information ("reddition de compte").

4.4.13 Bidirectional self-billing invoices (self-billing)

In certain sectors, the buyer-seller relationship leads to linked cross-sales involving a self-billing practice, supplemented by the sale of goods or services from the buyer to the seller—often related to the self-billed purchase.

Strict compliance with the EN16931 standard requires the creation of two separate invoices, with payment handled via netting (where the self-billed purchase invoice is offset by the cross-sale invoice amount to show the overall net amount payable).

However, a common practice involves consolidating these two invoices into a single document containing negative line items corresponding to the cross-sale from the buyer to the seller.

This practice should generally be avoided; it should only be implemented within the scope of the reform if it is already in use and accepted by the tax authorities.

Nevertheless, to allow this practice to continue where it is already established and tolerated by the tax authorities, a bidirectional self-billing invoice model is proposed within the EXTENDED-CTC-FR profile. This model utilizes sub-line management and relies on the same practices as those used for multi-seller invoices. Implementing this practice requires specific processing by the certified issuance platform (on the buyer's side) as part of its optional services, as well as specific accounting treatment by each party, thereby necessitating a bilateral agreement.

By design, a bidirectional invoice issued by the buyer (or even the seller) results in one of the two invoices being a self-billed invoice. However, the specific use case identified applies only to situations involving primary self-billing by the buyer, supplemented by a cross-sale invoice from the buyer to the seller.

4.4.13.1 Procedures for creating a bi-directional self-billed invoice

At this stage, this option is therefore reserved for the practice of self-billing—which has notably been excluded from the Multi-Vendor invoice—thereby allowing for a clear distinction based on the applied invoice type code.

To identify this practice, an additional invoicing category has been added: Category 9, with the values B9, S9, and M9. As with multi-vendor invoices, each of the two invoices (the main self-billed invoice and the cross-sale invoice from the Buyer to the Seller) is structured using line groups:

- For the self-billed invoice:
 - ✓ In its "GROUP" type line (with no Parent line), it specifies:
 - The Seller (using the self-billed invoice Seller data (BG-4))

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

- The invoice number (BT-1) in field BT-128 with schemeID "AFL"
 - The invoicing framework in field BT-128 with schemeID "AVV"
- ✓ And, on each attached "DETAIL" type line, it specifies:
- The individual invoice number (encoded using the line-level invoiced object identifier (BT-128), with the qualifier (BT-128-1) set to "AFL").
 - The Seller's legal identifier (EXT-FR-FE-167).
 - To enable a VAT breakdown specific to the self-billed invoice, the exemption reason in the line text (EXT-FR-FE-178) MUST begin with the invoice number enclosed in # symbols, followed by the exemption text if applicable.
- For the cross-sale invoice:
- ✓ In its "GROUP" type line (with no Parent line), it specifies:
- The Seller (using the BUYER's data (BG-7))
 - An invoice number different from the self-billed invoice number (BT-1), in field BT-128 with schemeID "AFL"
 - The invoicing framework in field BT-128 with schemeID "AVV"
- ✓ And, on each attached "DETAIL" type line, it specifies:
- The cross-sale invoice number (encoded using the line-level invoiced object identifier (BT-128), with the qualifier (BT-128-1) set to "AFL").
 - The legal identifier ...of the online seller (EXT-FR-FE-167), which therefore serves as the BUYER's legal identifier.
 - To enable a VAT breakdown specific to self-billing, the line-level exemption reason text (EXT-FR-FE-178) MUST begin with the cross-reference invoice number enclosed in # signs, followed by the exemption text, if applicable.
 - By inverting the unit prices (which led to a relaxation of the rule requiring positive unit prices for this scenario) so that the line amounts are negative.

Self billed Invoice

Cadre de Facturation

389

S9

Denom

Siren

N°TVA

Pays

Seller

AGRI1

100000009

FR8810000009

FR

Buyer

COOP1

200000008

FR3720000008

FR

N°

AUTOF202600035

02/06/2026

#line	#line parent	subType	Item	Unit Price BT-146	Quantity BT-129	Total BT-131	Total VAT EXT-FR-FE-181	VAT code BT-151	VAT rate BT-152	VATEX text EXT-FR-FE-178 / 179	Line SELLER				Cadre de facturation	Unit Invoice ID
											Name EXT-FR-FE-164	legal ID EXT-FR-FE-167	VAT ID EXT-FR-FE-169	Country code EXT-FR-FE-177	BT-128 + AVV	BT-128 + AFL
11	10	DETAIL	Lait	489,0570	43,8100	21 425,59		S	5,50%	#AUTOF202600035#	AGRI1	100000009	FR8810000009	FR		AUTOF202600035
21	20	DETAIL	CNIEL	-0,1070	43,8100	-4,69		E	0,00%	#AGRI1_F202600035#Exo1	COOP1	200000008	FR3720000008	FR		AGRI1_F202600035
22	20	DETAIL	CNIEL Part assuettie	-1,1130	43,8100	-48,76		S	20,00%	#AGRI1_F202600035#	COOP1	200000008	FR3720000008	FR		AGRI1_F202600035
23	20	DETAIL	Cotisation Labo	-0,3900	43,8100	-17,09		S	20,00%	#AGRI1_F202600035#	COOP1	200000008	FR3720000008	FR		AGRI1_F202600035
24	20	DETAIL	Cotisation Cliquest	-0,0150	43,8100	-0,66		E	0,00%	#AGRI1_F202600035#Exo1	COOP1	200000008	FR3720000008	FR		AGRI1_F202600035
31	20	DETAIL	Mise à disposition Tank	-3,0490	43,8100	-133,58		S	20,00%	#AGRI1_F202600035#	COOP1	200000008	FR3720000008	FR		AGRI1_F202600035
10		GROUP	Total des Ventes			21 425,59	1 178,41				AGRI1	100000009	FR8810000009	FR	S1	AUTOF202600035
20		GROUP	Total des Déductions (achat)			-204,78	-39,89				COOP1	200000008	FR3720000008	FR	S1	AGRI1_F202600035

VAT Breakdown

Base BT-116	VAT code BT-118	VAT rate BT-119	VATEX text BT-120/121	VAT BT-117
21 425,59	S	5,50%	#AUTOF202600035#	1 178,41
-199,43	S	20,00%	#AGRI1_F202600035#	-39,89
-5,35	E	0,00%	#AGRI1_F202600035#Exo1	0,00

Tota without VAT (BT-109)

21 220,81

Total VAT (BT-110)

1 138,52

Total with VAT (BT-112)

22 359,33

Paid amount (BT-113)

0,00

Due for Payment (BT-115)

22 359,33

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

4.4.13.2 Invoice number management

Self-billing practices require specific invoice numbering linked to each vendor (or, in very exceptional cases, to a group of vendors). Consequently, a dedicated cross-invoice number series must be managed in parallel, or created using a prefix that establishes the link between the cross-invoice and the self-billed invoice. The example above shows two invoice number series (202600015 for the cross-invoice and AGRI1_202600021).

It is also possible, for example, to align the invoice numbers as follows:

- Self-billing invoice number: AGRI1_202600021
- Cross-invoice number: FC_AGRI1_202600021

This ensures the uniqueness and chronological order of each invoice number but may result in gaps in the invoice numbering sequence, which must be documented (for the reliable audit trail).

4.4.13.3 Business rules

The business rules for bidirectional self-billing invoices are the same as those for Multi-Vendor invoices, with the exception of rules BR-FR-MV-02, BR-FR-MV-13, and BR-FR-MV-14, which correspond to BR-FR-BD-02, BR-FR-BD-13, and BR-FR-BD-14.

These are described in section 4.5.4.

4.4.13.4 Creation of flow 1 or 10.1

As with Multi-Vendor invoices, the bidirectional self-billing invoice requires the creation of two flow 1 (or 10.1) messages, corresponding respectively to the main self-billing invoice and the cross-sale invoice.

The rules are similar to those for Multi-Vendor invoices, except that the cross-sale invoice must also reverse the Buyer and Seller roles within the flow and invert the signs of Unit Prices and amounts (line items, VAT breakdowns, and totals), as described in mapping rule BR-FR-BDMAP-01.

This therefore constitutes specific processing for the Accredited Issuance Platform, which MAY offer this as part of its services. optional.

4.5 Additional specific management rules under the French reform

The requirements of the Electronic Invoicing reform in France have led to the definition of additional management rules to those of Standard EN16931, derived from the management rules on e-reporting elements to the tax authorities (Flow 1, Flow 10.1).

There are several types of management rules:

- Management rules that constitute additional checks to be carried out on the content of invoices, sometimes using external reference systems (e.g., the existence of the BUYER or SELLER SIREN number in the PPF directory). These are referred to as business checks.
- Mapping rules between invoice data and the files expected by the tax authorities (flow 1 and flow 10.1).
- "CHORUS PRO" rules applicable to B2G invoices intended for the public sector.
- Additional specific rules for multi-seller invoices:
 - ✓ Additional management rules.
 - ✓ Specific mapping rules for creating unit invoices and unit flows 1 or 10.1.

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

These rules are described in the Excel annex and are assigned to each line of an invoice description whenever it is affected by one of these rules.

4.5.1 Additional control rules for compliance with regulation in France

The table below shows the control management rules:

BR CODE	Title	Description	Applies to
BR-FR-01	Invoice ID 35 characters	The invoice ID SHALL be limited to 35 characters	BT-1, BT-25, EXT-FR-FE-136
BR-FR-02	invoice ID allowed characters	The invoice ID (BT-1) consists of alphanumeric characters (A-Z, a-z, 0-9). The following special characters are allowed: - hyphen ("-") - plus sign ("+") - underscore ("_") - slash ("/")	BT-1, BT-25, EXT-FR-FE-136
BR-FR-03	Date between 2000 and 2099	The year of a date SHALL BE between 2000 and 2099	Any DATE type
BR-FR-04	Document type codes	The document type codes for an invoice are as follows: Simple invoices: - Commercial invoice (380) - Self-billed invoice (389) - Factored invoice (393) - Self-billed factored invoice (501) Pre-payment invoices: - Pre-payment invoice (386) - Self-billed Pre-payment invoice (500) Corrected invoices: - Corrected invoice (384) - Self-billed corrected invoice (471) - Factored corrected invoice (472) - Self-invoiced corrected invoice invoiced by a third party (473) Credit notes: - Self-billed credit note (261) - Credit note for Global Allowance (262) - Credit note (381) - Factored credit note (396) - Factored self-billed credit note (502) - Pre-payment Credit note (503) The Other types of invoices defined in the standard (UNTDID 1001) shall not be used.	BT-3, EXT-EN-FE-02, EXT-EN-FE-137
BR-FR-05	Note	All invoices SHALL include at least 3 notes (BG-1) with the following codes: - BT-21 = PMT, for the mention of a fixed penalty of EUR 40 for collection costs (in BT-22) - BT-21 = PMD, mention of penalties corresponding to the payment terms specific to each company (in BT-22). - BT21 = AAB, mention of discount or no discount (in BT-22)	BT-22, BT-21
BR-FR-06	Note	Among the notes (BG-3), the subject codes (BT-21) PMD, PMT, AAB, and TXD SHALL only appear ONCE EACH.	BT-22, BT-21
BR-FR-07	Note	To indicate the information below in notes (BT-22), the corresponding subject codes (BT-21) shall be as follows: - ACC: Factoring subrogation clause - AAI: General information: general information at the bottom of paper invoices	BT-22, BT-21

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

BR CODE	Title	Description	Applies to
		- ADN: indicates whether the invoice falls under B2G in France (additional CPRO rules) - SUR: Supplier comments - ABL: Legal information: e.g., trade register number, RCS - CUS: Customs information - BLU: "Eco-participation (L. 541-10 of the Environmental Code)" or "WEEE eco-contribution" - BAR: type of processing expected (e-invoicing, e-reporting, non-reform, etc.)	
BR-FR-08	Invoicing framework	The billing Framework (BT-23) is mandatory, and the authorized values for the Framework (Invoicing Method) are: B1: Submission of a goods invoice S1: Submission of an invoice for services M1: Submission of a dual invoice (delivery of goods and services that are not ancillary to each other) B2: Submission of an invoice for goods that has already been paid S2: Submission of an invoice for services already paid M2: Submission of a duplicate invoice that has already been paid S3: Submission of a subcontractor payment request with direct payment (B2G only, restriction not verifiable) B4: Submission of a final invoice (after deposit) for goods S4: Submission of a final invoice (after deposit) for services M4: Submission of a final (after deposit) duplicate invoice S5: Submission by a subcontractor of an invoice for services rendered S6: Submission by a co-contractor of an invoice for services B7: Submission of an invoice for goods that has been e-reported (VAT already collected) S7: Submission of an invoice for services that have been e-reported (VAT already collected) B8: Submission of a multi-seller goods invoice S8: Submission of a multi-seller invoice for services M8: Submission of a duplicate multi-seller invoice containing individual invoices that are not all Sx or Bx. B9: Submission of a 2 ways goods invoice S9: Submission of a 2 ways invoice for services M9: Submission of a dual 2 ways invoice containing individual invoices that are not all Sx or Bx.	BT-23
BR-FR-09	SIRET SIREN consistency	In a Party, if the SIRET is provided (Private ID, 0009), the first 9 digits of the SIRET shall match the SIREN provided in the legal ID (schemeID 0002) and the SIRET shall be 14 digits long.	BT-29, BT-46, BT-60, EXT-FR-FE-06, EXT-FR-FE-46, EXT-FR-FE-69, EXT-FR-FE-92, EXT-FR-FE-115, BT-71, EXT-FR-FE-146
BR-FR-10	SIREN management	The Seller's SIREN number is mandatory and shall be present and active in the PPF directory.	BT-30
BR-FR-11	SIREN management	For invoices falling within the scope of "e-invoicing", the Buyer's SIREN number is mandatory and shall be present and active in the PPF directory. Rule to be applied if the invoice is subject to B2B processing or if it contains a note (BG-1) with a subject code (BT-21) = BAR and content (BT-22) = B2B: The Buyer's legal identifier (BT-47) SHALL be present.	BT-47

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

BR CODE	Title	Description	Applies to
BR-FR-12	Buyer's electronic address	When an electronic invoice shall be sent and is awaiting life cycle statuses in return, the Buyer's electronic address (BT-49) is MANDATORY. This is the electronic address to which the invoice is sent (excluding self-invoices), as well as the life cycle statuses intended for the BUYER. For information (managed by other rules): For invoices outside the scope of self-billing that fall within the scope of e-invoicing, this electronic address SHALL be in the format "SIREN" or "SIREN_XXX", where SIREN is the Buyer's SIREN number entered in BT-47, with a schemeId (BT-49-1) = 0225. For invoices outside the scope of "e-invoicing" or within the scope of "e-invoicing" in self-billing issued by the Buyer, the Buyer's electronic address SHALL be in one of the schemeIDs in the EAS code list (including an email, with schemeID (BT-49-1) = EM). For invoices made available on a portal, an email address (schemeID (BT-49-1) = EM) of the type "noreply@seller's domain" may be used to indicate that the Buyer does not have an electronic address.	BT-49, BT-49-1
BR-FR-13	Seller's electronic address	When an electronic invoice shall be sent and is awaiting life cycle statuses in return, the Seller's electronic address (BT-34) is MANDATORY. This is the electronic address to which the self-billed invoice is sent, along with the life cycle statuses intended for the Seller. <u>For information (managed by other rules):</u> For self-billed invoices falling within the scope of "e-invoicing", this electronic address SHALL be in the form "SIREN" or "SIREN_XXX", where SIREN is the Seller's SIREN number entered in BT-30, with a schemeId (BT-34-1) = 0225. For invoices outside the scope of "e-invoicing" or within the scope of "e-invoicing" but not self-billed, the Seller's electronic address SHALL be in one of the schemeIDs in the EAS code list (including an electronic, with schemeID (BT-34-1) = EM). For invoices made available on a portal, an email address of the type "noreply@seller's domain" may be used to indicate that the Seller does not have an electronic address.	BT-34, BT-34-1
BR-FR-14	Delivery Address	Certain data related to the delivery address BG-15 is mandatory if the address is different from the invoicing address (Buyer - Block BG-8) and only from 09/01/2027 (September 1st 2027). The mandatory data is as follows: • Delivery address - Line 1 (BT-75) • Delivery address locality (BT-77) • Delivery address postal code (BT-78) • Country code for delivery address (BT-80) This information may also be provided on the line (if different from the header: Block EXT-FR-FE-BG-10). This data is not to be transmitted for services. Business management rule but cannot be controlled from an application perspective	
BR-FR-15	VAT category code	Only the following VAT category codes will be accepted: S = Standard VAT rate E = VAT exempt AE = Reverse charge vAT K = Exempt due to intra-Community supply G = VAT exemption for exports outside the EU O = Outside the scope of VAT Z = VAT rate equal to 0 (see G1.47) The following VAT category codes are not relevant in France: L = Canary Islands M = Ceuta and Melilla	BT-95, BT-102, BT-118, BT-151

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

BR CODE	Title	Description	Applies to
BR-FR-16	Authorized VAT rate	The applicable VAT rate is in accordance with the following list: Rate 0, 0.0, 0.00 10, 10.0, 10.00 13, 13.0, 13.00 20, 20.0, 20.00 8.5, 8.50 19.6, 19.60 2.1, 2.10 5.5, 5.50 7, 7.0, 7.00 20.6, 20.60 1.05 0.9, 0.90 1.75 9.2, 9.20 9.6, 9.60 The rate is expressed as a percentage and not as a coefficient (e.g., 20). The symbol "%" should not be included. The separator (".") is not counted in the 5 characters.	BT-96, BT-103, BT-119, BT-152
BR-FR-17	Supporting document	The following codes can be used to describe attachments: RIB: for a bank account number (containing the IBAN/account number + account holder's name) LISIBLE (means READABLE): for THE FULL READABLE REPRESENTATION OF THE INVOICE. BORDEREAU_SUIVI (means STYLE_SHEET): for the style sheet used to create a readable representation PJA: for an additional attachment BORDEREAU_SUIVI (means TRACKING_SLIP): for a tracking slip DOCUMENT_ANNEXE (means ATTACHED_DOCUMENT): for an attached document BON_LIVRAISON (means DELIVERY_NOTE): a delivery note BON_COMMANDE (means Purchase order): for a purchase order BORDEREAU_SUIVI_VALIDATION (means TRACKING_SLIP_VALIDATION): for a tracking and validation slip ETAT_ACOMPTE (means PREPAYMENT_STATUS): for a prepayment status FACTURE_PAIEMENT_DIRECT (means DIRECT_PAYMENT_INVOICE): for a subcontractor invoice to be paid directly RECAPITULATIF_COTRAITANCE: to list all subcontractor invoices to be processed together.	BT-123
BR-FR-18	Supporting Document	There cannot be two Additional Documents (BG-24) for which the description BT-123 is equal to READABLE.	BT-123
BR-FR-19	Limit : 100 MB	All invoices under 100 MB shall be able to be processed by the «Solution Compatible (SC)» / «Plateformes Agréées» (PA) (including attachments). This is a business rule that allows an UNACCEPTABLE ("IRRECEVABLE") status to be assigned to an invoice file larger than 100 MB.	An invoice file to be processed
BR-FR-20	Qualification of the expected processing type	A Note can be used to indicate the expected processing for the invoice. The subject code SHALL be BAR and the expected values, to be meaningful, SHALL be in the list below, with their meanings: . B2B: means "e-invoicing" . B2BINT: means "relates to B2Bint sales e-reporting" . B2C: means "relates to B2C sales e-reporting" . OUTOFSCOPE: means "outside the scope of the reform" . ARCHIVEONLY: means that this is an internal CREDIT created to cancel a REJECTED or REFUSED invoice, and SHALL NOT be processed by e-invoicing (no flow 1, no transmission to the recipient)	BG-1, BT-21, BT-22

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

BR CODE	Title	Description	Applies to
BR-FR-21	Buyer's electronic address	Rule to be executed if the invoice is subject to B2B processing or if it contains a note (BG-1) with a subject code (BT-21) = BAR and content (BT-22) = B2B: If the invoice is not self-billed (BT-3 not in list ('389', '501', '500', '471', '473', '261', '502')) THEN the BUYER's electronic invoicing address (BT-49) shall begin with the BUYER's SIREN number (BT-47) AND the address schemeID (BT-49-1) SHALL be equal to 0225	BT-49, BT-49-1
BR-FR-22	Seller's electronic address	Rule to be executed if the invoice is subject to B2B processing or if it contains a note (BG-1) with a subject code (BT-21) = BAR and content (BT-22) = B2B If the invoice is self-billed (BT-3 in list ('389', '501', '500', '471', '473', '261', '502')) THEN the SELLER's electronic invoicing address (BT-34) shall begin with the SELLER's SIREN number (BT-30) AND the address schemeID (BT-30-1) SHALL be equal to 0225	BT-34, BT-34-1
BR-FR-23	Electronic address in 0225	Any electronic address with schemeID = 0225 is composed of alphanumeric characters (A-Z, a-z, 0-9). The following special characters are allowed: - hyphen ("-") - underscore ("_") - period (".")	BT-34 / BT-34-1, BT-49 / BT-49-1 EXT-FR-FE-12 / EXT-FR-FE-13, EXT-FR-FE-29 / EXT-FR-FE-30, EXT-FR-FE-52 / EXT-FR-FE-53, EXT-FR-FE-75 / EXT-FR-FE-76, EXT-FR-FE-98 / EXT-FR-FE-99, EXT-FR-FE-121 / EXT-FR-FE-122
BR-FR-24	Routing code	Any private ID with a schemeID = 0224 is made up of alphanumeric characters (A-Z, a-z, 0-9). The following special characters are allowed: - hyphen ("-") - underscore ("_") - period (".")	BT-29 / BT-29-1, BT-46 / BT-46-1
BR-FR-25	Electronic address	All electronic addresses shall not exceed 125 characters	BT-34, BT-49 EXT-FR-FE-12, EXT-FR-FE-29, EXT-FR-FE-52, EXT-FR-FE-75, EXT-FR-FE-98, EXT-FR-FE-121
BR-US-26	Routing code	Any private ID of a party with schemeID = 0224 shall not exceed 100 characters	BT-29 / BT-29-1, BT-46 / BT-46-1
BR-FR-27	Item attribute code and name	An Item Attribute group (BG-32) SHALL contain either an Item Attribute Name (BT-160) or an Item Attribute Code (EXT-FR-FE-159)	BG-32, BT-160, EXT-EN-FE-159
BR-EN-28	Attribute value and attribute value with unit of measure	An Item Attribute group (BG-32) SHALL contain either an attribute value (BT-161) or an attribute value with unit of measure (EXT-FR-FE-160) and its unit of measure (EXT-FR-FE-161).	BT-161, EXT-EN-FE-160, EXT-EN-FE-161
BR-FR-29	Billed object identifier	Among Invoiced Object Identifiers (BT-18), the identification schemes (BT-18-1) "AFL" and "AVV" SHALL only be present ONCE EACH	BT-18, BT-18-1
BR-EN-30	Line-level billed object identifier	Among Line Item Identifiers (BT-128), the identification schemes (BT-128-1) "AFL" and "AVV" SHALL appear only ONCE EACH.	BT-128, BT-128-1
BR-EN-31	Note with subject code BAR	In the event of multiple notes (BG-1) with a subject code (BT-21) = BAR, only one of the following values may be present in the content (BT-22): . B2B . B2BINT . B2C	BG-1, BT-21, BT-22

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

BR CODE	Title	Description	Applies to
		. B2CINT . OUTOFSCOPE . ARCHIVEONLY	
BR-FR-32	When present, the SIREN number consists of 9 digits	Any Party identifier with schemeID = '0002' or '0231' SHALL consist of 9 digits	BT-29d, BT-30, BT-47, BT-61 EXT-FR-FE-08, EXT-FR-FE-48, EXT-FR-FE-71, EXT-FR-FE-94, EXT-FR-FE-117, EXT-FR-FE-167
BR-FR-CO-01	No backdating into the future	The BT-2 invoice date SHALL BE on or before the date of application of the compliance check	BT-2
BR-FR-CO-02	Uniqueness of the invoice	The unique invoice identifier shall consist of the following elements: - Invoice number (BT-1) - Year of invoice production (derived from the invoice issue date (BT-2)) - Legal identifier of the Seller: SIREN number (BT-30) The uniqueness of the invoice is intended to prevent invoicing errors (double invoicing in particular). An invoice containing cumulative information similar to a previously sent invoice in relation to these three data points will be rejected by the platforms. The uniqueness check is systematically blocking. In the event of a invoicing mandate, the invoice number shall include a root specific to the agent to avoid duplicate invoices with those of the principal. The invoice number shall comply with the following BOFIP regulations: BOI-TVA-DECLA-30-20-20-10 of October 18, 2023 Section: A. Invoice numbering	BT-1, BT-2, BT-30
BR-FR-CO-03	Document type codes	If the document type code (BT-3) is equal to 262 (Global Credit Note), then: - The contract number (BT-12) SHALL be present - The invoicing period (BG-14) SHALL be present	BT-3, BT-12, BG-14
BR-FR-CO-04	Document code types	If the invoice code type (BT-3) is in the following list: Corrected invoices: - Corrected invoice (384) - Self-billed corrected invoice (471) (*) - Factored corrected invoice (472) (*) - Factored Self-billed corrected invoice (473) (*) Then ONE AND ONLY ONE reference to a previous invoice (BT-25) SHALL be included, along with its date (BT-26)	BT-3, BT-25, BT-26
BR-FR-CO-05	Document code types	If the document type code (BT-3) is in the following list: Credit notes: - Self-billed credit note (261) - Credit note (381) - Factored credit note (396) - Factored Self-billed credit note (502) (*) - Pre-payment Credit note (503) (*) Therefore, AT LEAST one reference to a previous invoice (BT-25) SHALL be present along with its date (BT-26) OR a reference to a previous in line invoice (EXT-FR-FE-136) SHALL be present IN EACH line (BG-25) where the "Invoice Line Subtype" (EXT-FR-FE-163 / BT-X-8) has the value "DETAIL" or is not specified, along with its date (EXT-FR-FE-138).	BT-3, BT-25, EXT-FR-FE-136, EXT-FR-FE-138

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

BR CODE	Title	Description	Applies to
BR-FR-CO-06	Date of payment of the deposit	If the invoice type code (BT-3) is: - Pre-Payment invoice (386) - Self-billed prepayment invoice (500) (*) - Pre-payment credit note (503) (*) and if the advance payment date is determined/known and is different from the issue date, then the advance payment date shall be entered in BT-9 Business management rule but cannot be controlled from an application perspective	BT-9
BR-FR-CO-07	Deposit payment date	The Due date (BT-9), if present, SHALL be later than or equal to the Invoice date (BT-2), EXCEPT IF the invoice is a pre-payment (BT-3): - Pre-payment invoice (386) - Self-billed Pre-payment invoice (500) (*) - Pre-payment credit note (503) (*) OR UNLESS the “Billing Framework” (BT-23, “Cadre de Facturation”) is equal to: - B2: Submission of an invoice for goods already paid - S2: Submission of an invoice for services already paid - M2: Submission of a duplicate invoice that has already been paid	BT-9, BT-3, BT-2, BT-23
BR-FR-CO-08	Invoicing framework Final invoice	If the “Billing Framework” (BT-23, “Cadre de Facturation”) is: - B4: Final invoices (after deposit) for goods - S4: Final invoices (after down payment) for services - M4: Final invoices (after deposit) duplicate THEN the invoice type cannot be: - Pre-payment invoice (386) - Self-billed Pre-payment invoice (500) - Pre-payment credit note (503)	BT-23, BT-3
BR-FR-CO-09	Invoicing framework Already paid	If the “Billing Framework” (BT-23, “Cadre de Facturation”) is: - B2: Submission of an invoice for goods already paid - S2: Submission of an invoice for services already paid - M2: Submission of a duplicate invoice that has already been paid THEN - The amount already paid (BT-113) is equal to the total amount of the invoice with VAT (BT-112) - The amount to be paid (BT-115) is equal to 0 - The due date (BT-9) SHALL indicate the date on which the invoice was paid	BT-23, BT-9, BT-112, BT-113, BT-115
BR-FR-CO-10	Private IDs of the parties	When there are multiple private identifiers for actors (e.g., BT-29), they shall be qualified by a schema identifier (BT-29-1). There cannot be two private identifiers with the same schema identifier.	BT-29, BT-46, BT-60, EXT-FR-FE-06, EXT-FR-FE-46, EXT-FR-FE-69, EXT-FR-FE-92, EXT-FR-FE-115, BT-71, EXT-FR-FE-146
BR-FR-CO-11	Private IDs of parties	Private party identifiers are used to provide specific identifiers, qualified by the schema identifier (ICD code list). Thus: - a SIRET (schema identifier = 0009) - a ROUTING CODE (schema identifier = 0224) - The SIREN of the Seller's sole taxpayer (schema identifier: 0231), only in BT-29	BT-29, BT-46, BT-60, EXT-FR-FE-06, EXT-FR-FE-46, EXT-FR-FE-69, EXT-FR-FE-92, EXT-FR-FE-115, BT-71, EXT-FR-FE-146
BR-FR-CO-12	VAT amount in EURO	If the Invoice currency (BT-5) is different from EUR, then - the accounting currency BT-6 SHALL be present and equal to EUR - The VAT amount in the accounting currency (and therefore in EURO) BT-111 SHALL be present, and BT-111-1 SHALL be equal to EUR	BT-5, BT-6, BT-110, BT-111
BR-FR-CO-13	Single Taxable Seller	If there is an occurrence of BT-29 with an identification pattern BT-29-1 = 0231, then the Seller is a Member of a Single Taxable Entity (AU), and the SIREN number of the Single Taxable Entity in BT-29 with the identification scheme (BT-29-1) = 0231 SHALL be present in the PPF Directory	BT-29, BT-29-1

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

BR CODE	Title	Description	Applies to
BR-FR-CO-14	Single Taxable Entity Seller	If there is an occurrence of BT-29 with an identification pattern BT-29-1 = 0231, then the Seller is a Single Taxable Unit (AU) Member, and a BG-1 block SHALL be present with Subject Code (BT-21) = "TXD" AND a note text (BT-22) = "MEMBRE_ASSUJETTI_UNIQUE".	BT-29, BT-29-1, BT-21, BT-22
BR-FR-CO-15	Single Taxable Person Seller	If there is an occurrence of BT-29 with an identification pattern BT-29-1 = 0231, then the Seller is a Member of a Single Taxable Person (AU) and the Seller's Tax Representative Block (BG-11) SHALL be present and contain the Single Taxable Person's information (and in particular their VAT number in BT-63)	BT-29, BT-29-1, BG-11, BT-63
BR-FR-CO-16	VAT exemption	Invoices exempt from VAT at source shall include a VAT details section with BT-118 = "E" AND an exemption reason in CODE BT-121 = "VATEX-FR-FRANCHISE". If the Seller does not have a VAT number, they shall repeat their SIREN number in BT-32	BT-118, BT-121, BT-120
BR-FR-CO-17	Delivery date	To be provided if it has been determined and is different from the date of issue of the invoice (Art. 242 nonies A 10°). The following may be entered on an invoice: - the delivery date or the date of completion of the service (BT-72) - or the delivery date per line, in the case of multiple deliveries (EXT-FR-FE-BG-11) - or a invoicing period in the case of periodic or summary invoices (Article 289 - I.3 of the CGI) (BG-26) Business management rule but cannot be controlled from an application perspective	BT-72, BG-14, EXT-FR-FE-BG-11
BR-FR-DEC-01	Amount 19.2	The amount in an invoice is expressed as a number with 19 digits and cannot have more than 2 decimal places. The separator between the whole number and the decimals is a period ("."). The "-" sign in front of the amount counts as a character. If the total number of digits in the number (including whole and decimal parts) exceeds 19 characters, the amount will be rejected. The separator "." is not counted in the 19 characters.	BT-92, BT-93, BT-99, BT-100, BT-106, BT-107, BT-108, BT-109, BT-110, BT-111, BT-112, BT-113, BT-114, BT-115, BT-116, BT-117, BT-131, BT-136, BT-137, BT-141, BT-142
BR-FR-DEC-02	Quantity 19.4	The quantity invoiced in an invoice is expressed as a number with 19 digits and cannot have more than 4 decimal places. The separator between the whole number and the decimals is a period ("."). The "-" sign in front of the amount counts as a character. If the total number of digits in the number (including whole numbers and decimals) exceeds 19 characters, the amount will be rejected. The separator "." is not counted in the 19 characters.	BT-129, BT-149
BR-FR-DEC-03	Unit Price 19.6	The amount in an invoice is expressed as a number with 19 digits and cannot have more than 6 decimal places. The separator between the whole number and the decimals is a period ("."). There is no sign (always positive), unless the Business process type is set to S9, M9, or B9. If the total number of digits in the number (including the whole number and decimal part) exceeds 19 characters, the amount will be rejected. The separator "." is not counted in the 19 characters.	BT-146, BT-147, BT-148
BR-FR-DEC-04	Percentage VAT rate 4.2	The VAT rate on an invoice is expressed as a 4-digit number and cannot have more than 2 decimal places. The separator between the whole number and the decimals is a period ("."). There is no sign (always positive). If the total number of digits in the number (including whole and decimal parts) exceeds 4 characters, the amount will be rejected. The separator "." is not counted in the 4 characters.	BT-96, BT-103, BT-119, BT-152

4.5.2 Mapping rules for creating flows 1 and 10.1

The table below details the mapping rules based on sales invoice data to be issued or issued to create flows 1 or 10.1.

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

BR CODE	Title	Description	Applies to
BR-FR-MAP-01	Invoice ID allowed characters	For the creation of flow 1 or 10.1, flow 6 for the PPF, the invoice ID is reduced to 20 characters if it contains more than 20, as follows: - Truncation to 19 characters on the right - Addition of a "T" on the left to indicate truncation Example: 987654321-123456782-F202500125 gives T23456782-F202500125	BT-1, BT-25, EXT-FR-FE-136
BR-FR-MAP-02	Document code type	If the invoice type code (BT-3) is equal to 262 (Credit for Global Allowance), then: For flow 1: - the invoice type code (BT-3 = 262) SHALL be mapped to 381 in flow 1 (BT-3) - the Contract reference (BT-12) of the invoice shall be mapped to the Reference to a previous invoice (BT-25) in Flow 1, and the Invoicing period start date (BT-73) SHALL be mapped to the Previous invoice date (BT-26). For flow 10.1: - the invoice type code (BT-3 = 262) SHALL be mapped to 381 in flow 10.1 (TT-21) - the Contract reference (BT-12) of the invoice SHALL be mapped to the Reference to a previous invoice (TT-30) and the Invoicing period start date (BT-73) SHALL be mapped to the Previous invoice date (TT-31)	BT-3, BT-12, BG-14
BR-FR-MAP-03	VAT on debits	It should be noted that the option of VAT on debits is general and takes precedence over all invoices issued. In the case of services and the option of VAT on debits, VAT is payable when the corresponding amount is debited from the "customer" account. In practice, the debit usually coincides with the invoicing. It should be noted that the option to pay tax on debits cannot have the effect of delaying the VAT TaxPoint Date.. The indication of the VAT Tax Point Date for debits is shown in BT-8 with the values 5 in CII and 3 in UBL. BT-8 is mandatory for service invoices when the taxable seller has opted for debits. In flow 10.1, the value of BT-8 is mapped to TT-24	BT-8
BR-FR-MAP-04	Note mapping	Only notes (BG-3) with subject codes (BT-21) equal to AAB, BLU, and TXD SHALL be transmitted in Flow 1 or Flow 10.1 (TT-26 = BT-21, TT-27 = BT-22). Notes with other subject codes may or may not be transmitted in Flow 10 or 10.1.	BT-22, BT-21, TT-26, TT-27
BR-FR-MAP-05	VAT amount in EURO in flow 10.1	If the Invoice Currency (BT-5) is EUR, then TT-52 is equal to BT-110, otherwise TT-52 is equal to BT-111	BT-5, BT-6, BT-110, BT-111, TT-52
BR-FR-MAP-06	Seller Single Taxable Entity	If there is an occurrence of the Note block (BG-1) with Subject Code (BT-21) = "TXD" AND a note text (BT-22) = "MEMBRE_ASSUJETTI_UNIQUE", then "MEMBRE_ASSUJETTI_UNIQUE" shall be transcoded to "Membre d'un assujetti unique" ("Single Taxable Entity Member") in BT-22 of Flow 1	BT-21, BT-22
BR-FR-MAP-07	Seller Single Taxable Entity	If there is an occurrence of the Note block (BG-1) with Subject Code (BT-21) = "TXD" AND a note text (BT-22) = "MEMBRE_ASSUJETTI_UNIQUE", then "MEMBRE_ASSUJETTI_UNIQUE" shall be transcoded to "Membre d'un assujetti unique" ("Single Taxable Entity Member") in in TT-27 of flow 10.1	BT-21, BT-22, TT-27
BR-FR-MAP-08	Exemption in base	If an invoice contains a VAT detail block (BG-23) containing a BT-118 Category code = "E" AND a BT-121 VATEX code = "VATEX-FR-FRANCHISE", THEN <u>the action to be taken in flow 1 is as follows:</u> - transcode BT-118 to "Z" - delete VATEX BT-121 and the reason in text BT-120, if present	BT-118, BT-121, BT-120

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

BR CODE	Title	Description	Applies to
BR-FR-MAP-09	Exemption in base	If an invoice contains a VAT detail block (BG-23) containing a BT-118 Category code = "E" AND a BT-121 VATEX code = "VATEX-FR-FRANCHISE", then BT-118 shall be transcoded to "Z" and neither the VATEX code BT-121 nor the text reason BT-120, if present, shall be transmitted in flow 10.1 (TT-56).	BT-118, BT-121, BT-120
BR-FR-MAP-10	Delivery Address	If BT-80 is present, there is a Delivery Address and all fields in the Delivery Address group (BG-15) shall be filled out in flow 1 or 10.1. If Line 1 (BT-75), Postal Code (BT-78) or Locality (BT-77) are missing, enter "-" instead.	BG-15, BT-75, BT-77, BT-78, BT-80
BR-FR-MAP-11	Delivery Address	If EXT-FR-FE-157 is present, there is a Delivery Address in line and all fields in the Delivery Address group (EXT-FR-FE-BG-10) shall be filled out except for the global location identifier (EXT-FR-FE-146, EXT-FR-FE-148) in flow 1 or 10.1, and if Line 1 (EXT-FR-FE-151), Postal Code (EXT-FR-FE-155) or City (EXT-FR-FE-154) is missing, enter "-" instead.	EXT-FR-FE-BG-10, EXT-FR-FE-151, EXT-FR-FE-154, EXT-FR-FE-155, EXT-FR-FE-157
BR-FR-MAP-12	Authorized VAT rate	The applicable VAT rate shall be mapped to the following data: Rate 0 10 13 20 8.5 19.6 2.1 5.5 7 20.6 1.05 0.9 1.75 9.2 9.6 The rate is expressed as a percentage and not as a coefficient (e.g., 20). The symbol "%" should not be included. The separator (".") is not counted in the 5 characters.	BT-96, BT-103, BT-119, BT-152
BR-FR-MAP-13	Data Flow 1, 10.1 TARGET	This data is not required at the START of the reform in flows 1 and 10.1, but in TARGET (09/01/2027) (September 1 st 2027).	BT-26, BG-15, BT-75, BT-76, BT-165, BT-77, BT-78, BT-79, BT-80, BG-20, BT-92, BT-95, BT-96, BG-25, BT-127-00, EXT-FR-FE-183, BT-127, BT-129, BT-130, EXT-FR-FE-BG-06, EXT-FR-FE-138, EXT-FR-FE-BG-10, EXT-FR-FE-149, EXT-FR-FE-150, EXT-FR-FE-151, EXT-FR-FE-152, EXT-FR-FE-153, EXT-FR-FE-154, EXT-FR-FE-155, EXT-FR-FE-156, EXT-FR-FE-157, EXT-FR-FE-BG-11, EXT-FR-FE-158, BG-26, BT-134, BT-135, BG-27, BT-136, BG-28, BT-141, BG-29, BT-146, BT-147, BT-148, BG-31, BT-153

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

BR CODE	Title	Description	Applies to
BR-FR-MAP-14	Country Code	The country codes for the French overseas departments and territories below shall be replaced by FR in flows 1 and 10 French Guiana (la) =; GF French Southern Territories (TF) Guadeloupe (la) =; GP Guyana (le) =; GY Martinique (la) =;MQ Mayotte =; YT Réunion (La) =;RE Saint Barthélemy =; BL Saint Martin (French part) =; MF Saint Pierre and Miquelon =; PM	BT-40, BT-55, BT-80, EXT-FR-FE-157
BR-FR-MAP-15	BT-24 MAPPING	For flow 1, BT-24 shall be equal to: urn.cpro.gouv.fr:1p0:invoicingextract#Base for the START profile, without the lines urn.cpro.gouv.fr:1p0:invoicingextract#Full for the complete profile (TARGET)	BT-24
BR-FR-MAP-16	Identifier of the Seller and Buyer in flow 10	The Seller ID (TT-33-1) entered is defined by the qualifier: - "0002" --> SIREN with 9 characters - "0223" --> EU_OUTSIDE_FRANCE (corresponds to the intra-community VAT identifier) with 18 characters - "0227" --> OUTSIDE_EU (including Wallis and Futuna) (corresponds to the country code and the first 16 characters of the company name) with 18 characters - "0228" --> RIDET with 9 or 10 characters - "0229" --> TAHITI with 9 characters The Buyer ID (TT-37) entered is defined by the qualifier: - "0002" --> SIREN in 9 characters - "0223" --> EU_OUTSIDE_FRANCE (corresponds to the intra-community VAT identifier) with 18 characters - "0227" --> OUTSIDE_EU (including Wallis and Futuna) (corresponds to the country code and the first 16 characters of the company name) on 18 characters - "0228" --> RIDET in 9 or 10 characters - "0229" --> TAHITI with 9 characters	BT-30
BR-FR-MAP-17	TRUNCATE TO 255 Characters	If the data length exceeds 255 characters <u>THEN for the same data to be reported in Flow 1</u> Only the first 255 characters on the left should be kept and the rest deleted	BT-75, BT-76, BT-165, BT-77, BT-79, EXT-FR-FE-151, EXT-FR-FE-152, EXT-FR-FE-153, EXT-FR-FE-154, EXT-FR-FE-156, BT-153
BR-FR-MAP-18	TRUNCATE TO 1024 Characters	If the length of the data exceeds 1024 characters <u>THEN for the same data to be reported in Flow 1</u> Only the first 1024 characters on the left should be kept and the rest deleted	BT-22, BT-120, BT-127
BR-FR-MAP-19	TRUNCATE TO 10 characters	If the data length exceeds 10 characters <u>THEN for the same data to be reported in Flow 1</u> Only the first 10 characters on the left should be kept and the rest deleted	BT-78, EXT-FR-FE-155
BR-FR-MAP-20	TRUNCATE TO 100 characters	If the data length exceeds 100 characters <u>THEN for the same data to be reported in Flow 1</u> Only the first 100 characters on the left should be kept and the rest deleted	EXT-EN-FE-149
BR-FR-MAP-21	Gross Price	If the Gross Unit Price (BT-148) is missing from the invoice, <u>THEN, to create flow 1:</u> the Net Unit Price (BT-146) shall be entered in the Gross Unit Price (BT-148)	BT-148
BR-FR-MAP-22	Gross Price	If the Gross Unit Price (BT-148) is not included in the invoice, <u>THEN, to create flow 10.1:</u> the Net Unit Price (BT-146) shall be indicated in the Gross Unit Price (TT-71)	BT-148

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

BR CODE	Title	Description	Applies to
BR-FR-MAP-23	Date format	In flow 10.1, dates are in YYYYMMDD format THEREFORE, for flows 2, 8, and 9 in UBL syntax, the "-" shall be removed EXAMPLE: 2025-02-12 becomes 20250212	BT-2/TT-20, BT-9/TT-201, BT-26//TT-31, BT-72/TT-41, BT-73/TT-42, BT-74/TT-43, EXT-FR-FE-138/TT-301, BT-134/TT-65, BT-135/TT-66
BR-US-MAP-24	Exclusion of GROUP and INFORMATION lines	Only lines (BG-25) without a line subtype (EXT-FR-FE-163) or with a line subtype value equal to "DETAIL" SHALL be taken into account for the creation of flows 1 or flows 10.1.	EXT-FR-FE-163
BR-FR-MAP-25	Reason for exemption in code and text in flows 1 and 10.1	In a VAT breakdown line (BG-23), if the exemption reason in code (BT-121) is present, and the exemption reason in text (BT-120) is absent, then the text corresponding to the VATEX code present in BT-121, as listed in the VATEX code list, shall be indicated in the exemption value in text (BT-120) of flow 1.	BT-120
BR-FR-MAP-26	Reason for exemption in code and text in flows 1 and 10.1	In a VAT breakdown line (BG-23), if the exemption reason in code (BT-121) is present and the exemption reason in text (BT-120) is absent, then the text corresponding to the VATEX code present in BT-121 (and to be entered in TT-59), as listed in the VATEX code list	TT-58
BR-FR-MAP-27	Reason for exemption in code and text in flows 1 and 10.1	In a VAT breakdown line (BG-23), if the exemption reason in text (BT-120) is present and the exemption reason in code (BT-121) is absent, then the value "NR" shall be indicated in the exemption field in code (BT-121) of flow 1.	BT-121
BR-FR-MAP-28	Reason for exemption in code and text in flows 1 and 10.1	In a VAT breakdown line (BG-23), if the exemption reason in text (BT-120) is present and the exemption reason in code (BT-121) is absent, then the value "NR" shall be entered in the exemption code field (TT-59) of flow 10.1.	TT-59
BR-FR-MAP-29	VAT Point Date code, Option for debits	The VAT due date on Debits may correspond to the invoice date (code 5 in CII or 3 in UBL), or to the delivery date (29 in CII or 35 in UBL). However, the PPF only expects 5 (CII) or 3 (UBL). If BT-8 is equal to 29 in CII or 35 in UBL, then in flow 1 or flow 10.1 (TT-24), you shall enter 5 (CII) or 3 (UBL) respectively.	BT-8, TT-24
BR-FR-MAP-30	Discount on Unit Price	If there are multiple unit price discounts (BT-147), they shall be added them together to populate Flow 1 (BT-147) and Flow 10.1 (TT-70). Please note that this information is required in Flows 1 and 10.1 starting in September 2027.	BT-147, TT-70
BR-FR-MAP-31	0% VAT Rate for Invoices Not subject to VAT (O)	If an invoice contains VAT breakdown blocks (BG-23) with a VAT category code "Not subject to VAT" (BT-118 = "O"), and if the VAT rate is missing (BT-119), it SHALL be mapped the value 0 in flow 1 (BT-119) and in flow 10.1 (TT-57).	BT-119, TT-57

4.5.3 CPRO control rules for B2G invoices to the public sector

All of the rules below apply if the invoice falls within the B2G scope. This can be determined by an indication in the invoice (through a Note with ADN Subject Code and B2G content), or by an indication in the transmission channel between the invoice issuer and its PA-E (Accredited Platform of the Sender) and/or following consultation of the directory by the PA-E to determine that the Purchaser is a public entity.

This translates into a general condition for applying all of the additional checks required for B2G invoices and listed below:

- If there is a note (BG-1) with a subject code (BT-21) equal to ADN and the content (BT-22) is equal to B2G, or if the processing identifies that it is a B2G invoice.

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

The table below lists the "CHORUS PRO" management rules applicable to B2G invoices:

BR CODE	Title	Description	Applies to
BR-FR-CPRO-01	Qualification of a contract/market	This management rule applies only to B2G: Possible values are: - for a "MARCHÉ" : value "GC" - for a "CONTRAT" : value "CT" If the contract type (EXT-FR-FE-01) is present, then the only possible values are "CT" (pour un CONTRAT) ou "GC" (MARCHÉ)	EXT-FR-FE-01
BR-FR-CPRO-02	Invoice ID	Management rule applicable to B2G: The invoice ID SHALL BE limited to 20 characters The number of characters in invoice numbers (BT-1), previous invoices (BT-25), and previous in line invoices (EXT-FR-FE-136) SHALL be less than or equal to 20.	BT-1, BT-25, EXT-FR-FE-136
BR-FR-CPRO-03	Private IDs of the parties	Management rule applicable only to B2G: The Seller's private ID (BT-29) SHALL be present, with a schemeld (BT-29-1) equal to 0009, 0223, 0226, 0227, 0228, or 0229. For information, the identifier shall be set to one of the values below and comply with the length: - SIRET with 14 characters (schema identifier: 0009) - EU_OUTSIDE_FRANCE (corresponds to the intra-community VAT identifier) with 18 characters (scheme identifier: 0223) - OUTSIDE_UE (including Wallis and Futuna) (corresponds to the country code and the first 16 characters of the company name) with 18 characters (scheme identifier: 0227) - RIDET with 9 or 10 characters (scheme identifier: 0228) - TAHITI with 9 characters (scheme identifier: 0229) - INDIVIDUAL with 80 characters (scheme identifier: 0226) The 0226 identifier is specific to B2G (the invoice recipient (BG-7) shall be exclusively a public entity). Not to be used in B2B, international B2B, or B2C. The identifier consists of a maximum of 80 characters in the following specific order: • Character #1: gender, represented by 1 digit (1 for male and 2 for female); • Characters 2 and 3: the year of birth, represented by the last 2 digits; • Characters 4 and 5: the month of birth, represented by 2 digits; • Characters 6 to 10: place of birth, represented by 5 digits. • Characters 11 to 80: - The first 35 characters of the last name (spaces removed) - The first 35 characters of the first name (spaces removed)	BT-29
BR-FR-CPRO-04	Private IDs of the parties	If the identification scheme for the Seller's private ID (BT-29-1) is equal to 0223, then the number of characters SHALL be less than 18 It shall correspond to the Seller's VAT number (also present in BT-31)	BT-29
BR-FR-CPRO-05	Private IDs of the parties	If the identification scheme for the Seller's private ID (BT-29-1) is equal to 0227, then the number of characters SHALL be less than 18. It shall correspond to the 2-character country code followed by the first 16 characters of the company name as entered in the ChorusPro repository.	BT-29
BR-FR-CPRO-06	Private IDs of the parties	If the identification scheme for the Seller's private ID (BT-29-1) is equal to 0228, then the number of characters SHALL be between 9 and 10. It shall correspond to the RIDET	BT-29
BR-FR-CPRO-07	Private IDs of the parties	If the identification scheme for the Seller's private ID (BT-29-1) is equal to 0229, then the number of characters SHALL be between 9 and 10 It shall correspond to a TAHITI identifier	BT-29

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

BR CODE	Title	Description	Applies to
BR-FR-CPRO-08	Private IDs of the parties	If the identification scheme for the Seller's private ID (BT-29-1) is equal to 0226, then the first 10 characters SHALL be numbers and the remaining 70 characters SHALL be letters. It shall correspond to an INDIVIDUAL identifier	BT-29
BR-FR-CPRO-09	Seller identifier	Management rule applicable only to B2G: If a SIREN-type identifier for the seller is entered in BT-30, the BT-29 tag shall be filled in with the seller's SIRET (schema identifier 0009). If BT-30 is present and BT-30-1 = 0002, then BT-29 SHALL be present with a schemedID BT-29-1 = 0009 This SIRET identifier shall exist and be active in Chorus Pro (i.e., this organization must be registered in the Chorus Pro Services Portal) in the Directory. This rule cannot be verified automatically.	BT-29, BT-29-1, BT-30, BT-30-1
BR-FR-CPRO-10	Buyer identifier	This management rule applies only to B2G: The BUYER's private ID (BT-46) SHALL be filled in with the Buyer's SIRET number. A private ID for the Buyer (BT-46) with a schemedID (BT-46-1) equal to 0009 SHALL be present.	BT-46, BT-46-1
BR-FR-CPRO-11	Buyer identifier	This management rule applies only to B2G: If the Directory indicates that the Buyer identified by the SIRET number (BT-46, with BT-46-1 equal to 0009) requires a Service Code (DT-4-13-2 = true), then a private ID (BT-46) with schemeID 0224 (routing code) SHALL be entered with a Service Code If the DT-4-13-2 Directory record for the Buyer's SIRET (DT-4-3) is equal to "true", then a private ID for the Buyer (BT-46) with a schemedID (BT-46-1) equal to 0224 SHALL be present and correspond to one of the Service Codes entered in the directory for this SIRET.	BT-46, BT-46-1
BR-FR-CPRO-12	Purchase order/commitment number	Management rule applicable only for B2G: For debtors who have made the commitment number mandatory (see the directory of recipients), the BT-13 tag shall be filled in. Where applicable, the number of the underlying executable contract may replace the commitment reference (and is therefore present in BT-13). If the DT-4-13-1 Directory entry for the Buyer's SIRET (DT-4-3) is "true", then the order number (BT-13) SHALL be present.	BT-13
BR-FR-CPRO-13	Purchase order/commitment number	Management rule applicable only for B2G: For debtors who have made the commitment number or the "Service Executant" code mandatory (see the directory of recipients), the BT-13 tag or the private ID BT-46 with schemeD 0224 shall be filled in. If the DT-4-13-3 Directory record for the Buyer's SIRET (DT-4-3) is equal to "true", then the order number (BT-13) or the Executing Service Code (BT-46 with shemeID = 0224) SHALL be present.	BT-13
BR-FR-CPRO-14	Contract reference	Management rule applicable only for B2G: The contract reference contains a maximum of 50 characters The number of characters in the contract number (BT-12) is less than or equal to 50 characters.	BT-12

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

BR CODE	Title	Description	Applies to
BR-FR-CPRO-15	Purchase order/commitment number	Management rule applicable only to B2G: The commitment reference contains a maximum of 50 characters The number of characters in the order number (BT-13) is less than or equal to 50 characters.	BT-13
BR-FR-CPRO-16	Third-party identification	Management rule applicable only to B2G: The "INVOICEE" (EXT-EN-FE-BG-04) and "BUYER'S AGENT" (EXT-EN-FE-BG-01) fields shall not be filled in. If these blocks are filled in, they will be ignored. Rule not verifiable	EXT-FR-FE-BG-01, EXT-FR-FE-BG-04
BR-FR-CPRO-17	Private third-party IDs	Management rule applicable only to B2G: If a payee shall be mentioned on the invoice, then a SIRET identifier (schema identifier 0009) shall be entered in BT-60 if the third party has a SIREN in BT-61 (payee) or another identifier from the following list if there is no SIREN in BT-61: EU_OUTSIDE FRANCE ("0223"), OUTSIDE_EU ("0227"), RIDET ("0228"), TAHITI ("0229"), INDIVIDUAL ("0226") If BG-10 is present, then: . If BT-61 is present with schemeID = 0002 (SIREN), then BT-60 SHALL be present with schemeID 0009 and be the SIRET (first 9 digits identical to the SIREN) . OTHERWISE, BT-60 shall be present, with qualifier (BT-60-1) equal to 0223, 0226, 0227, 0228, or 0229	BG-10, BT-60, BT-61
BR-FR-CPRO-18	Private third-party IDs	Management rule applicable only for B2G: If a sales agent shall be mentioned on the invoice, then a SIRET-type identifier (schema identifier 0009) shall be entered in EXT-FR-FE-69 if the third party has a SIREN in EXT-FR-FE-71 or another identifier from the following list if there is no SIREN in EXT-FR-FE-71: EU_OUTSIDE FRANCE ("0223"), OUTSIDE_EU ("0227"), RIDET ("0228"), TAHITI ("0229"), INDIVIDUAL ("0226") If a Sales Agent (EXT-FR-FE-BG-03) is present, then: . If EXT-FR-FE-69 is present with schemeID = 0002 (SIREN), then the SIRET number (EXT-FR-FE-71) SHALL be present with schemeID 0009 (EXT-FR-FE-72) and be the SIRET (first 9 digits identical to the SIREN) . OTHERWISE, EXT-FR-FE-71 shall be present, with qualifier (EXT-FR-FE-72) equal to 0223, 0226, 0227, 0228, or 0229	EXT-FR-FE-BG-03, EXT-FR-FE-69, EXT-FR-FE-71
BR-FR-CPRO-19	Invoice lines	Management rule applicable only for B2G: The line number (BT-126) is a numeric sequence (integer) limited to 6 characters (1-999999). Line numbers references are not checked, but the number of lines in a B2G invoice (BG-25) MUST be strictly less than 1,000,000.	BT-126
BR-FR-CPRO-20	Reference to the previous invoice	Management rule applicable only to B2G: Only one previous invoice reference is allowed. The BG-3 Previous Invoice group SHALL have only one occurrence	BG-3
BR-FR-CPRO-21	Subcontracting/co-contracting B2G	Management rule applicable only to B2G: If the "billing framework" (BT-23, "Cadre de Facturation") is S3 or S6 (B2G subcontracting/co-contracting management case), the AGENT OF SELLER group (EXT-FR-FE-BG-03) SHALL be present in order to provide information on the holder/agent, as well as their SIREN number (EXT-FR-FE-71) and SIRET number (EXT-FR-FE-69 with schemeID EXT-FR-FE-70 = 0009).	BT-23, EXT-FR-FE-BG-03, EXT-FR-FE-71

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

BR CODE	Title	Description	Applies to
BR-FR-CPRO-22	Private IDs of third parties	Management rule applicable only to B2G: If the AGENT DE VENDEUR (EXT-FR-FE-BG-03) is present and contains a Private ID (EXT-FR-FE-69) with a schema ID (EXT-FR-FE-70) equal to 0009 (SIRET type), then the Sales Agent's SIRET identifier shall exist and be active in Chorus PRO (i.e., this entity must be registered in the Chorus PRO Services Portal). Business rule that cannot be verified automatically	EXT-FR-FE-BG-03, EXT-FR-FE-69, EXT-FR-FE-70
BR-FR-CPRO-23	Subcontracting/co-contracting B2G	Management rule applicable only to B2G: If the invoicing framework (BT-23) is "S3" (Submission of a subcontracting service invoice with direct payment), the invoice recipient identified in BG-7 (Purchaser) SHALL be a public entity identified as such in the Directory Business rule not automatically verifiable	BT-23
BR-FR-CPRO-24	Invoicing framework	Management rule applicable only to B2G: The Invoicing Framework (BT-23) SHALL NOT be equal to S5 (Subcontractor submission of a service invoice).	BT-23
BR-FR-CPRO-25	Payment terms	Management rule applicable only to B2G: Only one payment condition is allowed. BT-20 has only one occurrence.	BT-20
BR-FR-CPRO-26	Seller contact	Management rule applicable only to B2G: Only one seller contact is allowed. BG-6 has only one occurrence	BG-6
BR-FR-CPRO-27	Buyer contact	Management rule applicable only to B2G: Only one buyer contact is allowed. BG-9 has only one occurrence	BG-9
BR-FR-CPRO-28	Seller agent contact	Management rule applicable only to B2G: Only one sales agent contact is allowed. EXT-EN-FE-85 has only one occurrence	EXT-EN-FE-85
BR-FR-CPRO-29	Reason for VAT exemption	Management rule applicable only for B2G: The length of the "Reason for VAT exemption" data is limited to 1024 characters. The number of characters in the Reason for exemption text in the VAT breakdown block (BT-120) SHALL be less than or equal to 1024.	BT-120
BR-FR-CPRO-30	Supporting document reference	Management rule applicable only to B2G: The length of the "Supporting document reference" data is limited to 50 characters. The number of characters in the Supporting Document Reference (BT-122 from BG-24) SHALL be less than or equal to 50.	BT-122
BR-US-CPRO-31	Item description	Management rule applicable only to B2G: The length of the "Item description" data is limited to 1024 characters. The number of characters in the Item Description (BT-154) SHALL be less than or equal to 1024.	BT-154

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

BR CODE	Title	Description	Applies to
BR-US-CPRO-32	Seller address - Line 1	Management rule applicable only to B2G: The length of the "Seller address - Line 1" data is limited to 400 characters. The number of characters in the Seller address - line 1 (BT-35) SHALL be less than or equal to 400.	BT-35
BR-US-CPRO-33	Seller's location	Management rule applicable only for B2G: The length of the "Seller's location" data is limited to 400 characters. The number of characters in the seller's location (BT-37) SHALL be less than or equal to 400.	BT-37
BR-US-CPRO-34	Buyer's trade name	Management rule applicable only to B2G: The length of the "Buyer's trade name" data is limited to 99 characters. The number of characters in the buyer's trade name (BT-45) SHALL be less than or equal to 99.	BT-45
BR-FR-CPRO-35	Payment terms	Management rule applicable only to B2G: The length of the "Payment terms" data is limited to 1024 characters. The number of characters in the Payment terms (BT-20) SHALL be less than or equal to 1024.	BT-20
BR-FR-CPRO-36	Seller's trade name	Management rule applicable only to B2G: The length of the "Seller's trade name" data is limited to 99 characters. The number of characters in the Seller's trade name (BT-28) SHALL be less than or equal to 99.	BT-28
BR-US-CPRO-37	Payee name	Management rule applicable only to B2G: The length of the "Payee name" data is limited to 99 characters. The number of characters in the Payee name (BT-59) SHALL be less than or equal to 99.	BT-59
BR-FR-CPRO-38	Delivery establishment identifier	Management rule applicable only to B2G: The length of the "Delivery establishment identifier" data is limited to 20 characters. The number of characters in the Delivery Facility Identifier (BT-71) SHALL be less than or equal to 20.	BT-71
BR-US-CPRO-39	Payment account identifier	Management rule applicable only to B2G: The length of the "Payment Account Identifier" data is limited to 27 characters. The number of characters in the Payment Account ID (BT-84) SHALL be less than or equal to 27	BT-84
BR-FR-CPRO-40	Global identifier of the delivery location on the line	Management rule applicable only for B2G: The length of the "Global delivery location identifier on the line" data is limited to 20 characters. The number of characters in the Global identifier of the delivery location at the line level (EXT-FR-FE-146) SHALL be less than or equal to 20.	EXT-FR-FE-146

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

BR CODE	Title	Description	Applies to
BR-FR-CPRO-41	File name of the attached document	Management rule applicable only to B2G: The length of the "Attached document file name" data is limited to 50 characters. The number of characters in the attached document file name (BT-125-2) SHALL be less than or equal to 50.	BT-125-2
BR-US-CPRO-42	Invoice note	Management rule applicable only to B2G: The length of the "Invoice note" data is limited to 1024 characters. The number of characters in the Invoice Note (BT-22) content SHALL be less than or equal to 1024.	BT-22
BR-FR-CPRO-43	Seller's company name	Management rule applicable only to B2G: The length of the "Seller's company name" data is limited to 99 characters. The number of characters in the Seller's company name (BT-27) SHALL be less than or equal to 99.	BT-27
BR-FR-CPRO-44	Buyer's company name	Management rule applicable only to B2G: The length of the "Buyer's company name" data is limited to 99 characters. The number of characters in the buyer's company name (BT-44) SHALL be less than or equal to 99.	BT-44
BR-FR-CPRO-45	B2G Subcontracting / Co- Contracting	If the invoicing framework (BT-23, Cadre de Facturation) of the invoice is of the subcontractor or co-contractor type (S3, S5, or S6): the seller's agent (EXT-FR-FE-BG-03) must not have a supplementary SIRET identifier (EXT-FR-FE-69, with EXT-FR-FE-70 equal to 0009) that is identical to the buyer's supplementary SIRET identifier (BT-46, with BT-46-1 equal to 0009).	BT-23, EXT-FR-FE-69, EXT-FR-FE-70, BT-46, BT-46-1
BR-FR-CPRO-46	B2G Subcontracting / Co- Contracting	If the invoicing framework (BT-23, Cadre de Facturation) of the invoice is of the subcontractor or co-contractor type (S3, S5, or S6): the sales agent (EXT-FR-FE-BG-03) must not have an additional SIRET identifier (EXT-FR-FE-69, with EXT-FR-FE-70 equal to 0009) that is identical to that of the government entity known to Chorus Pro (11000201100044).	BT-23, EXT-FR-FE-69, EXT-FR-FE-70, BT-46, BT-46-1
BR-FR-CPRO-47	B2G Subcontracting / Co- Contracting	If the invoicing framework (BT-23, Cadre de Facturation) of the invoice is of the subcontractor or co-contractor type (S3, S5, or S6): the sales agent (EXT-FR-FE-BG-03) must not have an additional SIRET identifier (EXT-FR-FE-69, with EXT-FR-FE-70 equal to 0009) that is identical to that of the government entity known to Chorus Pro (11000201100044).	BT-23
BR-FR-CPRO-48	Multi-sellers invoice	As the multi-seller use-cas is not yet available on CHORUS PRO, invoices with an invoice framework (BT-23) equal to B8, M8 or S8 will be rejected.	BT-84
BR-FR-CPRO-49	IBAN reference	If an IBAN reference must be used, the BT-84 must be exactly 27 characters	BT-84, BT-86
BR-FR-CPRO-50	payee financial institution's reference	If the payment account identifier (BT-84) is an IBAN, the payment service provider identifier (BT-86)—which is optional—must be a BIC. This field must be 8 to 11 characters long, excluding spaces (bank code + country code + location code + optional branch code, all combined without separators).	BT-29, BT-46 (BT-46-1 = '0224')

4.5.4 Specific management rules for multi-seller invoices and bidirectional self-billing

To indicate that an invoice is multi-seller, use a B8, S8, or M8 invoicing framework in BT-23, bearing in mind that the invoicing framework for unit invoices may vary from one SELLER to another and is therefore indicated in the invoice line (the one labelled GROUP at a minimum). Similarly, for bidirectional self-billing, a B9, S9, or

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

M9 invoicing framework must be used in BT-23, noting that the invoicing framework for the main self-bill and the cross-invoice is specified in the header GROUP line of each of the two sub-invoices. This is why all of the management rules below only apply if the Business process type (BT-23 : “Cadre de Facturation”) is equal to B8, S8, M8 or B9, S9 M9, some of which apply only to multi-vendor invoices or bidirectional self-invoices

The table below lists the specific rules for managing multi-seller invoices

BR CODE	Title	Description	Applies to
BR-FR-MV-01	Multi-seller invoice Two-way invoice	If the Business Process Type (BT-23 : “Cadre de Facturation” – “Billing Framework”) is equal to S8, B8, M8, or S9, B9, M9, then: All lines (BG-25) SHALL contain a line subtype (EXT-FR-FE-163).	EXT-US-FE-163
BR-FR-MV-02	Multi-seller invoice GROUP line by sub-vendor	If the Business process type (BT-23 : “Cadre de Facturation”) is equal to S8, B8, M8, then: The invoice SHALL contain at least 1 line (BG-25) with the line subtype (EXT-FR-FE-163) equal to "GROUP" and without a Parent line identifier (EXT-FR-FE-162)	EXT-FR-FE-163
BR-FR-BD-02	Two-way invoice	If the Business process type (BT-23 : “Cadre de Facturation”) is equal to S9, B9, or M9, then: The invoice SHALL contain exactly 2 lines (BG-25) with the line subtype (EXT-FR-FE-163) set to “GROUP” and without a parent line ID (EXT-FR-FE-162), and for which one has the legal line-level seller ID (EXT-FR-FE-167) set to the legal ID of the SELLER (BT-30) and the other has the legal line-level seller ID (EXT-FR-FE-167) set to the legal ID of the BUYER (BT-47).	EXT-FR-FE-163
BR-FR-MV-03	Multi-seller invoice Two-way invoice	If the Business process type (BT-23 : “Cadre de Facturation”) is equal to S8, B8, M8, or S9, B9, M9, then: For each line (BG-25) with a line subtype (EXT-FR-FE-163) equal to "GROUP" and without a parent line identifier (EXT-FR-FE-162), the following data SHALL be present: . A line level seller name (EXT-FR-FE-164) . A line level seller ID (EXT-FR-FE-167) . A line level seller country code (EXT-FR-FE-177) . A line level invoiced object value (BT-128) with schema identifier (BT-128-1) = AFL (invoice number per vendor) . A mine level invoiced object value (BT-128) with schema identifier (BT-128-1) = AVV (billing framework “Cadre de Facturation” per seller), different from M8/S8/B8/M9/S9/B9 . A total amount with VAT on the line (EXT-FR-FE-184) in invoice currency	EXT-FR-FE-164, EXT-FR-FE-167, EXT-FR-FE-177, BT-128, BT-128-1
BR-FR-MV-04	Multi-seller invoice Two-way invoice line level seller VAT ID	If the Business process type (BT-23 : “Cadre de Facturation”) is equal to S8, B8, M8, or S9, B9, M9, then: For each line (BG-25) with a line subtype (EXT-FR-FE-163) equal to "GROUP" and without a Parent line identifier (EXT-FR-FE-162), if the Line level Seller is subject to VAT and has a VAT ID, then the line VAT ID (EXT-FR-FE-168) SHALL be present.	EXT-FR-FE-168
BR-FR-MV-05	Multi-seller invoice Two-way invoice Rule for calculating the total excluding tax per seller	If the Business process type (BT-23 : “Cadre de Facturation”) is equal to S8, B8, or M8, or S9, B9, M9, then: The line total excluding tax (BT-131) for lines (BG-25) with a line subtype (EXT-FR-FE-163) equal to "GROUP" and without a parent line identifier (EXT-FR-FE-162) SHALL be equal to the sum of the line totals (BT-131) of the lines for which the Parent line identifier (EXT-FR-FE-162) is equal to the line identifier (BT-126) of the "GROUP" line.	EXT-FR-FE-BG-12, BT-128, EXT-FR-FE-162

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

BR CODE	Title	Description	Applies to
BR-FR-MV-06	Multi-seller invoice Two-way invoice Legal vendor ID on the line	If the Business process type (BT-23 : “Cadre de Facturation”) is equal to S8, B8, M8, or S9, B9, M9, then: All invoice lines (BG-25) SHALL contain a legal vendor ID on the line (EXT-FR-FE-167), identical to that of the line (BG-25) whose line ID (BT-126) is equal to the Parent line ID (EXT-FR-FE-162), if present.	EXT-US-FE-167
BR-FR-MV-07	Multi-seller invoice Two-way invoice invoice number on the line	If the Business process type (BT-23 : “Cadre de Facturation”) is equal to S8, B8, M8, or S9, B9, M9, then: All invoice lines (BG-25) SHALL contain a line invoice number, coded with the invoiced object (BT-128 with BT-128-1 = AFL) identical to that of the line (BG-25) whose line identifier (BT-126) is equal to the Parent line identifier (EXT-FR-FE-162), if present.	BT-128, BT-128-1
BR-FR-MV-08	Multi-seller invoice Two-way invoice Reason for exemption on the line	If the Business process type (BT-23 : “Cadre de Facturation”) is equal to S8, B8, M8, or S9, B9, M9, then: All invoice lines (BG-25) SHALL contain a VAT exemption reason in text beginning with the line level invoice number (EXT-FR-FE-178) between # (example #F2025003#)	BT-128, BT-128-1, EXT-US-FE-178
BR-FR-MV-09	Multi-seller invoice Two-way invoice VAT amount per "GROUP" line seller	If the Business process type (BT-23 : “Cadre de Facturation”) is equal to S8, B8, M8, or S9, B9, M9, then: The total VAT amount per line (EXT-FR-FE-181) for lines (BG-25) with a line subtype (EXT-FR-FE-163) equal to "GROUP" and without a parent line identifier (EXT-FR-FE-162) SHALL be equal to the sum of the VAT amounts from the VAT breakdown (BT-117) for which the reason for exemption (BT-120) begins with the invoice number on the line (BT-128 with BT-128-1 = AFL) between #	EXT-FR-FE-181
BR-FR-MV-10	Multi-seller invoice Two-way invoice Total amount with VAT per line seller "GROUP"	If the Business process type (BT-23 : “Cadre de Facturation”) is equal to S8, B8, M8, or S9, B9, M9, then: If the total amount with VAT at line level (EXT-FR-FE-184) of a line (BG-25) with a line subtype (EXT-FR-FE-163) equal to "GROUP" and without a Parent line identifier (EXT-FR-FE-162) is present, then: The absolute value of (total amount with VAT (EXT-FR-FE-184) - the total line amount without VAT (BT-131) - the total line VAT amount (EXT-FR-FE-181)) <= 0.01 * number of sub-lines with line subtype (EXT-FR-FE-163) equal to "DETAIL".	EXT-FR-FE-184, EXT-FR-FE-181, BT-131
BR-FR-MV-11	Multi-seller invoice Two-way invoice Line invoice number for the main seller	If the Business process type (BT-23 : “Cadre de Facturation”) is equal to S8, B8, M8, or S9, B9, M9, then: If the main seller identified in the Seller block (BG-4) of the invoice through its legal identifier (BT-30) has a group of invoicing lines, then there must be at least one line (BG-25) with line subtype (EXT-FR-FE-163) = "GROUP" and no Parent line identifier (EXT-FR-FE-162), for which the invoice number at the line level (Value of BT-128 with BT-128-1 = AFL) is equal to the invoice number (BT-1).	BT-128, BT-128-1
BR-FR-MV-12	Multi-seller invoice Two-way invoice Unique line item invoice numbers	If the Business process type (BT-23 : “Cadre de Facturation”) is equal to S8, B8, M8, or S9, B9, M9, then: The invoice numbers on the line (value of BT-128 with BT-128-1 = AFL) for lines (BG-25) with line subtype (EXT-FR-FE-163) = "GROUP" and without parent line identifier (EXT-FR-FE-162) SHALL be unique (only one occurrence) and SHALL: - consist of alphanumeric characters (A-Z, a-z, 0-9). The following special characters are allowed: hyphen ("-"), plus sign ("+"), underscore ("_"), and slash ("/")	BT-128, BT-128-1

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

BR CODE	Title	Description	Applies to
		- and be less than 35 characters long. . See recommendations for creating distinct unit invoice numbers that comply with regulatory requirements, chapter 4.4.12.2.	
BR-FR-MV-13	Standard codes for multi-seller invoices (no self-billing)	If the Business process type (BT-23 : “Cadre de Facturation”) is equal to S8, B8, or M8, then: the invoice type code (BT-3) is different from: - Self-billed invoiced (389) - Self-billed credit note (261) - Factored self-billed invoice (501) - Self-billed pre-payment invoice (500) - Factored Self-billed credit note (502) - Self-billed corrected invoice (471) - Self-billed corrected invoice factored (473)	BT-3
BR-FR-BD-13	Standard codes for two-way invoices (only self-billing)	If the Business process type (BT-23 : “Cadre de Facturation”) is equal to S9, B9, or M9, then: the invoice type code (BT-3) is in the following list - Self-billed invoiced (389) - Self-billed credit note (261) - Factored self-billed invoice (501) - Self-billed pre-payment invoice (500) - Factored Self-billed credit note (502) - Self-billed corrected invoice (471) - Self-billed corrected invoice factored (473)	BT-3
BR-FR-MV-14	Previous invoice for a credit memo or a multi-vendor credit note	If the Business process type (BT-23 : “Cadre de Facturation”) is equal to S8, B8, or M8, and if the invoice is a correction invoice or a corrected invoice, with the following codes: - Correction invoice (384) - Factored correction invoice (472) - Credit memo (381) - Factored credit memo (396) - Down payment invoice credit memo (503) Then each line (BG-25) with a line subtype (EXT-FR-FE-163) equal to “GROUP” and without a Parent line identifier (EXT-FR-FE-162) shall include an identifier for the preceding invoice identifier on line level (EXT-FR-FE-136) as well as its date (EXT-FR-FE-138)	EXT-FR-FE-136, EXT-FR-FE-138
BR-FR-BD-14	Previous invoice reference for a corrective two-way invoice or a two-way credit note	If the Business process type (BT-23 : “Cadre de Facturation”) is equal to S8, B8, or M8, and if the invoice is a correction invoice or a corrected invoice, with the following codes: - Self-billed credit note (261) - Factored Self-billed credit note (502) - Self-billed corrected invoice (471) - Self-billed corrected invoice factored (473) Then each line (BG-25) with a line subtype (EXT-FR-FE-163) equal to “GROUP” and without a Parent line identifier (EXT-FR-FE-162) shall include an identifier for the preceding invoice identifier on line level (EXT-FR-FE-136) as well as its date (EXT-FR-FE-138)	EXT-FR-FE-136, EXT-FR-FE-138

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

Below is the table of mapping rules for creating unit invoices for each SELLER, then extracting unit flows 1 / 10.1 as well:

BR CODE	Title	Description	Applies to
BR-FR-MVMAP-01	Unit invoice per seller in the case of multi-seller invoices	If the Business process type (BT-23 : "Cadre de Facturation") is equal to S8, B8, or M8, then the Accredited Platform of the sender ("Plateforme Agréée" PA-E) that supports multi-seller invoice management SHALL create as many flows 1 as there are invoice line numbers in the invoice. To do this, the first step is to create unit invoices by in line invoice number following the rules below based on the information provided at line level (BG-25) with a line subtype (EXT-FR-FE-163) equal to "GROUP" and without a Parent line identifier (EXT-FR-FE-162): . Replace the Seller information (BG-4) with that of the line level Seller (EXT-FR-FE-BG-12) . Replace the invoice number (BT-1) with the invoice number at line level (BT-128, with BT-128-1 = AFL) . Replace the "Cadre de Facturation" (BT-23) with "Cadre de Facturation" (Billing Framework) at line level (BT-128 with BT-128-1 = AVV). . Replace the VAT Tax Point date code (option on debits, BT-8) with the one indicated at line level (EXT-FR-FE-180) . Replace the VAT total in the invoice currency (BT-110) with the VAT amount in invoice currency at line level (EXT-FR-FE-181). . If the preceding Invoice Identifier from the "GROUP" line (EXT-FR-FE-136) is present, enter it in the preceding Invoice Identifier field (BT-25) . If the previous invoice date from the "GROUP" line (EXT-FR-FE-138) is present, enter it in the preceding Invoice date field (BT-26) . If present, replace the VAT total in the accounting currency (BT-111) with the VAT amount in accounting currency at line level (EXT-FR-FE-182). . Replace the total amount with VAT (BT-112) with the total amount with VAT in line (EXT-FR-FE-184). . Fill out the paid amount (BT-113) with the total amount with VAT above (BT-112). . Enter the amount to be paid (BT-115) as 0 (consequently). . Keep only the lines for which the invoice number at line level is that of the unit invoice (BT-128, with BT-128-1 = AFL). . Keep only the VAT breakdown lines (BG-23) for which the reason for exemption in text (BT-120) begins with the invoice number at line level (BT-128, with BT-128-1 = AFL) between #	EXT-FR-FE-BG-12, BT-128, BT-128-1, EXT-FR-FE-180, EXT-FR-FE-181, EXT-FR-FE-182, EXT-FR-FE-184, EXT-FR-FE-136, EXT-FR-FE-136-8
BR-FR-MVMAP-02	Flow configuration 1 or 10.1	If the Business process type (BT-23 : "Cadre de Facturation") is equal to S8, B8, or M8, then the Approved Issuing Platform that supports multi-seller invoice management SHALL create as many flows 1 as there are unit invoices (in line invoice numbers). To do this, the second step consists of extracting flow 1 or 10.1 from the unit invoice, which amounts to using the information provided in line (BG-25) with a line subtype (EXT-FR-FE-163) equal to "GROUP" and without a Parent line identifier (EXT-FR-FE-162), identifying the data specific to each Seller, as follows: . Use the line level Seller information (EXT-FR-FE-BG-12) instead of the Seller information (BG-4). . Use the invoice number at line level (BT-128, with BT-128-1 = AFL) instead of the invoice number (BT-1) . Use the "Cadre de Facturation" at line level (BT-128 with BT-128-1 = AVV) instead of the Business process type (BT-23 : "Cadre de Facturation") . Use the VAT Tax Point date code at line level (option on debits, EXT-FR-FE-180) instead of the invoice code (BT-8) . Use the VAT total amount in invoice currency at line level (EXT-FR-FE-181) instead of the invoice total (BT-110), if present . If the preceding Invoice Identifier from the "GROUP" line (EXT-FR-FE-136) is present, enter it in the preceding Invoice Identifier field (BT-25) of flow 1 (TT-30 of Flow 10.1) . If the previous invoice date from the "GROUP" line (EXT-FR-FE-138) is present, enter it in the preceding Invoice date field (BT-26) of flow 1 (TT-31 of Flow 10.1)	EXT-FR-FE-BG-12, BT-128, BT-128-1, EXT-FR-FE-180, EXT-FR-FE-181, EXT-FR-FE-182

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

BR CODE	Title	Description	Applies to
		. If present, use the VAT total amount in accounting currency at line level (EXT-FR-FE-182) instead of that of the invoice (BT-111). . Use only lines for which the invoice number at line level is that of the unit invoice (BT-128, with BT-128-1 = AFL), and for which the line subtype (EXT-FR-FE-163) is equal to "DETAIL". . Only use VAT breakdown lines (BG-23) for which the exemption reason in text (BT-120) begins with the invoice number at line level (BT-128, with BT-128-1 = AFL) between #	
BR-FR-BDMAP-01	Set up 2 Flow 1 (or 2 Flow 10.1 for B2BINT invoices, if the recipient agrees).	If the Business process type (BT-23 : "Cadre de Facturation") is equal to S9, B9, or M9, then the issuing "Platform Agréée" that supports two-way invoice management SHALL create two required Flow 1 / 10.1 (one for the main self-billing invoice and one for the sales invoice from the Buyer to the Seller). To do this, For the Self-billing invoice: only the DETAIL line data for which the Seller on line level (EXT-FR-FE-BG-12) is the SELLER (BG-4) is extracted. The GROUP line contains the following information to be used instead of that from the invoice: . Use the Business process type on line level (BT-128 with BT-128-1 = AVV) instead of the Business process type at document level (BT-23) . Use the VAT due date code (option on debits, EXT-FR-FE-180) if present, instead of the one from the invoice (BT-8) . Use the VAT total in the invoice currency on line level (EXT-FR-FE-181) instead of the one from the document level (BT-110) . If the Previous Invoice ID from the "GROUP" line (EXT-FR-FE-136) is present, enter it as the Previous Invoice ID (BT-25) for the single-unit flow (TT-30 of flow 10.1) . If the previous invoice date from the "GROUP" line (EXT-FR-FE-138) is present, enter it as the previous invoice date (BT-26) in the unit-based flow 1 (TT-31 of flow 10.1) . For invoices with an accounting currency (BT-6), use the VAT total in the invoice currency on line level (EXT-FR-FE-182) instead of the invoice currency (BT-111). . Use only the VAT breakdown lines (BG-23) for which the exemption reason in text (BT-120) begins with the invoice number on line level (BT-128, with BT-128-1 = AFL) between # For the reverse purchase invoice: . Replace the invoice type code with its corresponding code (380 for 389, 381 for 261, 393 for 501, 396 for 502, 386 for 500, 384 for 471, 472 for 473). . Reverse the SELLER and BUYER data . Extract the DETAIL lines for which the Seller on line level (EXT-FR-FE-BG-12) is the Buyer (BG-7), by reversing the signs of unit prices, line totals, charges, and discounts . Use the same rules as for the self-billing invoice regarding the business processtype (BT-23), the VAT due date code, the VAT breakdown, the total without VAT and total VAT amount, and previous invoices if any.	EXT-FR-FE-BG-12, BT-128, BT-128-1, EXT-FR-FE-180, EXT-FR-FE-181, EXT-FR-FE-182, EXT-FR-FE-136, EXT-FR-FE-136-8

4.6 Rule for creating a readable representation of an electronic invoice under this Standard.

European regulations and their transposition into French law require companies to provide a readable representation of electronic invoices.

Under French law, this obligation is specified as applying to all information contained in the electronic invoice, whether mandatory or optional.

A structured electronic invoice (here in UBL or UN/CEFACT CII) is a set of data associated with a syntactic and semantic structure that conveys the meaning of each piece of data.

4.6.1 Building a readable representation model

The readable representation shall therefore provide both the data and its semantic meaning, and for encoded data (code lists), the meaning in text.

It shall therefore be organized as follows:

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

- First, a presentation model should be defined, which generally consists of three parts commonly accepted in commercial practice:
 - ✓ Header data, presenting the parties (name, electronic address, postal address, identifiers, contact details) and references (including the date, invoice number, and, where applicable, a purchase order number, etc.)
 - ✓ Footer data, which includes VAT breakdown, totals, payment information, and regulatory notices
 - ✓ Line data, generally organized in columns to provide all line information.

Each piece of data shall be unambiguous, which means it shall be named to convey its meaning. For example, a date on its own means nothing. It shall be specified whether it is the invoice date, delivery date, due date, etc.

4.6.2 How to represent data in the form of codes

A certain amount of data is actually codes, such as "invoice type" codes (BT-3: 380 for invoice, 381 for credit note, 386 for advance invoices, etc.). The readable presentation shall therefore show the meaning in text as given in the code lists. When these are in English, the French translation should be provided. Thus, code type 380 will be presented as "Invoice" and 381 as "CREDIT NOTE."

It is not necessary to provide the code value, but it is also possible to display it (for example, in parentheses).

For example, electronic addresses have an identification scheme that can be integrated into the address:

- For an address listed in the directory, a presentation of 0225:SIREN_SUFFIX is sufficiently clear.
- For an email, the structurexxx@zzz.tt is sufficient to understand.

For notes (BG-1), the subject code (BT-21) can also be used to position them in the readable representation (penalty note, discount condition note, processing type note, additional information notes, etc.).

4.6.3 Factur-X and structured invoices with an attached readable presentation

It is complex to create a universal template for presenting all the possible fields of an invoice, as there are many, which is what a receiving solution would do. In particular, the presentation of the lines then requires completing a columnar presentation of data lists to be organized in each line.

It is easier to create a presentation template for the issuer, as they know the data they are using and can therefore present it better.

The Factur-X format consists of a fully readable representation of the invoice to which an invoice data file (factur-x.xml) is attached, which shall comply with the requirements described in this Standard and shall only contain information present in the readable presentation, with the freedom to include certain additional information only in the readable presentation.

Factur-X therefore contains a readable representation that is compliant by design, which means that the solutions that create it strive to ensure that all the information present in the structured file is also present in the PDF presentation.

To do this, it is important that the readable presentation be created from the structured file, adding additional information where necessary, either because it does not fit into the data model or because the issuer does not have it in a structured form (such as general information, graphs, logos, or even promotional or operational information, etc.).

It is also possible for the issuer to create their own readable representation of their UBL or UN/CEFACT CII invoice, in accordance with the rules described above. This readable representation shall then be attached to the structured file in UBL or UN/CEFACT CII, in group BG-24, in BT-125 (usually encoded in Base64), with a BT-123 document description equal to "READABLE."

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

This READABLE representation may contain additional information to that present in the structured file, provided that this information does not belong in the semantic structure of the minimum base format used.

This READABLE presentation can then be used by the invoice recipient for their own purposes. However, they are still required to present the structured invoice file in a readable form at the request of the administration in the event that the file transmitted by the issuer is not compliant. Standard presentation tools for each profile can then be used for this purpose, even if the presentation will be significantly less suited to operational visualization needs for validation purposes, for example.

LISIBLE can also be created using a style sheet that can be made available by the issuer or on their behalf. However, each party wishing to use this style sheet shall ensure that it is kept intact and that it can be used during the retention period. The responsibility for producing the readable version lies with each party, and therefore with the recipient, who cannot be held liable in the event of a defect in the style sheet or its non-applicability.

4.6.4 Examples

It is complex to create a universal template for presenting all the possible fields in an invoice, as there are many of them, which would be a solution on the receiving end. In particular, the presentation of the lines then requires the completion of a columnar presentation of data lists to be organized in each line.

It is easier to create a presentation template for the issuer, as they know the data they are using and can therefore present it better.

Below is an example of the presentation of a fictitious invoice containing almost all of the data present in the EN16931 profile.

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

LOGO LE FOURNISSEUR SELLER TRADE NAME LE FOURNISSEUR 35 rue d'ici, Seller line 2 75018 PARIS, FR CONTACT : M. CONTACT, 01 02 03 54 87, seller@seller.com @dresse électronique (EM) : moi@seller.com ID : 123 - GLN : 587451236587 SIRET : 12345678200077 - DUNS : DUNS1235487 ODETTE : ODETTE254879 SIREN : 123 456 782 N° TVA intra : FR 11 123 456 782		FACTURE N° : F20260023 Date : 31/01/2026 CLIENT : Buyer contact name LE CLIENT CLIENT NOM COMMERCIAL MON ADRESSE LIGNE 1 Buyer line 2 Buyer line 3 06000 MA VILLE, FR @dresse de facturation (EM) : me@buyer.com Contact: 01 01 25 45 87, buyer@buyer.com						
Représentant Fiscal SELLER TAX REP 35 rue d'ici, Seller line 2 75018 PARIS, FR N° TVA Intra : FR 05 987 654 321		Vos identifiants GLN : 3654789851 SIRET : 98765432100029 CODE_R : CDROUT1 - DUNS : DUNS1235684 SIREN : 987 654 321 N° TVA : FR 05 987 654 321						
Nos références N° DE CLIENT : REFCL0215 N° BON DE VENTE : SALES REF 2547		Vos références REFERENCE ACHETEUR / SERVICE EXECUTANT : SERVEXEC REF APPEL D'OFFRES : TENDER-002 REF PROJET : PROJET2547 REF COMPTABLE : BUYER ACCOUNT REF N° CONTRAT : CT2018120802 N° BON DE COMMANDE : PO201925478						
Références sur la facture CADRE DE FACTURATION : S1 N° DE FACTURE ASSOCIÉE : F20260003 DATE DE FACTURE ASSOCIÉE : 01/01/2026 DATE DE DEBUT DE PRESTATION : 01/01/2026 DATE DE FIN DE PRESTATION : 31/12/2026		Livraison: adresse, références DEL Name DEL ADRESSE LIGNE 1 DEL line 2 06000 NICE, FR ID : PRIVATE_ID_DEL - N° BON DE LIVRAISON : DESPADV002 DATE DE LIVRAISON : 28/01/2026 N° BON DE RECEPTION : RECEIV-ADV002						
DEVISE : EURO (EUR)								
# Ligne FACT	# ligne BC CODE ARTICLE, REFERENCE	NOM & DESIGNATION, Période Objet Classification Attributs Note	P.U. HT (EUR)	UNITÉ pour P.U.	Qté	Remise (-) Charge (+) (EUR)	TOTAL HT (EUR) - TVA TTC	TVA (taux, code) - VATEX code VATEX texte
1	# ligne BC: 1 S98785412598745 C.FO: ART_1254 C.ACH: REF5487 REF:BUY_ACC_REF	PRESTATION SUPPORT - Description Période de 01/01/2026 au 31/01/2026 Work team (AOP): EQUIPE_A Cadre de Facturation (AVV): S1 SKU (Stock keeping unit) (SK): SKU2578 (ATT) CATEGORIE : JOUR 8H-20H (I): DONT 0,50 EUR de DEEE	(Brut: 65,00) (Rabais: 5,00) (Net): 60,00	PCE	1,00	-1,00 (RE) 1,00 (CH)	60,00	0,00% (E) - (C) VATEX-EU-79-C (T) DEBOURS
2	# ligne BC: 3 C.FO: ART_9874 C.ACH: REF9854 REF:BUY_ACC_REF ORIGINE:FR	FOURNITURES PAPIER - Description Période de 01/01/2026 au 31/01/2026 Tariff number (AFG): TARIF_2022 Lot number (BB): LOT6254784 (ATT) COULEUR : BLANC (I): DONT 0,50 EUR de DEEE	(Brut: 31,00) (Rabais: 1,00) (Net): 30,00	3 PCE	3,00	-2,00	28,00	10,00% (S)
3	# ligne BC: 2 REF:BUY_ACC_REF	APPEL - Description (I): DONT 0,50 EUR de DEEE	(Brut: 7,00) (Rabais: 0,00) (Net): 7,00		1,00		7,00	20,00% (S)
	95	REMISE : REMISE COMMERCIALE			5,00% sur 100,00 EUR		-5,00	20,00%
	100	REMISE : REMISE COMMERCIALE			1,00% sur 100,00 EUR		-1,00	20,00%
	100	REMISE : REMISE COMMERCIALE			1,00% sur 100,00 EUR		-1,00	20,00%
		REMISE : REMISE COMMERCIALE			2,00% sur 100,00 EUR		-2,00	10,00%
	FC	CHARGE : FRAIS DEPLACEMENT			10,00% sur 100,00 EUR		10,00	20,00%
	ADR	CHARGE : FRAIS DEPLACEMENT			1,00% sur 100,00 EUR		1,00	20,00%
	FC	CHARGE : FRAIS DEPLACEMENT			2,00% sur 100,00 EUR		2,00	(K) 0,00%
	FC	CHARGE : FRAIS DEPLACEMENT			1,00% sur 100,00 EUR		1,00	10,00%
Détail TVA (motif, obligatoire si exonération, code S, E, AE, K, G, O)			Code	Taux	Base TVA	Montant TVA		
VATEX-EU-79-C			DEBOURS	S	20,00%	11,00	2,20	
				E	0,00%	60,00	0,00	
VATEX-EU-IC			LIVRAISON INTRACOMMUNAUTAIRE	S	10,00%	27,00	2,70	
				K	0,00%	2,00	0,00	
TVA acquittée sur les encaissements Tout retard de paiement engendre une pénalité exigible à compter de la date d'échéance, calculée sur la base de trois fois le taux d'intérêt légal. Indemnité forfaitaire pour frais de recouvrement en cas de retard de paiement : 40 €. Les règlements reçus avant la date d'échéance ne donneront pas lieu à escompte. CONDITIONS DE PAIEMENT : PAIEMENT 30 JOURS NET								
						TOTAL HT	TOTAL TVA	TOTAL TTC
						100,00	4,90	104,90
Montant déjà payé : (ou à payer par un tiers)						0,00		
Date d'échéance :			02/03/2026			NET A PAYER		
						104,90 EUR		
Bénéficiaire NOM : PAYEE NAME SIREN : 303656847 - GLN : 587451236586			MOYEN DE PAIEMENT : VIREMENT					
			COMPTES : MON COMPTE BANCAIRE					
			IBAN : FR20 1254 2547 2569 8542 5874 698 - BIC : BIC_MONCOMPTE					
			REFERENCE AVIS DE PAIEMENT : F20260023BUYER					
			MANDATE PT -					

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

4.7 Conversions between base formats

The reform imposes an obligation to convert between the minimum base invoice formats and profiles, which is the subject of this document.

There are several conversion situations:

- Conversion between a UBL invoice and a UN/CEFACT invoice with the same profile: this is the simplest case, since the semantic model is available in both syntaxes. Each piece of data in one syntax has an equivalent place in the other syntax. If a READABLE presentation is attached to the file before conversion, it can be attached in the same way to the converted file.
- Conversion from an EN16931 profile to an EXTENDED profile: the same applies here, since the EXTENDED profile contains all the data from the EN16931 profile.
- Conversion of an EXTENDED-CTC-FR profile to an EN16931 profile: all common data can be converted. However, data present in the EXTENDED-CTC-FR profile that is not in the EN16931 profile cannot be converted. To avoid losing information, it is therefore necessary to attach a READABLE file, either by using the one provided, if applicable, or by creating a READABLE file based on all the information in the EXTENDED-CTC-FR profile before conversion. The READABLE file SHALL then be attached to the converted invoice file.
However, given that the EXTENDED-CTC-FR profile contains tolerances in certain calculation rules, conversion to the EN16931 profile may result in the result not complying with the stricter rules.
- The conversion of a structured UBL or UN/CEFACT CII invoice to Factur-X is like a conversion between structured formats and profiles, except that the creation of a READABLE file is mandatory, either by using the one attached to the source invoice file or by creating it from the data file. Any attachments present in BG-24 of the structured invoice can be attached directly as a PDF/A-3 attachment, alongside the factur-x.xml.
- The conversion of a Factur-X invoice with EN16931 or EXTENDED profile into a structured format (UBL or UN/CEFACT CII) consists first of converting the structured file factur-x.xml to the target format (only for data that has a place in the target profile), then attaching the BG-24 readable file, as well as any attachments from the Factur-X.
- The last case, which will only be accepted until September¹, 2027, is the conversion of a Factur-X with the BASIC WL profile (without lines) to a structured format that shall contain lines. In this case, the conversion shall also create invoice lines containing VAT breakdown information in order to comply with the EN16931 standard.

4.8 Presentation of the annex file describing the minimum invoice formats

The description of the minimum invoice formats is provided in an Excel file containing several sheets:

Sheet name	Description
FE EN16931 + EXTENDED	Semantic description of the invoice for the two profiles (EN16931 and EXTENDED-CTC-FR). The EXTENDED-CTC-FR profile includes all data whose ID begins with EXT. The cardinality can be increased in the EXTENDED-CTC-FR profile compared to EN16931 . Column C: semantic cardinality EN16931 . Column D: Semantic cardinality EN16931 France (CIUS) profile . Column E: semantic cardinality EXTENDED-CTC-FR
BR-France CTC	Specific management rules for France, by category: . BR-FR: management rule on a piece of data . BR-FR-CO: conditional management rule . BR-FR-DEC: rule for number of decimal places . BR-FR-MAP: mapping rule for creating flow 1 or 10.1 . BR-FR-MV: management rules for multi-seller invoices . BR-FR-MVMAP: mapping rules for multi-seller invoices

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

Sheet name	Description
BR-France-CTC-CPRO	BR-FR-CPRO: management rules for B2G invoices (Chorus Pro)
BR EN16931 + EXT FR and FX	Management rules from standard EN16931, + Alternative rule for the EXTENDED-CTC-FR profile (tolerance in footer calculations of 0.01 per line). The application of the rules is then also indicated for the additional Factur-x profiles (BASIC, BASIC WL, MINIMUM, EXTENDED). Additional management rules are also indicated for Factur-X EXTENDED: . BR-FREXT-XXXX: rule for the EXTENDED-CTC-FR profile . BR-FXEXT- XXX: Rule for the EXTENDED Factur-x profile
Codelists for XML Fx - 15 05 2026	List of codes applicable to EN16931 profiles (possibly reduced due to French management rules) and the Factur-X EXTENDED profile, applicable from May 15, 2025
UBL EN16931 FR Flow 2	Description of the UBL invoice format for the EN16931 profile. This is the syntactic implementation of the EN16931 standard, taking into account specific French management rules
Flow 2 UBL EXT-CTC-FR	Description of the UBL invoice format for the EXTENDED-CTC-FR profile. This is the syntactic implementation of the EN16931 semantic profile, taking into account specific management rules for France.
CII D22B & FX EN16931 FR	Description of the UN/CEFACT CII D22B invoice format for the EN16931 profile (and therefore also Factur-X EN16931). This is the syntactic implementation of the EN16931 standard, taking into account specific management rules for France.
CII D22B & FX EXT-CTC-FR	Description of the UN/CEFACT CII D22B invoice format for the EXTENDED-CTC-FR profile (and therefore also Factur-X EXTENDED-CTC-FR, which is a subset of the Factur-X EXTENDED profile). This is the syntactic implementation of the EN16931 Semantic Profile, taking into account specific French management rules.
FACTUR-X BASIC WL FR	Description of the Factur-X data format in UN/CEFACT CII D22B, for the BASIC WL profile. This is the syntactic implementation of the EN16931 standard, taking into account the specific management rules for France.
FE - Flow 1	Semantic description of Flow 1, as published in the external specifications of AIFE 3.0, Annex1.
Flow 1 UBL	Implementation of Flow 1 in UBL. Built from Flow 2 in UBL.
Flow 1 CII	Implementation of Flow 1 in UN/CEFACT built from Flow 2 in CII.
E-REPORTING - Flow 10	Semantic and syntactic description of Flow 10, as published in the AIFE's external specifications, with correspondence between the fields in 10.1 and Flow 2.
Management rules 3.2	Management rules applicable to exchanges between Approved Platforms and the PPF (Annex7 of external specifications 3.2)
CDV FE - CDAR	Semantic and syntactic description of Flow 6 (CDV) in CDAR, on the one hand for use between «Plateformes Agréées» (PA) and PPF (see AIFE external specifications), and on the other hand between «Plateformes Agréées» (PA) themselves and with their respective customers (subject of this publication).
BR-FR-CDV for invoices	Management rules for CDVs (CDAR) relating to invoices (Flows 2, 3)
CDV actors	Life cycle: in the context of life cycle exchanges, which actors are referenced in the CDAR (to maintain «Plateformes Agréées» (PA, Accredited Platforms) confidentiality between end users)
Action codes	"Expected Action" codes that can be used in life cycle status messages
Table of STATUS reasons	Possible reasons for each status, in B2B, to be used and controlled in the CDAR (Reason Codes)

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

4.8.1 Sheet "FE EN16931 + EXTENDED"

This sheet describes the semantic model of the two profiles. In practice, the entire EXTENDED-CTC-FR profile is described, with its cardinality (column E). However, by filtering column A for IDs and excluding all IDs beginning with "EXT," you obtain the description of the EN16931 profile, with the cardinality in column D.

For clarity, the columns are organized as follows:

- A: ID of each data item or data group.
- B: presence of the data in flow 1 or 10.1.
- C, D, E: cardinalities of the EN16931 standard, of the EN16931 profile (identical except for BT-29 and BT-46, because the description of the EN16931 profile artificially replicated this data to explain its use for filling in SIRET, CODE_ROUTAGE and SIREN of the Single Taxable Entity (for the SELLER)), and the EXTENDED-CTC-FR profile (in E).
- F to J: the name of the data.
- K to M: the Xpaths in UBL and CII (for information, hidden columns).
- N: logical data type
- O and P: field length as required for flow 1, and for flows 2, 8, and 9, i.e., the invoice covered by this document.
- Q: list of codes to be used when the field shall find its value in a list.
- R: implementation indication.
- S and T: description and usage note for the field (taken from EN16931).
- U: applicable management rule for flows 1 and 10.1.
- V to Z: Specific management rules for France applicable to invoices in the minimum base formats (Flows 2, 8, and 9, by rule type).
- AA: rules applicable for B2G in France
- AB and AC: applicable EN16931 standard rules and EXTENDED-CTC-FR profile rule.
- AD: comments, if any.
- AF to AJ: indicates changes to each version
- AN: Indicates whether the data is required at START (DEMARRAGE) or in TARGET (flow 1 or 10.1).
- AP to AR: indicates the presence of the data in each profile.
- AT to BD: applicable management rules, provided in text form.
- BF to BL: management rule applicable to flow 1 or 10.1 (column U) in text.

4.8.2 Sheet "BR-France CTC"

This sheet describes the Management Rules, referencing those that apply to flow 1 from which they may originate, what data they apply to, and what types of invoices or mapping for flow 1 or flow 10. It also contains additional management rules and flow 1 mapping for multi-seller invoices.

The columns are organized as follows:

- Column A: Name of the rule
- Column B: Code for the corresponding Flow 1 or Flow 10 rule (if applicable)
- Column C: Business rule title
- Column D: Description of the business rule

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

- Column E : Title in English
- Column F : Description in English
- Column G: Fields affected by the rule
- Columns H to P: How does the rule apply, to which types of invoices
 - ✓ Flow 2: e-invoicing
 - ✓ Flow 8 outgoing: International B2B sales
 - ✓ Flow 8 incoming: international B2B acquisitions, to which specific French rules do not generally apply (as rules cannot be imposed on invoices issued by non-French companies)
 - ✓ Flow 9: B2C sales
 - ✓ Map Flow 1 or Map Flow 10: mapping rule for building Flow 1 or Flow 10 from the invoice.
 - ✓ Business rule: if the rule requires data other than that on the invoice (for example, to check that the SIREN number is listed in the directory).
 - ✓ Non-verifiable rule: rule provided for reference purposes only but cannot be verified by the schematron or even business processing.
 - ✓ Rule present in schematron
 - ✓ Columns R-AB : tracking changes by version

4.8.3 Sheet "BR-France-CTC-CPRO"

This sheet presents the additional specific rules applicable to B2G invoices, intended for the public sector and the CHORUSPRO platform.

The columns are organized in the same way as in the "BR-France CTC" sheet.

4.8.4 Sheet "BR EN16931 + EXT FR and FX"

This sheet presents the rules of the EN16931 standard and the rules of the EXTENDED-CTC-FR and EXTENDED profiles of Factur-x, which replace some of the rules of the standard on these profiles.

For each rule, the profile(s) to which it applies (including the Factur-x MINIMUM, BASIC WL, BASIC, and EXTENDED profiles) is specified.

Invoices shall therefore first comply with these sets of rules and then, in addition, with the specific rules for France presented in the previous chapter.

The sheet is organized as follows: with 2 tables

- VAT rules table, by VAT category
- Column B: correction indicator by version
 - ✓ Column C: Name of rules
 - ✓ Columns D and E: description of the rules in French and English
 - ✓ Columns G to L: Applicability by profile
 - ✓ Columns N and O: applicable to flow 1, Base and Full profiles
 - ✓ Then by blocks of lines, corresponding to each VAT category
 - Lines 5 to 21: for VAT category "S", with in gray (lines 16 and 17) the rules that apply to the EXTENDED-CTC-FR profile instead of rules BR-S-8 and BR-S-9 to allow for tolerance in the calculation of sums, and

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

in green, the rules that apply to the EXTENDED profile of Factur-x (the same rules but taking into account an additional piece of information in the sums: the amount of logistics service fees).

- Lines 22 to 36: same as for category "Z", zero rate
 - Lines 37 to 51: same for category "E", Exempt
 - Lines 52 to 66: same for category "AE", reverse charge
 - Lines 67 to 83: same for category "K", intra-Community deliveries
 - Lines 84 to 98: same as for category "G", Exports
 - Lines 99 to 117: same as category "O", outside scope
 - Lines 118 to 147: same as for category "L" (IGIC) and "M" (IPSI), not applicable in France
- Table of other rules:
 - ✓ Column Q: Name of rules
 - ✓ Columns R and U: description in French and English
 - ✓ Columns S and V: Context in French and English
 - ✓ Columns T and W: on which fields
 - ✓ Columns Y to AD: application by profile
 - ✓ Columns AF and AG: application on Feed 1, Base and Full profiles
 - ✓ Column AI and beyond: modifications to this table by version. The rules are then grouped by category:
 - BR rules: management rules applicable to a field
 - BR-CO rules: cross-functional conditional rules
 - BR-DEC rules: rules on the number of decimal places
 - BR-CL rules: rules relating to code values to be selected from a list
 - BR-B rules: split payment rules not applicable in France (for Italy)
 - FXEXT rules: Factur-X extension rules on EXTENDED profile extension data
 - Rules BR-CO-04, BR-CO-06, BR-CO-08, BR-CO-10, BR-CO-11, BR-CO-12, BR-CO-13, BR-CO-15, BR-CO-22, and BR-CO-24 are replaced by rules BR-FREXT-CO-04, 06, 08, 10, 11, 12, 13, 15, 22, and 24 for the EXTENDED-CTC-FR profile, and by rules BR-FXEXT-CO-04, BR-FXEXT-CO-06, BR-FXEXT-CO-08, BR-FXEXT-CO-10, BR-FXEXT-CO-11, BR-FXEXT-CO-12, BR-FXEXT-CO-13, BR-FXEXT-CO-15, BR-FXEXT-CO-22, and BR-FXEXT-CO-24 for the Factur-X EXTENDED profile (sum calculation tolerance).
 - Rules BR-22, BR-23, BR-24, BR-26, BR-38, BR-44, and BR-54 are replaced by rules BR-FREXT-BR-22, BR-FREXT-BR-23, BR-FREXT-BR-24, BR-FREXT-BR-26, BR-FREXT-BR-38, BR-FREXT-BR-44, and BR-FREXT-BR-54 for the EXTENDED-CTC-FR profile, and by rules BR-FXEXT-BR-22, BR-FXEXT-BR-23, BR-FXEXT-BR-24, BR-FXEXT-BR-26, BR-FXEXT-BR-38, BR-FXEXT-BR-44, and BR-FXEXT-BR-54 for the Factur-X EXTENDED profile.

4.8.5 Sheet "Codelists for XML Fx - 15 05 26"

This sheet provides the various lists of applicable codes as of November 2025, including those that apply to certain extension fields, mainly on data from the Factur-X EXTENDED profile in UN/CEFACT CII.

The lists are organized by column groups, with the fields to which they apply and the link to the corresponding list in the header.

In particular, VATEX codes (reasons for VAT exemption) are in columns AX to BA, with all codes dedicated to French regulations at the bottom of the list.

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

Please note that when codes apply to extensions, the coding of the fields in the Factur-X EXTENDED profile in CII is used, as it already exists (see Sheet CII D22B & FX EXT-CTC-FR) and because these fields are not included in the EXTENDED-CTC-FR profile.

NOTE: There are two versions of the XSD for UN/CEFACT CII: a "coupled" version—linked to the standard UN/CEFACT code lists—and an "uncoupled" version, where this link to the code lists is not present. Since the EN 16931 standard made different choices regarding the use of certain code lists (and sometimes restricted the list of usable codes), the "uncoupled" version must be used; code list validation is performed via the Schematron files published alongside the EN 16931 standard.

4.8.6 Sheets "Flux 2 UBL EN16931 FR" and "Flux 2 UBL EXT-CTC-FR"

These sheets describe the two profiles EN16931 and EXTENDED-CTC-FR in UBL, i.e. by describing the structure of the UBL restricted to the fields necessary to implement the two profiles, in the order of the message (since the data shall be presented according to a strictly defined tree structure, including the order of data at the same level).

These sheets describe the INVOICE message (columns B to AT), then the CREDIT NOTE message (columns AV to CN). Some lines are highlighted in orange to align the INVOICE and CREDIT NOTE structures, which are very similar but not identical.

The columns are organized as follows for the INVOICE message (and then in the same way for the CREDIT NOTE message):

- Column B: ID of the data from the UBL profile implementation (with some structure IDs linked to the UBL implementation).
- Column C: Data ID in the French semantic model (see "FE EN16931 + EXTENDED" sheet).
- Column F: UBL tree level (different from that of the EN16931 standard, as the UBL tree is not the same as that of the EN16931 standard). This is what allows the UBL data tree to be represented, with the cardinality in column G.
- Column G: cardinality of the data for the profile (corresponding to the profile of each leaf), which implicitly includes a management rule when it differs from the cardinality of the complete UBL message in column AR. For example, if the UBL cardinality is 0..n (column AR) and that of column G is 1..1, this means that the data is no longer optional and repeatable, but mandatory and present only once. This can be implemented either by creating a dedicated xsd or through a management rule described in a schematron (which will state that the data SHALL be present once and only once).
- Column H: Name of the data taken from the semantic model of the "FE EN16931 + EXTENDED" sheet.
- Column I: UBL Xpath.
- Columns J to AB: contain the information from columns M to AC of the semantic description (sheet "FE EN16931 + EXTENDED").
- Columns AD and AE: line belongs to Flow 1 (allows filtering), Base and Full profiles.
- Columns AG to AT: description of the UBL mapping:
 - ✓ Column AG: name of the term in the Standard field.
 - ✓ Column AH: description of the data (EN16931 standard).
 - ✓ Column AI: Note on data usage (EN16931 standard).
 - ✓ Column AJ: ChorusPro CIUS rules (for reference and information).
 - ✓ Column AK: applicable EN16931 standard rules, as well as some PEPPOLBIS 3.0 rules, for information.
 - ✓ Column AL: data type.

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

- ✓ Column AM: cardinality of the UBL model of the EN16931 profile (source of column G for the EN16931 profile).
- ✓ Column AN: cardinality of the UBL model of the EXTENDED-CTC-FR profile (source of column G for the EXTENDED-CTC-FR profile).
- ✓ Columns AO and AP = Xpath, in deployed or in line presentation.
- ✓ Column AR: Cardinality of the complete UBL message (indicates the potential for evolution for the profile, if applicable).
- ✓ AS and AT columns: mapping information from the standard.

In UBL, there is one message for invoices (INVOICE) and another for credit notes (CREDIT NOTE). The description therefore continues in the other columns in the same way for the CREDIT NOTE message.

The CR columns and following indicate the changes made by the different versions.

This description could lead to the creation of an xsd dedicated to each profile, restricting the data tree to what is strictly necessary. In practice, the restriction is made through the schematron application of the EN16931 standard for this profile. This involves adding a large number of rules to the schematron, named "UBL-CR-XXX."

The corresponding schematrons for the EN16931 profile can be found at [THIS LINK](#). Reading the file "EN16931-UBL-validation-preprocessed.sch" allows you to see all of these syntax rules, which, for the most part, consist of disabling certain branches or leaves of the UBL INVOICE data tree, do not prevent the invoice from being considered valid when these rules are set to "warning" rather than "fatal".

4.8.7 Leaves "FACTUR-X BASIC WL FR," "CII D22B & FX EN16931 FR," and "CII D22B & FX EXT-CTC-FR)


These sheets describe the three profiles BASIC WL (only for Factur-X), EN16931 and EXTENDED-CTC-FR in UN/CEFACT CII, whether in a structured invoice file or as part of Factur-X (attached file factur-x.xml). This describes the structure of the UN/CEFACT CII message restricted to the fields necessary to implement the three profiles, in the order of the message (since the data shall be presented according to a strictly defined tree, including the order of data at the same level).

These sheets describe the Invoice message: CII (meaning Cross Industry Invoice), bearing in mind that in UN/CEFACT CII, CREDITS and all types of invoices are coded according to this CII message (there is no dedicated CREDIT NOTE message as in UBL).


The message structure is common to all supply chain messages in the UN/CEFACT SCRDM (Supply Chain Reference Data Model), of which CII is one of the messages (along with CIO for the ORDER message, for example).

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

It is organized as follows (abridged version, then more detailed):



PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France



PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

This gives the following structure, which is more tree-like than the EN16931 standard and UBL:

- **rsm:ExchangedDocumentContext:** Message identification block (Context), which contains information defining the underlying process (BT-23), then the message profile (BT-24), for example urn:cen.eu:en16931:2017 for the EN16931 profile
- **rsm:ExchangedDocument:** Header block of the message, which contains information about the message itself with the invoice number (BT-1), then its type code (BT-3), then its issue date (BT-2), then the notes (BG-1).
- **rsm:SupplyChainTradeTransaction:** Block containing commercial transaction information, body of the invoice, itself composed of:
 - ✓ **ram:IncludedSupplyChainTradeLineItem:** Line block, which provides all line information, itself grouped into subgroups structured like the message body.
 - ✓ **ram:ApplicableHeaderTradeAgreement:** Block identifying the Parties and references to the transaction, which contains all references and Parties to the exchange, except those relating to the invoice itself and payment.
 - ✓ **ram:ApplicableHeaderTradeDelivery:** Block identifying delivery information
 - ✓ **ram:ApplicableHeaderTradeSettlement:** Block containing information on the terms of the agreement, i.e. the parties involved in invoicing and payment (Invoicer, Invoicee, Payee, Payer), as well as Document-level allowances and charges, VAT footer, payment details and totals.

The Excel file presents the message by describing the tree from top to bottom, branch by branch, leaf by leaf. The columns in the Excel presentation are organized as follows for the UN/CEFACT CII message:

- Column B: CII block codes, which show the general structure of the message (see above), with color codes illustrating the structure of the message
- Column C: IDs of the data from the UN/CEFACT CII profile implementation. This contains the IDs from the semantic standard, with a few suffixes added to identify additional structural elements. For extension data, the Factur-X EXTENDED profile nomenclature is used (as it already exists).
- Column D: Data ID in the French semantic model, with the corresponding extension data nomenclature (see sheet "FE EN16931 + EXTENDED").
- Column E: tree level in UN/CEFACT CII (different from that of the EN16931 standard, as the CII tree is not the same as that of the EN16931 standard). This is what allows the UN/CEFACT CII data tree to be represented, with the cardinality in columns F, G and AS.
- Columns F and G: data cardinalities for BASIC WL and EN16931 profiles (column F) and EXTENDED-CTC-FR and EXTENDED profiles in Factur-X (column G), which implicitly includes a management rule when it differs from the cardinality of the complete UN/CEFACT CII message in column AS. For example, if the UN/CEFACT CII cardinality is 0..n (column AS) and that of column G is 1..1, this means that the data is no longer optional and repeatable, but mandatory and present only once. This can be implemented either by creating a dedicated xsd or through a management rule described in a schematron (which will state that the data SHALL be present once and only once).
- Column H: Name of the data taken from the semantic model of the "FE EN16931 + EXTENDED" sheet.
- Column I: UN/CEFACT CII Xpath.
- Columns J to AB: contain the information from columns M to AC of the semantic description (sheet "FE EN16931 + EXTENDED").
- Columns AD and AE: line belongs to Flow 1 (allows filtering), Base and Full profiles.
- Columns AG to AU: description of the UN/CEFACT CII mapping:
 - ✓ Column AG: name of the term in the Standard field.

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

- ✓ Column AH: description of the data (EN16931 standard).
- ✓ Column AI: Note on data usage (EN16931 standard).
- ✓ Column AJ: ChorusPro CIUS rules (for reference and information).
- ✓ Column AK: applicable EN16931 standard rules, as well as some PEPPOLBIS 3.0 rules, for information.
- ✓ Column AL: data type.
- ✓ Column AM: cardinality of the UN/CEFACT CII model for the BASIC WL (Factur-X) and EN16931 profiles, source of column F for these profiles.
- ✓ Column AN: cardinality of the UN/CEFACT CII model for the EXTENDED-CTC-FR and EXTENDED (Invoice-X) profiles, source of column G for the EXTENDED-CTC-FR profile.
- ✓ Columns AO and AP = Xpath, in both deployed or in line presentations.
- ✓ Column AS: Cardinality of the complete UN/CEFACT CII message (indicates the potential for evolution for the profile, if applicable).
- ✓ Columns AT and AU: mapping information from the Standard.
- Columns AX to BC: indicate which description lines belong to which profile, providing an overview of each profile through simple filtering.
- Columns BE and BF: give the Factur-x profile, which is organized into nested dolls: MINIMUM, then BASIC WL, then BASIC, then EN16931, then EXTENDED. The BF column gives a more detailed breakdown of the EXTENDED profile by inserting the EXTENDED-CTC-FR profile.
- Columns BL to CP: exactly the same as columns AG to BF, but in English.
- Columns CR and following: indicate the changes made by the different versions.

This description can lead to the creation of an xsd dedicated to each profile, restricting the data tree to what is strictly necessary. This is what has been done for each Factur-X profile (see [this page](#) for the latest version of the documentation and the associated xsd and schematrons descriptions).

For the implementation of the EN16931 standard profile alone, the tools proposed by the European Commission are based on the complete UN/CEFACT CII D16B message, to which an application schematron is applied. This involves adding a large number of rules to the schematron, named "CII-SR-XXX" or "CII-DT-XXX."

The corresponding schematrons for the EN16931 profile can be found at [THIS LINK](#). Reading the file "EN16931-CII-validation-preprocessed.sch" allows you to see all of these syntax rules, which, most of which consisting of disabling certain branches or leaves of the UN/CEFACT CII data tree, do not prevent the invoice from being considered valid when these rules are set to "warning" mode rather than "fatal" mode.

In this description, the pink lines correspond to data from the EXTENDED-CTC-FR profile (and therefore also EXTENDED from Factur-X). The gray lines, which vary in shade, represent the level of the UN/CEFACT CII structure (the darker the color, the closer the level is to the root).

4.8.8 Sheets "FE - Flow 1," "Flow 1 UBL," and "Flow 1 CII"

These sheets describe flow 1 in three ways:

- Sheet "FE - Flow 1": the description of Flow 1 in semantic model, as published in version 3.1 of the external specifications. In columns W to AC, the applicable management rules from the external specifications 3.1 are provided in text on each line.
- Sheet "Flow 1 UBL": the description of Flow 1 in UBL based on filtering the "CII D22B & FX EXT-CTC-FR" sheet on the FLOW 1 TARGET data (column AE), to which the Document level charges have been added (as they will be).

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

- "Flow 1 CII" sheet: the description of Flow 1 in UN/CEFACT based on filtering the "Flow 2 UBL EXT-CTC-FR" sheet on the FLOW 1 TARGET data (AF column), to which the Document level charges have been added (as they will be).

4.8.9 Sheet "E-REPORTING - Flow 10"

This is the description sheet for flow 10 published in the external specifications 3.1, supplemented by the correspondence with the semantic model data for flow 10.1, provided in column S.

This version has been enhanced with the TG-2 block (TT-5 and TT-6), available only for exchanges between taxpayers and their "Plateforme Agréée" and authorizing the transmission of additional or corrective flow 10, enabling the Accredited Platform to create an aggregated flow 10 as expected by the PPF Data Concentrator.

4.8.10 Sheet "Flux F11 – Annuaire"

This is a description sheet for an XML message intended to enable an Accredited Platform ("Plateforme Agréée") to transmit the publishable data from the "PPF Annuaire" to its customers who are subject to and affected by the Electronic Invoicing Reform in France. This can also be achieved in a more targeted manner through the use of the "Directory API" described in the XP Z12-013 standard.

4.8.11 Sheet "Management Rules 3.2"

Reminder of the management rules (Annex 7), published in the external specifications 3.2.

5 The Life cycle Message – CDAR

The life cycle message is implemented in UN/CEFACT CDAR (Cross Domain Application and Response). It allows information about one or more messages received to be transmitted, both to provide information on successful transmission and on whether or not the message has been processed correctly. In exchanges between «Plateformes Agréées» (PA, Accredited Platform) and the PPF, it is used for all types of business flows or objects exchanged.

This document describes its use solely for exchanging life cycle information on invoice messages between «Plateformes Agréées» (PA) and with end users. This use may differ from that required by the PPF, including for mandatory status messages (mainly concerning message header management).

5.1 Description of the CDAR message structure to be used

The CDAR D22B message is available in its entirety

- **at the link**
<https://unece.org/trade/documents/2024/12/standards/cross-domain-acknowledgement-and-response-d22b>
for its xsd description
- **and at the link**
<https://unece.org/trade/documents/2020/06/standards/cross-domain-application-error-and-acknowledgement-process-brs>
for the English description document on how to use this message.

The management of the life cycle between the SELLER and the BUYER is broken down into two phases:

- The transmission phase, which aims to track the progress of the invoice from the moment it is issued until it is received by the recipient. In this phase, statuses are created by the «Plateformes Agréées» (PA) for their customers and the «Plateformes Agréées» (PA) of their counterpart (and for statuses classified as "Mandatory," they are also transmitted to the PPF).
- The processing phase, which aims to ensure that the SELLER and the BUYER exchange statuses on the invoice life cycle. These statuses are then created by the SELLER or the BUYER and are intended to be forwarded to the counterparty via the «Plateformes Agréées» (PA) without being modified (like invoices).


There is no provision or requirement to send status messages confirming the successful receipt of status messages.

However, it will be necessary to specify whether the status message relates to the transmission or processing phase, as this will have an impact on the creation of the message header.

In general, the identity of the «Plateformes Agréées» (PA) used by a company does not have to be disclosed to third parties. Therefore, «Plateformes Agréées» (PA) do not have to be identified in life cycle messages that are intended to be shared end-to-end.

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

The diagram below illustrates the life cycle and the different types of statuses:




Life cycle status messages are intended to be used for three distinct purposes:

- To provide information on the transmission and processing status, indicating any errors detected and actions expected.
- To take action on the process or use case by indicating changes in the situation, for example, the factoring of an invoice, the need to pay to a bank account other than the one indicated on the invoice, or, where applicable, to provide additional information that has been omitted or is required for processing.
- Communicate information relating to payment or payment received, the execution of a discount, partial approval, in short, indicate different amounts for different situations.

To do this, the life cycle message is illustrated by the diagram below, which shows the useful structure of the message in its header (some data from the complete message that is not used has been excluded to simplify reading). The bold lines indicate mandatory cardinality (minimum 1..1), and in the case of repeatability, cardinality 0..∞ or 1..∞ is indicated.

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France



Its structure is therefore as follows:

- An "Exchange Document Context" header block, which contains the CDAR message profile.
- An "Exchange Document" header block, which essentially identifies the Parties: who creates, who transmits, and for whom is it intended?
- An "Acknowledgement" block, which is mandatory and repeatable (cardinality 0..n), but which will only be used once per CDAR message.
This block itself contains a mandatory and repeatable "Document" block (below), which allows a CDAR message to be shared between several Documents, although this will not generally be implemented. This "Acknowledgement" block therefore contains (see description below for the rest of the structure in the scheme):
 - ✓ A "Document" block, which corresponds to the invoice that is the subject of the life cycle message, which itself contains:
 - A "status detail" block, which is optional and repeatable (cardinality 0..n), used to explain any errors found or provide additional information, and which contains:
 - A "Characteristic" block, which is optional and repeatable (cardinality 0..n), dedicated to providing information on data to be modified or in error, to be e-reported, or to qualify certain statuses (e.g., amount approved or paid).


This reflects the usual structure of UN/CEFACT messages, namely (the codes are those used in the description in the Life Cycle of External Specifications 3.1 annex):

- A context block (**MDB-1**), which identifies a message profile to which an xsd and a schematron will be attached for any specific management rules (equivalent to BT-23 and BT-24 for invoices).
- A message header block (**MDB-2**) consisting of:
 - ✓ **MDT-4** (ID): a message identifier (life cycle message number).

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

- ✓ **MDT-5** (Name): a message name.
- ✓ **MDG-4** (IssueDateTime): a date and time when the life cycle message was created.
- ✓ **MDT-9** (LanguageID): a message language (French or English).
- ✓ **MDG-9** (SenderTradeParty): a party responsible for transmitting the message ("Sender"): in our context:
 - For the transmission phase, these are the "Plateformes Agréées" (PA), which will only be identified by the role code ("WK") in **MDT-21**.
 - For the processing phase, these will be users (BUYER or SELLER, or certain third parties).
- ✓ **MDG-16** (IssuerTradeParty): a Party originating the message (i.e., at the time of creation: "Issuer"): in our context:
 - For the transmission phase, these are "Plateformes Agréées" (PA), which will only be identified by the role code ("WK") in **MDT-40**.
 - For the processing phase, these will be users (BUYER or SELLER, or certain third parties).
- ✓ **MDG-23** (Recipient): one or more parties receiving the status message ("Recipient"): these are the end users.
- An "Acknowledgement" block (**MDB-03**), which can be multiple in CDAR D22B, but which will be used in cardinality 1..1, composed of the following elements:
 - ✓ **MDT-74** (MultipleReferencesIndicator): an indicator used to specify whether the block is for multiple Documents or a single Document. By default, status messages will be for a single document. There may be exceptions for certain use cases requiring a status for two or more linked invoices, on an exceptional basis.
 - ✓ **MDT-75** (ID): a number, if necessary.
 - ✓ **MDT-77** (TypeCode): a type code that distinguishes a transmission phase status (**305**) from a processing phase status (**23**).
 - ✓ **MDT-75** (Name): a name.
 - ✓ **MDG-31** (IssueDateTime): a date and time when the event that is the subject of the status was created.
 - ✓ **MDG-32** (ReferenceReferencedDocument): the document to which the status relates: in this case, the invoice.


PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France



Next, the Document block (MDG-32) consists of the following elements:

- **MDT-87**: the invoice number.
- **MDT-88** (StatusCode): a standard status code, i.e. from a standard UNTDID 1373 list; the values are detailed in the Excel file and in the management rules. This is an optional status, but should be used in particular for international invoices, and in line with the specific status code of the reform (in **MDT-105**).
- **MDT-91** (Typecode): invoice type code (380, 381, etc.).
- **MDT-94**: name of the invoice (if applicable).
- **MDG-34**: date and time of receipt of the invoice. For transmission statuses, this is the date and time at which the «Plateformes Agréées» (PA) that created the message recorded the invoice (as sent or received, respectively). For processing statuses, this is the date and time when the invoice was received by the recipient or was given the status "Submitted" by the issuer.
- **MDT-96**: attachment, useful when an invoice needs to be supplemented with an additional document, and in certain cases, this also allows invoices to be attached (for example, a direct payment request in the case of subcontracting with direct payment).
- **MDT-97** (ReferenceTypeCode): Reference type code, to be selected from the UNTDID 1153 list (not normally used)
- **MDG-35** (FormattedIssueDateTime): invoice date (allows the invoice to be uniquely identified)
- **MDT-104** (Status): status description provided as a code in **MDT-88**.
- **MDT-105** (ProcessConditionCode): status code as defined by the reform (200 to 213 for invoices at present).
- **MDT-106** (ProcessCondition): text status corresponding to the code in MDT-105.

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France




- **MDG-40** (IssuerTradeParty): ALWAYS identifies the SELLER, which allows the invoice to be uniquely identified (number, date, and SIREN number of the Seller).
- **MDG-41** (RecipientTradeParty): by convention, allows a new Payee to be named in the event of Factoring.
- **MDG-42** (SenderTradeParty): not used
- **MDG-37** (SpecifiedDocumentStatus): Block used to provide details on the status (and potentially several, since this is a 0..n cardinality).

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

The status detail block (**MDG-37**) can then be detailed:


- **MDG-38**: date and time of the status. To be used in the case of a Life Cycle Message transmitting a history of life cycle statuses. Otherwise, the date and time of the status is already provided in **MDG-31**.
- **MDT-111** (ConditionCode): To be used in the case of a Life Cycle Message transmitting a history of life cycle statuses, corresponds to the standard status code provided in **MDT-88**.



- **MDT-113** (ReasonCode): allows the reason for the status to be entered as a code, to be selected from a list.
- **MDT-114** (Reason): allows the reason to be entered as text.
- **MDT-112** (Condition): status description entered in MDT-111, only if a status history is provided.
- **MDT-115** (ProcessConditionCode): To be used in the case of a Life Cycle Message transmitting a life cycle status history, corresponds to the reform status code (such as **MDT-105**).
- **MDT-116** (ProcessCondition): To be used in the case of a Life Cycle Message transmitting a history of life cycle statuses, corresponds to **MDT-115**, in text.
- **MDT-121** (RequestedActionCode): Action requested in code (for example, waiting for a CREDIT NOTE).
- **MDT-122** (RequestedAction): Action expected in text.

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

- **MDT-124-2** (SequenceNumeric): Allows a number to be given to each Status Detail record.
- **MDG-39** (IncludedNote): Note, with a subject code and text. Allows free text to be entered for comments.
- **MDG-43** (SpecifiedDocumentCharacteristic): Repeatable information block providing data necessary for the status, consisting of the following elements:



- ✓ **MDT-206** (ID): code of the data to which the status detail relates (BT-84 for an IBAN, for example).
- ✓ **MDT-207** (TypeCode): Code used to qualify how the block will be used, see rule BR-FR-CDV-CL-11.
- ✓ **MDT-208** (ValueChangeIndicator): indicates whether a value change is being proposed or requested (e.g., IBAN number following factoring).
- ✓ **MDT-211** (Name): Name of the data referenced in MDT-206 (e.g., IBAN).

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

- ✓ **MDT-212** (Description): Description of the data (if necessary).
- ✓ **MDT-213** (Location): Xpath of the data concerned in the invoice message.
- ✓ **MDT-214** (Value): New value to be taken into account, if it is text data.
- ✓ **MDT-215** (ValueAmount): Amount value when an amount needs to be referenced. In particular for an amount to be e-reported; a payment amount, an invoice approval amount, etc.
- ✓ **MDT-217** (ValueMeasure): Used to indicate an expected unit of measurement value.
- ✓ **MDT-218** (ValueDateTime): used to indicate an expected date and/or time value.
- ✓ **MDT-221** (ValueCode): used to indicate an expected code value.
- ✓ **MDT-222** (ValueQuantity): used to indicate an expected quantity value.
- ✓ **MDT-223** (ValueNumeric): used to indicate an expected value of type Numeric.
- ✓ **MDT-224** (ValuePercent): used to indicate an expected percentage value and, when used for e-reporting of receipts, the VAT rate applicable to the amount received is expressed here.

5.2 Applicable management rules

The table below lists the management rules applicable to CDAR messages for the exchange of invoice life cycle statuses. These are mainly rules that make optional data mandatory in the CDAR message or code list rules to be followed, depending on the message type (processing or transmission phase).

BR CODE	Title	Description	Applies to
BR-FR-04	Invoice code type	The document type codes for an invoice are as follows: Simple invoices: - Commercial invoice (380) - Self-billed invoice (389) - Factored invoice (393) - Self-billed factored invoice (501) (*) Pre-payment invoices: - pre-payment invoice (386) - Self-billed pre-payment invoice (500) (*) Corrected invoices: - Corrected invoice (384) - Self-billed corrected invoice (471) (*) - Factored corrected invoice (472) (*) - Factored self-billed corrected invoice (473) (*) Credit notes: - Self-billed credit note (261) - Credit note for Global Allowance (262) - Credit note (381) - Factored credit note (396) - Factored self-billed credit note (502) (*) - Pre-payment Credit note (503) (*) Other types of invoices defined in the standard (UNTDID 1001) shall not be used. /!\: (*) Awaiting integration of codes by EN16931 maintenance	MDT-91
BR-FR-CDV-01	Mandatory data	MDG-3(and therefore MDG-3) is mandatory	MDG-3
BR-FR-CDV-02	Mandatory	MDT-3 shall be equal to urn.cpro.gouv.fr:1p0:CDV:invoice For the CDV sent to the PPF, this data shall be equal to urn.cpro.gouv.fr:1p0:CDV:einvoicingF2	MDT-3

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

BR CODE	Title	Description	Applies to
BR-FR-CDV-03	Mandatory data	MDT-4 is mandatory	MDT-4
BR-FR-CDV-04	Mandatory	MDG-4 is mandatory	MDG-4
BR-FR-CDV-05	Mandatory	MDG-9 is mandatory	MDG-9
BR-FR-CDV-06	Mandatory	MDT-21 is mandatory	MDT-21
BR-FR-CDV-07	Legal ID of the CDV recipient	IF MDT-77 is equal to 23 THEN MDT-38 is mandatory This is the ID (legal, private) of the person setting the status IF MDT-77 is equal to 305 THEN MDT-38 is not filled in	MDT-38
BR-FR-CDV-08	Electronic address of the CDV recipient	if MDT-59 IS DIFFERENT from WK, MDT-73 is mandatory	MDT-73
BR-FR-CDV-09	CDV Transmission or Processing	MDT-77 is MANDATORY and shall be equal to 23 or 305	MDT-77
BR-FR-CDV-10	Unique invoice identifier: Invoice ID	MDT-87 (Identifier of the document subject to the CDV) is MANDATORY In case of INADMISSIBLE status (MDT-105 = 501), MDT-87 is the name of the inadmissible file	MDT-87
BR-FR-CDV-11	Unique invoice identifier: Invoice date	MDG-35 is MANDATORY unless MDT-105 = 501 (UNACCEPTABLE : "IRRECEVABLE")	MDG-35
BR-FR-CDV-12	Mandatory data	MDT-105 is MANDATORY	MDT-105
BR-FR-CDV-13	Mandatory data	MDT-129 is MANDATORY unless MDT-105 = 501 (UNACCEPTABLE : "IRRECEVABLE") If present, at least one value must correspond to the SELLER's legal identifier as it appears in the invoice in BT-30.	MDT-129
BR-FR-CDV-14	Status Cashed	If the status is "Collected" (MDT-105 = 212), THEN there shall be at least 1 MDG-43 Block with a value of MDT-207 = MEN and all MDG-43 blocks with an MDT-207 value of "MEN" must contain an MDT-215 value (Amount) and an MDT-224 value (VAT percentage).	MDT-207
BR-FR-CDV-15	Mandatory reasons	The status REASON (MDT-113) is mandatory for the statuses Rejected (213), Refused (210), Disputed (207), Partially Approved (206), Suspended (208), and Inadmissible (501).	MDT-113
BR-FR-CDV-16	Incremental status detail number	The incremental status detail number (MDT-124-2) is mandatory if a status detail (MDG-37) is present.	MDT-124-2
BR-FR-CDV-CL-01	Listed data	MDT-2 is in the list below: - REGULATED - NON_REGULATED - B2C - B2CINT - B2BINT - OUTOFSCOPE REGULATED indicates that the invoice falls under the scope of the French electronic invoicing reform. NON_REGULATED indicates the opposite. B2C, B2CINT, B2BINT, and OUTOFSCOPE allow for the specification of the NON_REGULATED type. B2G indicates that the underlying invoice falls under B2G, allowing for the application of B2G-specific rules.	MDT-2

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

BR CODE	Title	Description	Applies to
		This data is not transmitted in CDVs sent to the PPF (for the mandatory statuses "Filed," "Rejected," "Refused," "Cashed"), since only regulated flows (e-invoicing) are subject to CDVs sent to the PPF ((thus corresponding only to the value "REGULATED"))..	
BR-FR-CDV-CL-02	Code Role of the CDV sender	If the status (MDT-77) is equal to 305, then MDT-21 SHALL be equal to WK. If the status (MDT-77) is equal to 23, then MDT-21 SHALL be in the following list: (extract from UNCL 3035): BY: Buyer; AB: Buyer's representative for the sale. DL: Factor SE: Seller AB: Buyer's agent SR: Seller's agent WK: Platform or dematerialization operator (of the supplier/seller or buyer) =; «Plateformes Agréées» (PA) or other PE: Payee PR: Payer II: INVOICER (Invoice issuer) IV: INVOICEE	MDT-21
BR-FR-CDV-CL-03	CDV Issuer Role Code	If the status (MDT-77) is equal to 305, then MDT-40 SHALL be equal to WK If the status (MDT-77) is equal to 23, then MDT-40 is in the following list: (extract from UNCL 3035) BY: Buyer; AB: Buyer's representative for the sale. DL: Factor SE: Seller AB: Buyer's agent SR: Seller's agent PE: Payee PR: Payer II: INVOICER IV: INVOICEE	MDT-40
BR-FR-CDV-CL-04	Role code of the CDV recipient	MDT-59 SHALL BE in the following list: (Extract from UNCL 3035) BY: Buyer; AB: Buyer's representative for the sale. DL: Factor SE: Seller AB: Buyer's agent SR: Seller's agent PE: Payee PR: Payer II: INVOICER IV: INVOICEE WK: Platform or dematerialization operator (of the supplier/seller or buyer)	MDT-59

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

BR CODE	Title	Description	Applies to
BR-FR-CDV-CL-05	Standard Status Code (UNTDID 1373)	MDT-88 SHALL BE in the UNTDID 1373 list, with the following correspondences for MDT-105 statuses Transmission phase: MDT-77 = 305 •10 (Document valid): Submitted •51: Issued •43: Received •8: Rejected •48: Acknowledged = Made available Processing phase: MDT-77 = 23 • 45 (In Process) = Handled • 39 (on hold) = Suspended • 37 (Complete) = Completed • 50 (Rejected/Refused) = Refused (by C4) • 49 (Conditionally accepted) = Partially approved • 47 (Paid) = Payment Sent AND Received • 46 (Under Query) = Under dispute • 1 (accepted) = Approved • 5 (Information only) = for all other statuses	MDT-88
BR-FR-CDV-CL-06	Reform Status Code	MDT-105 and MDT-115 are in the list of Invoice Status Codes	MDT-105, MDT-115
BR-FR-CDV-CL-07	Seller Type Code	MDT-132 SHALL BE equal to SE: Seller	MDT-132
BR-FR-CDV-CL-08	Invoice Recipient Role Code (New Payee)	MDT-158 SHALL BE in the list below: (Extract from UNCL 3035) BY: Buyer; AB: Buyer's representative for the sale. DL: Factor SE: Seller AB: Buyer's agent SR: Seller's agent WK: Platform or dematerialization operator (of the supplier/seller or buyer); DFH: For the PPF PE: Payee PR: Payer II: INVOICER IV: INVOICEE	MDT-158
BR-FR-CDV-CL-09	Status REASON code	MDT-113 is in the list of Status Reason Codes "Refused B2G" status reasons must only be accepted for B2G invoices where MDT-19 (with MDT-18 = "0238") is equal to "9999".	MDT-113
BR-FR-CDV-CL-10	ACTION required code	MDT-121 is in the list of Invoice Action Codes	MDT-121

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

BR CODE	Title	Description	Applies to
BR-FR-CDV-CL-11	Item code MDG-43	MDT-207 is in the following list (to be completed): - MEN: Amount collected (including tax) - MPA: Amount paid - RAP: Amount remaining to be paid (in case of partial payment); - ESC: Discount granted; - RAB: Rebate granted; - REM: Allowance granted. - MAP: amount without VAT approved - MAPTTC: amount with VAT approved - MNA: Amount without VAT NOT approved - MNATTC: Amount with VAT not approved - CBB: Payee bank details to be modified - DIV: INVALID data - DVA: VALID data expected - MAJ: Data to be used instead of that shown on the invoice for processing (status "Completed" or "Additional information")	MDT-207

5.3 Reasons for life cycle statuses.

Some statuses have restricted lists of reasons, particularly those that result in automatic cancellation of invoices: statuses "Rejected on issue," "Rejected on receipt," and "Refused."

The list of these statuses is provided in the "STATUS reasons table" sheet, along with their descriptions.

A "NON_TRANSMISE" (NOT TRANSMITTED) reason has been added for the "Submitted" status in cases where an invoice has been processed for transmission and could therefore be given a "Submitted" status, but transmission is not actually possible because the recipient has not chosen an Accredited Platform of the Sender (i.e., because the recipient is present but has not chosen its Accredited Platforme ("Plateforme Agréée") for the reception of its invoices). "Filed" status, but transmission is not actually possible because the recipient has not selected an Accredited Platform for the reception of its invoices (i.e., because the recipient is listed in the directory but does not have an address line associated with an Accredited Platform other than the default platform – registration number 9998).

A list of status reasons for B2G invoices has been added to ensure continuity with existing processes, including certain additional reasons applicable only to B2G (the criterion being the presence of the CPRO ID in MDT-19 (9999) with MDT-18 = 0238).

5.4 Presentation of the annex file for CDAR sheets

The Excel file attached to this document also describes the implementation of the Life Cycle message applied to B2B invoice exchanges through «Plateformes Agréées» (PA).

5.4.1 Sheet "CDV FE – CDAR"

This is the description sheet for the Life Cycle message (CDAR: Cross Domain Acknowledgement & Response). The source is Annex 2 of the external specifications 3.1, to which certain columns have been added:

- Column A: Data ID (from Annex 2 of the external specifications 3.0)
- Column B: the level in the XML structure (0 root, 1, first block, etc.)
- Column C: Cardinality in the CDAR message

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

- Column D (hidden): corrected cardinality for the PPF in Annex 2 of the external specifications 3.0. This will be managed by schematron rules and not by a modification of the xsd cardinality.
- Columns F to I: description of data, by level.
- Column J (and K, hidden): Xpath in expanded view (the single-line view is in column K, hidden)
- Column L: data presence rule: R (Required), O (Optional), I (informative, not used in practice), for exchanges between «Plateformes Agréées» (PA) and PPF, for information only.
- **Column M:** data presence rule: R (Required), O (Optional), I (informative, not used in practice) for exchanges between «Plateformes Agréées» (PA). This column shall be taken into account for the CDV format description. To simplify reading, the sheet has been filtered so as not to show the "I" lines.
- Columns N to R: description of logical types, length required by the PPF, applicable lists, business definition and comments taken from Annex2 of external specifications 3.0
- Columns S to U (hidden): management rules to be applied to the CDV message for PPF ↔ «Plateformes Agréées» (PA) exchanges.
- Column V: Management rule to be applied for the use of the CDV message between «Plateformes Agréées» (PA), subject of this document.
- Column W: text of the management rules in column V
- Column X: filtering to exclude lines from the message that do not need to be used.
- Column Y: comments and tracking of changes.

5.4.2 Sheet "BR-FR-CDV for invoices"

This sheet lists all the management rules applicable to the Life Cycle message for invoice exchanges via «Plateformes Agréées» (PA). Basis for constructing the Schematron to be applied:

- Column B: Management rule code
- Column C: Title of the management rule
- Column D: Description of the management rule
- Column E: Which data in the message does the rule apply to?

5.4.3 Sheet "CDV actors"

This sheet describes, for each status, how to fill in the header of the CDV message so that «Plateformes Agréées» (PA) are not named in the messages. It also specifies who can send the message (role) and who the recipients are.

5.4.4 Sheet "Action codes"

This sheet presents the expected "Action" codes, previously found in the "CDV actors" sheet.

5.4.5 Sheet "STATUS reasons table"

This sheet lists the reasons applicable to statuses:

- Column A: REASON code
- Column B: Reason label

PR XP Z12-012 – Message formats and profiles for invoices and life cycle statuses, constituting the minimum requirements applicable to the Electronic Invoicing Reform in France

- Column C: Description of the REASON and when it can be used
- Columns I to Q: For which statuses the Reason can be used. By filtering, this provides a list of reasons applicable by status
- Columns T and following: indicate the changes made to each version

**Annexe A
(normative)**

Excel description of formats and profiles

XP_Z12-012_Annexe_A_V1.4.xls

**Annexe B
(normative)**

Examples of invoices (flow 2) and CDAR life cycle messages

XP_Z12-012_Annexe_B_V1.4_EN.zip

Bibliography

- [1] External specifications for Electronic Invoice 3.1 - General file - Agency for State Financial Information Technology.
- [2] Electronic Invoice External Specifications – Chorus Pro Document V1.1
- [3] Documentation of the Factur-X format, published by the FNFE-MPE and FeRD, updated every six months on May 15 and November 15 of each year on the website www.fnfe-mpe.org
- [4] AFNOR XP-Z12-014 standard: B2B use cases applicable within the framework of the Electronic Invoicing Reform in France
- [5] AFNOR XP Z12-013 standard: API for interfacing company information systems with Accredited Platforms (API SI/SC/OD ⇔ PA).